332D

DC Voltage Standard

FLUKE®



332D

DC Voltage Standard

Instruction Manual

P/N 353292
April 1972
Rev. 1 3/75

FLUKE®

©1981, John Fluke Mfg. Co., Inc., all rights reserved Litho in U.S.A.

WARRANTY

Notwithstanding any provision of any agreement the following warranty is exclusive:

The JOHN FLUKE MFG. CO., INC., warrants each instrument it manufactures to be free from defects in material and workmanship under normal use and service for the period of 1-year from date of purchase. This warranty extends only to the original purchaser. This warranty shall not apply to fuses, disposable batteries (rechargeable type batteries are warranted for 90-days), or any product or parts which have been subject to misuse, neglect, accident, or abnormal conditions of operations.

In the event of failure of a product covered by this warranty, John Fluke Mfg. Co., Inc., will repair and calibrate an instrument returned to an authorized Service Facility within 1 year of the original purchase; provided the warrantor's examination discloses to its satisfaction that the product was defective. The warrantor may, at its option, replace the product in lieu of repair. With regard to any instrument returned within 1 year of the original purchase, said repairs or replacement will be made without charge. If the failure has been caused by misuse, neglect, accident, or abnormal conditions of operations, repairs will be billed at a nominal cost. In such case, an estimate will be submitted before work is started, if requested.

THE FOREGOING WARRANTY IS IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO ANY IMPLIED WARRANTY OF MERCHANTABILITY, FITNESS, OR ADEQUACY FOR ANY PARTICULAR PURPOSE OR USE. JOHN FLUKE MFG. CO., INC., SHALL NOT BE LIABLE FOR ANY SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, WHETHER IN CONTRACT, TORT, OR OTHERWISE.

If any failure occurs, the following steps should be taken:

1. Notify the JOHN FLUKE MFG. CO., INC., or nearest Service facility, giving full details of the difficulty, and include the model number, type number, and serial number. On receipt of this information, service data, or shipping instructions will be forwarded to you.

2. On receipt of the shipping instructions, forward the instrument, transportation prepaid. Repairs will be made at the Service Facility and the instrument returned, transportation prepaid.

SHIPPING TO MANUFACTURER FOR REPAIR OR ADJUSTMENT

All shipments of JOHN FLUKE MFG. CO., INC., instruments should be made via United Parcel Service or "Best Way"* prepaid. The instrument should be shipped in the original packing carton; or if it is not available, use any suitable container that is rigid and of adequate size. If a substitute container is used, the instrument should be wrapped in paper and surrounded with at least four inches of excelsior or similar shock-absorbing material.

CLAIM FOR DAMAGE IN SHIPMENT TO ORIGINAL PURCHASER

The instrument should be thoroughly inspected immediately upon original delivery to purchaser. All material in the container should be checked against the enclosed packing list. The manufacturer will not be responsible for shortages against the packing sheet unless notified immediately. If the instrument is damaged in any way, a claim should be filed with the carrier immediately. (To obtain a quotation to repair shipment damage, contact the nearest Fluke Technical Center.) Final claim and negotiations with the carrier must be completed by the customer.

The JOHN FLUKE MFG. CO., INC, will be happy to answer all applications or use questions, which will enhance your use of this instrument. Please address your requests or correspondence to: JOHN FLUKE MFG. CO., INC., P.O. BOX C9090, EVERETT, WASHINGTON 98206, ATTN: Sales Dept. For European Customers: Fluke (Holland) B.V., P.O. Box 5053, 5004 EB, Tilburg, The Netherlands.

*For European customers, Air Freight prepaid.

John Fluke Mfg. Co., Inc., P.O. Box C9090, Everett, Washington 98206

Rev. 6/81

Table of Contents

SECTION	TITLE	PAGE
1	**INTRODUCTION AND SPECIFICATIONS**	1-1
	1-1. Introduction	1-1
	1-6. Specifications	1-2
2	**OPERATING INSTRUCTIONS**	2-1
	2-1. Introduction	2-1
	2-3. Claim For Damage In Shipment	2-1
	2-5. Shipping Instructions	2-1
	2-7. Input Power	2-1
	2-9. Rack Mounting Procedures	2-1
	2-11. Controls, Terminals and Indicators	2-2
	2-13. Initial Operation	2-2
	2-14. General	2-2
	2-16. Voltage Trip Setting	2-2
	2-18. Current Limit Setting	2-5
	2-20. Sense Connections	2-5
	2-23. Guard Connection	2-5
	2-25. Operation	2-6
3	**THEORY OF OPERATION**	3-1
	3-1. Introduction	3-1
	3-3. Functional Description	3-1
	3-7. Circuit Descriptions	3-2
	3-8. Voltage Control Circuitry	3-2
	3-30. Pre-Regulation Circuitry	3-4
	3-38. Protection Circuitry	3-5
	3-44. Miscellaneous Circuitry	3-6

(Continued on page ii)

TABLE OF CONTENTS, *continued*

SECTION	TITLE	PAGE
4	MAINTENANCE	4-1
	4-1. Introduction	4-1
	4-3. Service Information	4-1
	4-6. General Maintenance	4-1
	4-7. Maintenance Access	4-1
	4-10. Unique Maintenance Procedures	4-2
	4-14. Fuse Replacement	4-2
	4-16. Lamp Replacement	4-2
	4-18. 115/230V Conversion	4-2
	4-20. Performance Tests	4-2
	4-21. Introduction	4-2
	4-27. DC Output	4-4
	4-32. Meter and Protection Circuits	4-6
	4-36. Calibration	4-7
	4-37. Introduction	4-7
	4-39. Meter Mechanical Zero	4-7
	4-41. Auxiliary Circuits	4-7
	4-48. Voltage Standard Output	4-9
	4-54. Troubleshooting	4-14
	4-57. Resistance Measurements	4-14
	4-59. Standby Power	4-15
	4-61. Auxiliary Supply Voltages	4-15
	4-63. Unijunction Oscillator and Control Amplifier	4-16
	4-67. Pre-Regulator	4-17
	4-69. Series Pass Element	4-18
5	LISTS OF REPLACEABLE PARTS	5-1
	TABLE OF CONTENTS	5-1
	5-1. Introduction	5-2
	5-4. How to Obtain Parts	5-2
	5-7. Use Code Effectivity List	5-2
6	OPTION AND ACCESSORY INFORMATION	6-1
7	GENERAL INFORMATION	7-1
8	SCHEMATIC DIAGRAMS	8-1

List of Illustrations

FIGURE	TITLE	PAGE
1-1.	Model 332D Outline Drawing	1-1
2-1.	Chassis Slide Installation	2-2
2-2.	Controls, Terminals, and Indicators (Sheet 1 of 2)	2-3
2-2.	Controls, Terminals, and Indicators (Sheet 2 of 2)	2-4
2-3.	Nomograph of Voltage Drop Across Load Wires	2-6
2-4.	Guard Connection	2-7
3-1.	Voltage Control Circuitry	3-2
4-1.	115/230 VAC Conversion	4-3
4-2.	Location of Adjustments	4-8
4-3.	Connections for Sample String Linearization	4-12
4-4.	Connections for Range Calibration Checks	4-13
4-5.	Chopper Waveform	4-16
4-6.	Pre-Regulator Q1, Waveform on STDBY/RESET	4-17
4-7.	Pre-Regulator Q1, Waveform on OPR	4-17
4-8.	Waveforms Across Zener Diode	4-18

LIST OF ILLUSTRATIONS, *continued*

FIGURE	TITLE	PAGE
5-1.	DC Voltage Standard (Sheet 1 of 3)	5-4
5-1.	DC Voltage Standard (Sheet 2 of 3)	5-5
5-1.	DC Voltage Standard (Sheet 3 of 3)	5-6
5-2.	Capacitor Printed Circuit Assembly	5-10
5-3	Sample String Printed Circuit Assembly	5-13
5-4.	Capacitor Switch Printed Circuit Assembly	5-14
5-5.	Range Calibration Printed Circuit Assembly	5-15
5-6.	Main Mother Board Printed Circuit Assembly	5-16
5-7.	Reference Supply Printed Circuit Assembly	5-18
5-8.	Series Pass Driver Printed Circuit Assembly	5-20
5-9.	Differential Amplifier Printed Circuit Assembly	5-24
5-10.	Chopper Amplifier Printed Circuit Assembly	5-28
5-11.	Auxiliary Power Supply Printed Circuit Assembly	5-30
5-12.	Current Limiter Printed Circuit Assembly	5-32
5-13.	Time Delay Printed Circuit Assembly	5-35
5-14.	High Voltage Mother Board Printed Circuit Assembly	5-36
5-15.	Series Pass Element Printed Circuit Assembly	5-38
5-16.	Pre-Regulator Printed Circuit Assembly	5-42
8-1.	DC Voltage Standard (332B-1001)	8-3
8-2.	Support Module Assemblies (332B-1002)	8-9
8-3.	A2 Sample String (332B-1003)	8-13
8-4.	Power Distribution Assemblies (332B-1004)	8-15

List of Tables

TABLE	TITLE	PAGE
4-1.	Test and Calibration Equipment Required (Sheet 1 of 2)	4-3
4-1.	Test and Calibration Equipment Required (Sheet 2 of 2)	4-4
4-2	Control Settings, Load Requirements, and Limits for Line Regulation	4-5
4-3.	Control Settings, Load Requirements, and Limits for Load Regulation	4-5
4-4.	Control Settings for V-I Monitor Test	4-6
4-5.	Control Settings for Voltage Trip Check	4-6
4-6.	Control Settings for Voltage Monitor Linearity Check	4-9
4-7.	Control Settings for Trip Range Check	4-9
4-8.	Sample String Pre-linearization	4-10
4-9.	Preliminary Range Calibration	4-10
4-10.	Control Settings for Voltage Monitor Linearity Check	4-11
4-11.	Control Settings for Trip Range Check	4-11
4-12.	Final Linearization of Deck C, B and A	4-12
4-13.	Final Range Calibration	4-13
4-14.	Control Settings and Tolerances for Calibration Check	4-14
4-15.	Reference and Auxiliary Voltages	4-16
4-16.	Series Pass Element Voltage Checks	4-18
7-1.	List of Abbreviations	7-1
7-2.	Federal Supply Codes for Manufacturers	7-3
7-3.	Fluke Technical Service Centers	7-10
7-4.	Sales Representatives - Domestic	7-11
7-5.	Sales Representatives - International	7-13

Section 1

Introduction & Specifications

1-1. INTRODUCTION

1-2. The Model 332D DC Voltage Standard provides dc voltages from 0 to 1111 volts with an accuracy of ±0.001%. Output current is rated at 0 to 50 milliamperes. The output voltage is set by seven in-line decade switches. Separate terminals are provided for sensing the output voltage directly at the load, thereby eliminating errors due to voltage drop in connecting wires between the instrument and load.

1-3. Protection against possible equipment failures or operator errors, which might damage expensive instruments, are incorporated. The VOLTAGE TRIP and VERNIER controls provide a means of limiting the output voltage within the selected range. Should the output voltage exceed a preset limit, the OUTPUT terminals are de-energized. A current limiting circuit limits the available current to a level determined by the setting of the CURRENT LIMIT control.

1-4. The inner chassis and circuitry are surrounded by an isolation guard, which is also isolated from the front panel and the outside cover. When properly connected, the guard bypasses any circulating ground currents which may cause error.

1-5. Most of the instrument circuitry is mounted on modular plug-in cards. An extender card is provided as an accessory to aid in the maintenance and adjustment of the instrument.



Figure 1-1. MODEL 332D OUTLINE DRAWING

1-6. SPECIFICATIONS

OUTPUT VOLTAGE: 0 to 1111.1110 VDC.

OUTPUT CURRENT: 0 to 50 milliamperes at any output voltage.

VOLTAGE RANGES: 10, 100, and 1000V ranges with outputs as follows:

0 to 11.111110 (1 uv steps)
0 to 111.11110 (10 uv steps)
0 to 1111.1110 (100 uv steps)

RESOLUTION: 0.1 ppm of range (1 uv maximum).

ACCURACY OF OUTPUT: (For 60 Days)

10V range - ±(0.001% of setting + 10 uV)
100V range - ±(0.001% of setting + 0.00002% of range)
1000V range - ±(0.0015% of setting + 0.00002% of range)

NOTE: The above accuracies are absolute, relative to NBS standards, and include effects of stability, line regulation, load regulation, and calibration uncertainties under standard reference conditions of 23°C ±1°C and up to 70% relative humidity.

STABILITY OF OUTPUT: (At standard reference conditions described under ACCURACY OF OUTPUT).

10V Range
±(5 ppm of setting + 7 uV) per month
100V and 1000V Range
±(5 ppm of setting + 30 uV) per month

OVERCURRENT PROTECTION: Automatically limits output current at any preset level between 1 ma and 60 ma via continuously variable front panel control. Panel lamp illuminates during limiting. Normal operation restored upon removal of overload.

OVERVOLTAGE PROTECTION: Automatically disables output voltage if level exceeds setting of front panel control. Continuously variable from 10% to 110% of each range. Manual reset.

DESIGN: All solid-state throughout (no vacuum tubes).

RIPPLE AND NOISE (to 30 kHz):

10V range - less than 20 uv RMS
100V range - less than 30 uv RMS
1000V range - less than 40 uv RMS

OUTPUT RESISTANCE: Less than 0.0005 ohms or ($0.0001E_O$) ohms (whichever is greater) at DC.

SETTLING TIME: Typically, within 10 ppm of final output, less than 20 seconds after a range change.

LINE REGULATION: 0.0002% of setting or 10 uv for a 10% line voltage change from nominal.

LOAD REGULATION: 0.0002% of setting or 10 uv for a full load change.

COMMON MODE REJECTION: Better than 140 db from DC to 400 Hz, up to 700V RMS or 1000 VDC. (Output voltage changes less than 10^{-7} of the applied common mode voltage.)

ISOLATION: Either output terminal may be floated up to 1000 VDC from chassis ground.

TERMINAL CONFIGURATION:

Voltage output	-	2 terminals
Remote sense	-	2 terminals
Guard	-	1 terminal
Chassis	-	1 terminal

REMOTE SENSE: Separate terminals are provided for sensing the output voltage directly at the load, reducing errors due to voltage drop in connecting wires between the instrument and load.

METER (switch selectable): 0 - 1200 VDC
0 - 60 ma

OPERATING TEMPERATURE RANGE: 0°C to 50°C (see ACCURACY OF OUTPUT and TEMPERATURE COEFFICIENT OF OUTPUT).

STORAGE TEMPERATURE RANGE: –40°C to +65°C.

RELATIVE HUMIDITY: 0 to 70%.

SHOCK: Meets all test requirements of MIL-T-945A, rigidly mounted or rack-mounted with slides.

VIBRATION: Meets all test requirements of MIL-T-945A, rigidly mounted or rack-mounted with slides.

ALTITUDE: 10,000 ft. operating; 50,000 ft. non-operating.

FUSES: One power line fuse, one high voltage fuse.

INPUT POWER: 115/230 VAC ±10%, 50 - 60 Hz, single phase. Approximately 130 VA fully loaded.

SIZE: 7" high x 19" wide x 18" behind panel.

WEIGHT: 60 lbs.

MOUNTING: Standard EIA relay rack (tapped for attachment of slides); resilient feet provided for bench use.

static awareness

A Message From

John Fluke Mfg. Co., Inc.



Some semiconductors and custom IC's can be damaged by electrostatic discharge during handling. This notice explains how you can minimize the chances of destroying such devices by:

1. Knowing that there is a problem.
2. Learning the guidelines for handling them.
3. Using the procedures, and packaging and bench techniques that are recommended.

The Static Sensitive (S.S.) devices are identified in the Fluke technical manual parts list with the symbol "⊗"

The following practices should be followed to minimize damage to S.S. devices.



1. MINIMIZE HANDLING



2. KEEP PARTS IN ORIGINAL CONTAINERS UNTIL READY FOR USE.



3. DISCHARGE PERSONAL STATIC BEFORE HANDLING DEVICES. USE A HIGH RESISTANCE GROUNDING WRIST STRAP.



4. HANDLE S.S. DEVICES BY THE BODY



5. USE STATIC SHIELDING CONTAINERS FOR HANDLING AND TRANSPORT



6. DO NOT SLIDE S.S. DEVICES OVER ANY SURFACE



7. AVOID PLASTIC, VINYL AND STYROFOAM® IN WORK AREA

PORTIONS REPRINTED
WITH PERMISSION FROM TEKTRONIX, INC.
AND GENERAL DYNAMICS, POMONA DIV.



8. WHEN REMOVING PLUG-IN ASSEMBLIES, HANDLE ONLY BY NON-CONDUCTIVE EDGES AND NEVER TOUCH OPEN EDGE CONNECTOR EXCEPT AT STATIC-FREE WORK STATION. PLACING SHORTING STRIPS ON EDGE CONNECTOR HELPS TO PROTECT INSTALLED SS DEVICES.



9. HANDLE S.S. DEVICES ONLY AT A STATIC-FREE WORK STATION

10. ONLY ANTI-STATIC TYPE SOLDER-SUCKERS SHOULD BE USED.

11. ONLY GROUNDED TIP SOLDERING IRONS SHOULD BE USED.

A complete line of static shielding bags and accessories is available from Fluke Parts Department, Telephone 800-526-4731 or write to:

JOHN FLUKE MFG. CO., INC.
PARTS DEPT. M/S 86
9028 EVERGREEN WAY
EVERETT, WA 98204

® Dow Chemical

J0089D-07U8604/SE EN Litho in U.S.A.
Rev. 1 MAR 86

Section 2
Operating Instructions

2-1. INTRODUCTION

2-2. This section of the manual contains information essential to the correct operation and performance of the Model 332D DC Voltage Standard. It is recommended that the contents of this section be thoroughly read and understood before attempting to operate the instrument. Should any difficulties be encountered during the operation of your instrument, please feel free to contact the nearest John Fluke Sales Representative or the John Fluke Mfg. Co., Inc., Box 43210, Mountlake Terrace, Washington, 98043. A complete list of Sales Representatives is located in Section 7 of this manual.

2-3. CLAIM FOR DAMAGE IN SHIPMENT

2-4. The Instrument should be thoroughly inspected immediately upon receipt. All material in the container should be checked against the enclosed packing list. The manufacturer will not be responsible for shortages against the packing sheet unless notified immediately. If the instrument fails to operate properly, or is damaged in any way, a claim should be filed with the carrier. A full report of the damage should be obtained by the claim agent, and this report should be forwarded to the John Fluke representative. Upon receipt of this report you will be advised of the disposition of the equipment for repair or replacement. Include the model number, type number, and serial number when referring to this instrument for any reason.

2-5. SHIPPING INSTRUCTIONS

2-6. All John Fluke Mfg. Co., Inc. instruments should be shipped prepaid in the original packing carton. Upon request, a new carton can be obtained from the John Fluke Mfg. Co., Inc. Please include the instrument model number when requesting a new container.

2-7. INPUT POWER

2-8. The power transformer has dual primary windings. Normally, these primary windings are connected in parallel for 115 volt operation. Upon request, the primary windings are connected in series at the factory for 230 volt operation. Should it become desirable to convert the instrument from one type of power line operation to the other, refer to paragraph 4-18 in Section 4.

2-9. RACK MOUNTING PROCEDURES

2-10. The Model 332D is supplied with rubber nonskid feet. A rack-slide kit (FLUKE MEE-8088) is available for installation of the instrument in a standard 19-inch rack. In order to rack mount the instrument refer to figure 2-1 and perform the following steps:

a. Attach the chassis section (A) to the side panels with the screws (B) provided in the kit.

b. Install the cabinet sections (D) and center sections (C) into equipment rack. The extension angle



Figure 2-1. CHASSIS SLIDE INSTALLATION

brackets, which are part of section (D), are mounted at the rear of the cabinet.

c. Slide the center sections (C) toward the front of the cabinet until they lock in place.

d. Depress the spring locks on the chassis sections (A) and insert the instrument between the extended center sections (C) on the cabinet.

e. Slide the instrument completely into the equipment rack and secure it in place with fasteners through the front panel.

2-11. CONTROLS, TERMINALS AND INDICATORS

2-12. The name and function of the front and rear panel controls, terminals, and indicators are illustrated and described in Figure 2-2. The numbers at the tails of the arrow callouts correspond to the reference numbers in the chart.

2-13. INITIAL OPERATION

2-14. General

2-15. Before operating the instrument, some preliminary settings and connections should be considered. The use of these settings and connections depends upon the degree of equipment safety and accuracy required. The following paragraphs discuss the merits and procedures for each of the settings and connections.

2-16. Voltage Trip Setting

2-17. The VOLTAGE TRIP switch and VERNIER control provide protection to external equipment by limiting the maximum allowable output voltage to the external load. The range of voltage limiting is selected with the VOLTAGE TRIP switch. Refinement of the value of the voltage to be limited is accomplished with the VERNIER control. If no degree of limiting is required within the ranges of the instrument, set the VOLTAGE TRIP switch to 1000 and the VERNIER fully clockwise. Should some degree of limiting be desirable, proceed as follows:

a. Without any load connected to the OUTPUT terminals and the POWER switch in the STDBY/RESET position, set the front-panel controls as follows:

RANGE	As desired
VOLTAGE TRIP	To the lowest range that overlaps the desired trip voltage



REF. NO.	NAME	FUNCTION
1	POWER switch	Applies line power to the auxiliary power supplies within the instrument, when in the STDBY/RESET postion. The instrument is completely energized when the POWER switch is in the OPR position and the red indicator lamp near the switch is illuminated.
2	METER Switch	Selects meter indication of either output voltage or output current.
3	Meter	Indicates either output voltage or output current depending on the position of the METER switch. The meter voltage range depends on the setting of the VOLTAGE RANGE switch. The current range is 0 to 60 milliamperes.
4	VOLTAGE RANGE Switch	Selects the output voltage range of 10, 100, or 1000 volts, and changes the meter to a corresponding range.

Figure 2-2. CONTROLS, TERMINALS, AND INDICATORS (Sheet 1 of 2)

REF. NO.	NAME	FUNCTION
5	VOLTAGE TRIP Switch and VERNIER Control	The VOLTAGE TRIP switch provides a means of limiting the output voltage in three ranges (10, 100, and 1000 volts) independent of the VOLTAGE RANGE switch. The VERNIER control varies the amount of limiting within the ranges of the VOLTAGE TRIP switch. When an over-voltage condition exists, the red indicator lamp near the VOLTAGE TRIP switch illuminates and the red lamp near the POWER switch is extinguished.
6	CURRENT LIMIT control	Provides a means of setting a limit on the magnitude of the output current within a range to 0 to 60 milliamperes. An over-current condition is signified when the indicator lamp, near the CURRENT LIMIT control, illuminates.
7	OUTPUT Terminals	Provides a convenient means of connecting the load to the output circuit.
8	SENSE Terminals	Allows the regulating circuitry to be connected to the OUTPUT terminals (7) or directly to the load for optimum regulation.
9	GUARD Terminal	When properly connected, provides a means of eliminating circulating ground currents through the load.
10		Power line ground.
11	Readout Dials	Select and indicate the output voltage. The recessed numbers directly above each dial provide in-line readout of the output voltage. When a dial is set to "X" (10), it represents 0 with a 1 carry-over to the digit to the immediate left. For example: 10. X X X X X X represents 11.111110 volts.
12	Decimal Lamps	These lamps indicate the proper decimal point setting when illuminated and are controlled by the RANGE switch.
13	Mechanical Zero adjust	Provides a means of setting the meter mechanical zero. Adjustment should be made after the instrument has been completely de-energized for at least 3 minutes.
14	Fuse, line	A 3 ampere slow-blow fuse for 115 volt power line operation. Use a 1½ ampere slow-blow fuse for instruments converted to 230 volt power line operation.
15	Fuse, high voltage	A ¼ ampere slow-blow fuse electrically located at the output of the high voltage rectifier circuit.

Figure 2-2. CONTROLS, TERMINALS, AND INDICATORS (Sheet 2 of 2)

VERNIER	Fully cw
CURRENT LIMIT	As desired
METER	Voltage
Readout Dials	Desired trip voltage

b. Set the POWER switch from the STDBY/RESET position to OPR.

c. Slowly rotate the VERNIER control counter-clockwise until the indicator lamp near the VOLTAGE TRIP switch illuminates and the red lamp near the POWER switch is extinguished. The voltage trip is now set to the value indicated on the readout dials and the instrument is tripped to the STDBY mode.

d. To reset the instrument, set the readout dials to a value less than the trip voltage and place the POWER switch in the STDBY/RESET position, then to OPR.

2-18. Current Limit Setting

2-19. The CURRENT LIMIT control provides a means of limiting the amount of output current. If no limiting within the current range of the instrument is desirable, set the CURRENT LIMIT control to the fully clockwise position (60). Should some degree of current limiting be desirable, proceed as follows:

a. With the POWER switch in the STDBY/RESET position, set the front panel controls as follows:

RANGE	As desired
VOLTAGE TRIP and VERNIER	As desired
VOLTAGE CURRENT LIMIT	Fully clockwise
METER	Current
Readout Dials	1 volt

b. Place a short across the OUTPUT terminals.

c. Set the POWER switch to the OPR position.

d. Adjust the CURRENT LIMIT control until the current indicated on the meter is the value of the desired limiting current.

e. Place the POWER switch in the STDBY/RESET position. Remove the short. Current limiting is now set to the desired value for any output voltage.

2-20. Sense Connections

2-21. When a load is connected, there may be an appreciable voltage drop between the instrument and the load, depending on the length and gauge of the connecting leads. The nomograph of Figure 2-3 can be used to determine the approximate voltage across the connecting wire leads.

2-22. Using the nomograph of Figure 2-3, lay a straight edge from the value of the output current, represented on scale 1, to the gauge of the connecting wires used, represented on scale 2. The voltage across the connecting wires, expressed in millivolts per foot, is obtained from scale 3. To determine the total voltage across the connecting wires, multiply the total length in feet by the value obtained from scale 3. For example, assume that two AWG No. 28 wires, each 3 feet long, are used to connect a load, requiring 50 milliamperes, to the Model 332B. With a straight edge, connect the known current on scale 1 (50 ma) and the wire size on scale 2 (No. 28). The resulting IR drop on scale 3 is approximately 3.2 millivolts per foot. Therefore, the connecting wires develop a total voltage of 19.2 millivolts (2 x 3ft x 3.2 mv/ft= 19.2 mv), which is several times the published load regulation at 1000 volts output. To compensate for this, the instrument is equipped with remote sensing, which maintains regulation at the load. Consequently, the voltage across the connecting wires will have no effect. Determine if the wire leads used to connect the instrument to the load, will cause a voltage drop in excess of the load regulation specifications. If this voltage drop is excessive, remote sensing should be used. To prepare the instrument for remote sensing, proceed as follows:

a. With the POWER switch set to OFF, or to STDBY/RESET, remove the front-panel shorting links between the SENSE and OUTPUT terminals.

b. Using a twisted pair of insulated wires, connect the +SENSE terminal to the positive side of the load, and connect the -SENSE terminal to the negative side of the load.

CAUTION

Ensure that the SENSE terminals are connected to the load in the proper polarity. Incorrect connections will result in loss of regulation and possible damage to the instrument.

2-23. Guard Connection

2-24. When the instrument is connected to another instrument (both instruments grounded through their respective power cords), a potential difference may exist between the power line grounds of the two instruments.

This potential difference can cause circulating ground currents, which could cause errors in the output voltage. To prevent these errors from occurring, the instrument is equipped with a guard. This guard, when properly connected to the load, will provide a separate path for the circulating ground currents, thus eliminating possible errors in the output voltage. For proper connection, connect the GUARD terminal directly to the grounded side of the load, at the load. Figure 2-4 illustrates the correct GUARD terminal connection and the re-routed circulating ground current path.

2-25. OPERATION

2-26. Operate the instrument in accordance with the following procedure:

a. Set the METER switch to VOLTAGE.

b. Set the POWER switch in the STDBY/RESET position. Allow at least a 10 minute warm-up period, if the instrument has just been energized.



Figure 2-3. NOMOGRAPH OF VOLTAGE DROP ACROSS LOAD WIRES



Figure 2-4. GUARD CONNECTION

c. Connect the SENSE terminals to the OUTPUT terminals with the shorting links provided.

d. Set the CURRENT LIMIT control fully clockwise (60) or to a predetermined value, using the procedure of paragraph 2-20.

e. Set the RANGE switch to the desired output voltage range (10, 100, or 1000).

f. Set the VOLTAGE TRIP and VERNIER controls fully clockwise or to a predetermined value, using the procedure of paragraph 2-18.

g. Set the readout dials to the value of the output voltage desired.

h. If desired, connect the GUARD terminal to the grounded side of the load in accordance with paragraph 2-25. The SENSE terminals may remain connected to the OUTPUT terminals. Should remote sensing be desired, connect the SENSE terminals to the load in accordance with paragraph 2-22.

i. Connect the load to the OUTPUT terminals.

j. Set the POWER switch to the OPR position.

k. The output voltage provided to the load will be the voltage indicated on the readout dials. Should it be desirable to monitor the output current, place the METER switch in the CURRENT position.

Section 3
Theory of Operation

3-1. INTRODUCTION

3-2. This section describes the theory of operation of the Model 332D. In conjunction with the text, refer to the functional schematic diagrams located in the rear of the manual. Before attempting to trouble shoot the unit in detail, one should be thoroughly familiar with circuit operation.

3-3. FUNCTIONAL DESCRIPTION

3-4. This voltage standard is a series regulated power supply basically consisting of the voltage control circuitry, preregulation circuitry, and protection circuitry. The voltage control circuits are the main regulation circuits and respond to load, RANGE, and readout dial changes. Figure 3-1 illustrates a simplified schematic diagram of the voltage control circuitry. The error amplifier and series pass element, illustrated in the shaded portion, together constitute a dc operational amplifier. The tendency of the operational amplifier is to maintain the summing point effectively at +SENSE potential. In this condition the output voltage of the voltage standard is equal to the ratio of the sample string resistance (^{R}READOUT) to the range resistance (^{R}RANGE) times the reference (^{E}REFERENCE), as illustrated in Figure 3-1. The constant reference voltage (^{E}REFERENCE), in combination with the appropriate series resistance (^{R}RANGE), provides a constant current to the sample string. Due to the constant current, the output is proportional to the resistance of the sample string (^{R}READOUT). Since the tendency of the operational amplifier is to maintain the summing point at +SENSE potential, the output voltage is equal to the sample string voltage. Changing the setting of the readout dials (sample string) causes the output voltage to change correspondingly. Each change in the RANGE switch setting causes the constant current to change by a factor of 10, thus the output voltage changes by the same factor. A detailed block diagram is illustrated in the Functional Block Diagram (332B-1500), at the back of the manual. In this diagram, the chopper amplifier, differential amplifier, and series pass driver constitute the error amplifier of Figure 3-1.

3-5. Series regulated power supplies have the inherent disadvantage of low efficiency. When providing a low level output, the series pass element of the supply must dissipate the bulk of the power supplied by the high voltage transformer circuit. In this instrument, a unijunction oscillator circuit monitors the voltage across the series pass element and provides a voltage level information to a pre-regulation circuit. The pre-regulation circuit utilizes this information to provide full-wave control of the input line voltage to the primary of the high voltage transformer. Thus, the power supplied by the high voltage transformer is controlled to provide only that amount necessary for the load requirements. This in turn increases the overall efficiency of the instrument. This also accounts for symbolizing the unregulated dc voltage, in Figure 3-1, as a variable dc voltage.

3-6. Circuitry, for protection of personnel as well as external equipment, is provided. The instrument contains an interlock system to de-energize the high voltage circuits within the instrument when the covers are removed. A limit may be set for the output voltage and/or current. Whenever the output voltage or current tries to exceed the set limits, the instrument output is de-energized. Therefore, sensitive external equipment can be protected from excessive voltage and current.



Figure 3-1. VOLTAGE CONTROL CIRCUITRY

3-7. CIRCUIT DESCRIPTIONS

3-8. Voltage Control Circuitry

3-9. REFERENCE SUPPLY. The master reference voltage for the instrument is produced in the A5A1 Reference Supply (332B-1083). This assembly consists of a +15V dc reference supply, an oven temperature regulator for the reference supply, and divider networks for compensation of offset voltages when the output is set to zero.

3-10. The Reference supply is composed of differential amplifier A2 and zener reference amplifier A3. The reference amplifier is enclosed in an oven which maintains a constant temperature for environmental stability. Selection of the values of R7A and R7B scales the output of the Reference Supply to +15V dc. Variable resistor R9 allows adjustment of the resulting V_{REF} output. Temperature coefficient of the base/emitter voltage for A3 is accurately matched to the zener element through selection of R13. The resulting stable reference at the collector of A3 is applied to the non-inverting input of A2. The other input to A2 receives an equivalent voltage from the divider composed of R14 and R15. Any change in V_{REF} is sensed at the base of A3 and the resulting amplified change applied to the non-inverting input of A2. This change then alters the conduction of A2 such that V_{REF} is maintained at +15V dc.

3-11. Constant operating temperature for the reference amplifier A3 is provided by the Oven Temperature Regulator Q1 and A1. The series-pass regulator composed of Q1 and A1 establishes a constant voltage across the heater element of A3. Any variation in heater voltage is sensed by A1 and amplified. The resulting output of A1 then alters the conduction of Q1 to eliminate the voltage variation across the heater element. The heater element consists of a semiconductor material which has moderate conductivity at temperatures below a specific stabilization point and a marked decrease in conductivity as the temperature approaches the stabilization point. Application of a constant voltage to the heater provides a fast warm-up and a much more stable operating temperature.

3-12. The divider network composed of R1 through R6 provide a bias voltage to one input of the A5A4 Chopper Amplifier. Potentiometers R2, R4, and R6 are adjusted to compensate for offsets in the 10V, 100V, and 1000V ranges when the output is set to zero.

3-13. RANGE RESISTORS. The A4 Range Cal (332B-1052) provides three separate adjustable range resistors. These resistors together with the A2 Sample String form a resistive divider which determines the output voltage of the instrument.

3-14. SAMPLE STRING. The A2 Sample String (332B-1051) together with the selected range resistor in the A4 Range Cal forms a resistive divider, the ratio of which is controlled by the front panel decade dials. The output voltage of the sample string is proportional to the reference voltage multiplied by the ratio of the sample string resistance to the A4 range resistance.

3-15. CHOPPER AMPLIFIER. The A5A4 Chopper Amplifier (332B-1058) compares low frequency and dc control signals from the A2 Sample String output to the +SENSE terminal voltage and amplifies any difference. The circuitry consists of an input filter, a MOSFET chopper, an operational amplifier, a synchronous demodulator, an output filter, and a multivibrator.

3-16. Low frequency and dc control signals at terminal 6 are passed through the input filter C2, R1, C3 to reject frequencies above 30 Hz. The MOSFET chopper Q1 modulates the signal appearing at the junction of C4 and output signal at Q2 is then amplified by the operational amplifier IC1, which has a gain of approximately 420. The paraphase amplifier Q3 amplifies the output of IC1 and provides two equal amplitude, but 180° out-of-phase signals. The collector signal of Q3 is coupled by C16 to the shunt demodulator Q4. The resulting demodulated signal appearing at the junction of C17 and R24 is filtered by R24, R26 and C18, leaving only the amplified dc and low frequency signals. The emitter signal of Q3 is applied through C14, R21, C15, R25, R23, and C22 to C18, where it is used to cancel any chopper ripple at 270 Hz.

3-17. The 270 Hz multivibrator is formed by Q6, Q7 and associated timing networks, in addition to a driver Q5. Variable resistor R43 adjusts the level of the signal applied to the driver Q5, and subsequently the output signal applied to the gate of Q1. The collector signal of Q5 is applied to Q1 across C5 to compensate for spikes coupled through Q1. Variable resistor R34 provides adjustment of the compensation signal. An output signal at the collector of Q7 is applied to the base of Q4, which synchronously demodulates the Chopper Amplifier output.

3-18. DIFFERENTIAL AMPLIFIER. Error signals in the form of ac changes are applied to the A5A3 Differential Amplifier (332B-1057). These signals are coupled through C1 to the gate of Field Effect Transistor (FET) Q2. Error signals appearing as dc changes are applied to the chopper amplifier at the base of Q6. Using a separate path for ac changes allows rapid regulation of the output voltage for rapid changes in load requirements. The Differential Amplifier P/C Assembly provides an output that is proportional to the amplified dc error signal from the Chopper Amplifier P/C Assembly.

3-19. Use of a Field Effect Transistor for Q2 provides high input impedance and low noise. Transistor Q8 is a current source for one stage of the differential amplifier. Use of the current source provides high gain and good common mode rejection at the input of the amplifier. The compound configuration of Q4-Q5 and Q6-Q7 provides high input impedance and minimizes temperature effects. The output signal from the collector of Q9 is applied to the base of the common collector amplifier Q11. Transistor Q11 provides impedance matching between the high output impedance of Q9 and the low input impedance of the series pass driver circuit.

3-20. SERIES PASS. The A7A1 Series Pass (332B-1061) contains the series-pass transistors which control the output voltage. It also contains a voltage controlled oscillator (VCO) and control amplifiers which are part of the preregulator, a power supply, and an automatic "crowbar" driver.

3-21. The power supply composed essentially of CR1 through CR4 produces the required operating voltages for the series pass circuitry. AC voltage at terminals 8 and 9 is rectified by CR1 through CR4 to provide an unfiltered positive voltage. This voltage is isolated by CR5 and filtered by C2 to provide a +150V dc operating voltage for the series-pass transistors. The voltage divider of R1 through R3 and zener CR6 produces a clipped, full-wave rectified 16V synchronizing signal for the VCO.

3-22. Output voltage of the instrument is established and maintained by the series-pass transistors, Q1 through Q8. The transistors Q1 through Q7 are normally saturated and Q8 is absorbing the total voltage required to maintain the output of the instrument. However, when the output level or load current is changed and the voltage across Q8 exceeds 150V, Q1 through Q7 absorb the additional voltage. The preregulator circuitry then reduces the output of the A7 H.V. Mother Board until the voltage across Q8 is less than 150V. When this condition is reached, Q1 through Q7 again saturate and Q8 absorbs the total regulation voltage.

3-23. The automatic "crowbar" consisting of Q10 monitors the total voltage drop across the series-pass transistors. Load or output changes that cause the voltage across the series-pass to exceed 225V will cause Q10 to conduct. Its conduction energizes K2 on the A7 H. V. Mother Board and places a load across the high voltage rectifier, thus limiting

the voltage across the series-pass transistors.

3-24. Unijunction transistor Q9 and C3, L3, R37, CR18, R35, and CR19 form a VCO which furnishes turn-off pulses to the preregulator circuitry. This VCO is synchronized to the ac line zero crossing through amplifiers Q11 and Q12.

3-25. A clipped 16V pulse is rectified by CR32 and C5 to provide operating voltage for the base of the VCO, Q9. This voltage is clamped to zero during the ac line zero interval by amplifiers Q11 and Q12. The divider composed of R36 and R42 provides a sample of the clipped 16V pulse at the base of Q12. When the pulse is at 0V, Q12 produces an amplified positive pulse at its collector. This pulse is differentiated by C4 and R41 and the resulting positive spike momentarily turns on Q11. Conduction of Q11 clamps the output of rectifier CR32, C5 to zero, thus synchronizing the output of Q9 to the ac line zero crossing. The output pulses from Q9 are dependent upon the voltage charge on C3. The voltage is sensed across Q8 through the divider consisting of L3, R37, R35, CR18, and CR19. If this voltage increases. Q9 will produce a preregulator turn off pulse earlier in the ac line cycle, thus reducing the ac power available to the A7 H.V. Mother Board. Conversely, should the voltage across Q8 decrease, the ac power to the A7 H.V. Mother Board is increased.

3-26. POWER SUPPLIES. Operating voltages for the temperature regulating circuit, zener reference circuit, chopper amplifier, and differential amplifier are provided by the A5A5 Auxiliary Power Supply P/C Assembly (332B-1059). The auxiliary power supply consists of the 25 volt supply and −15 volt supply circuits. The auxiliary supply reference element is located in the 25 volt supply. The output of the 25 volt supply is then used as the reference for regulation of the −15 volt supply.

3-27. In the 25 volt supply, CR1 through CR4, C2, R4, and C3 provide unregulated dc voltage to the regulation circuitry consisting of Q2 through Q6. Transistors Q5 and Q6 constitute a differential amplifier. The base of Q6 is held at a constant voltage by zener diode CR6. The base of Q5 is connected to a voltage divider, consisting of R8, R9, and R10, referenced to the output of the supply. Variations in the +25 volt output of the supply are sensed at the base of Q5. Any difference between the base voltages of Q5 and Q6 is amplified by the differential pair and applied from the collector of Q5 to the base of series pass driver Q3. The amplified error signal controls the conduction of Q3, which in turn controls the series pass element Q4. Transistor Q2 is a constant current source to supply base drive to Q3.

3-28. In the −15 volt supply, CR7 through CR10, R14, and C8 provide the unregulated dc voltage to the regulating circuit consisting of series pass element Q7 and differential pair Q8 and Q9. The base of Q9 is connected to a voltage divider referenced to the +25 volt supply output. The base of Q8 is connected to the positive side of the -15 volt supply. Variations in the output voltage are sensed at the base of Q9. Any difference between the base voltages of Q8 and Q9 is amplified by the differential pair and applied from the collector of Q8 to the base of series pass element Q7. The amplified error signal controls the conduction of Q7 and consequently the magnitude of the output voltage. The positive side of the -15 volt supply is connected to the negative side of the +25 volt supply through pins 11 and 12. The + sense line is connected to this junction and is the common for the auxiliary power supply.

3-29. The ±35 volt operating voltages for the series pass driver circuitry on the A5A2 Series Pass Driver P/C is provided by a power supply located on the A5A6 Current Limiter P/C Assembly (332B-1060). In the diode bridge configuration of CR1 through CR4, diodes CR1 and CR2, R1 and C1 provide a positive unregulated dc voltage. Diodes CR3 and CR4, R4, and C4 provide negative unregulated dc voltage. The positive unregulated dc voltage is applied to the regulating circuit of Q1 and CR5 and through a voltage divider to the RANGE switch, for application to the appropriate decimal lamp. The 36 volt reference voltage, established by CR5, provides the input signal for the emitter follower configuration of Q1. This emitter follower configuration provides the necessary low output impedance and power gain of the power supply. The −35 volt supply functions in the same manner as the +35 volt supply.

3-30. Pre-Regulation Circuitry

3-31. OSCILLATOR. A unijunction oscillator, consisting of Q9 and associated circuitry, is located on the A7A1 Series Pass Element P/C Assembly (332B-1060). Applied to base two of Q9 is a 6.8v clipped, full-wave rectified, 60 Hz sine wave. The potential at the emitter of Q9 depends upon the charge of C4 and C5. The charge of C5 depends upon the voltage across the main series pass element, Q8. At the trailing edge of each pulse at the base two of Q9, the oscillator provides a series of positive pulses until the leading edge of the next +6.8 volt pulse occurs. With an increased charge across C4 and C5, the initial output pulse of the oscillator will occur earlier in each half cycle. The initial pulse from the oscillator during each half cycle will switch the preregulator off to control the amount of line power supplied to the high

voltage transformer. If the series pass element voltage of Q8 increases, the pre-regulator is switched off earlier in each half cycle. This in turn reduces the series pass element voltage of Q8 to its equilibrium value.

3-32. The +6.8 volt operating voltage for the oscillator circuit is taken from the +150 volt supply for the series pass element. A portion of the +150 volt supply is applied to the voltage divider consisting of R1 through R3. The divided-down voltage is regulated by zener diode CR6 to approximately +6.8 volts.

3-33. PREREGULATOR. The A7A2 Preregulator (332B-1082) controls the ac power supplied to the instrument by passing only enough power to the A7 H. V. Mother Board to meet the output load requirement. It consists of a ±V supply, a relay power supply, preregulator control drivers, a preregulator bridge, and a current limiter.

3-34. ±V and +10V dc operating voltages are produced for the A7A2 Preregulator by the rectifier CR1 through CR4 and associated components. A 10V ac input is applied to CR1 through CR4. The dc output at the junction of CR2 and CR4 is filtered by C3 to provide a −V operating voltage. The dc voltage at the junction of CR3 and CR1 is heavily loaded by R1 to provide an unfiltered +V operating voltage. This voltage is also isolated through CR5 and filtered by C4 to provide a +10V dc operating voltage.

3-35. Operating voltage for relay K1, which supplies ac voltage to the preregulator bridge, is produced by bridge rectifier CR6 through CR9 and K2. AC return for the bridge rectifier is provided through the contacts of K2. This relay is energized only in the OPR mode by a control voltage from the A5A2 Series Pass Driver. The A5A2 Series Pass Driver automatically removes the control voltage from K2 should a VOLTAGE TRIP occur, thus removing ac power to the preregulator bridge and establishing a STDBY condition.

3-36. The circuitry consisting of Q2 through Q9 controls the conduction of the preregulator bridge attenuator, Q1. Input pulses from the VCO in the A7A1 Series Pass are supplied to the base of Q7 via terminal 14. The first pulse turns on Q7 and Q6, which through regenerative action, saturate. This condition turns off Q5 and causes Q4 and Q8 to also turn off. Q9 is subsequently turned on by the −V collector voltage of Q8 and provides a negative voltage at the base of Q2. This condition turns off Q2 and also Q1, thus causing the preregulator bridge of CR10 through CR13 and Q1 to provide maximum attenuation to the ac voltage applied to the A7 H.V. Motherboard. When the ac line passes through zero, the 0V, +V condition at the emitter of Q6 causes it to turn off and also turns off Q7. This condition reverses the previously described state of each transistor and the preregulator bridge again passes the ac line voltage to the A7 H.V. Motherboard.

3-37. AC line voltage applied to T2 and subsequently the A7 H.V. Motherboard is controlled through the preregulator bridge consisting of CR10 through CR13 and Q1. The previously described circuitry of Q2 through A9 controls conduction of Q1. Diodes CR10 through CR13 provide a unidirectional current through Q1. Positive alterations are passed by CR10 and CR13. CR12 and CR11 pass negative alternations. Should Q1 be cut off, C6 and R5 provide a dynamic load for the bridge. Overload current protection for Q1 is provided through divider R2, R8, and R9 and Q3. Should the current through Q1 exceed 17 amperes, the voltage at the base of Q3 turns it on and causes Q6 to saturate. This condition causes Q1 to be cut off, thus limiting the current through the preregulator bridge.

3-38. Protection Circuitry

3-39. Trip. The purpose of the trip circuit is to remove ac power from the primary of the high voltage transformer and to open the negative output path, if an overvoltage or catastrophic overcurrent condition exists. The trip circuitry is located on the A5A2 Series Pass Driver P/C Assembly (335A-1056). Transistor Q3 is a constant current source for relays A7K1 and A7A2K2. With A7A2K2 (on the Pre-Regulator P/C Assembly) closed, current is provided to A7A2K1 which completes the primary circuit for the high voltage transformer. With relay A7K1 (on the High Voltage Motherboard P/C Assembly) closed, the negative output path is completed and power may be supplied to the load. The current sensing resistor, R22, is effectively connected through R24 to the base of normally off Q4. In the event of a catastrophic failure, in which the current limiting circuitry would not function, an excessive current approaching 120 milliamperes would develop sufficient voltage across R22 to turn on Q4. Because of the regenerative configuration, transistors Q4 and Q2 would become saturated. With Q2 saturated, the potential at pin 10 becomes nearly the same as the positive buss potential. This bypasses the current away from the relays, which causes them to open. With the relays open, the OUTPUT terminals are de-energized, the input power to the high voltage transformer is interrupted, and the OPR indicator lamp goes out. To reset the instrument, the POWER switch is placed in the STDBY/RESET position; then to the OPR position after the cause of the overload

has been corrected. With the POWER switch in the STDBY/RESET position, the circuit common is connected through a section of the POWER switch and pin 10 to the emitter of Q2. This results in turning off both Q2 and Q4, and thus returning them to their original state.

3-40. The overvoltage trip element is Q1. The base of Q1 is connected to R15 and the appropriate resistor selected by the VOLTAGE TRIP switch. The voltage trip point is selected by the VERNIER control (R5), which sets a reference bias on Q1 (maintaining Q1 cut off). As the output voltage increases, the voltage at the base of Q1 increases negatively until it exceeds the selected trip voltage and causes Q1 to conduct. The conduction of Q1 saturates Q2 and results in de-energizing the instrument output terminals, as previously described.

3-41. CURRENT LIMIT. The current limit circuitry, located on the A5A6 Current Limiter P/C Assembly (332B-1060), provides a means of varying the limiting point of the output current. Current sensing resistor R22 on the A5A2 Series Pass Driver P/C Assembly provides a voltage to the current limiter circuit that is proportional to the output current. This voltage is applied through pin 10 and CR12 to the base of Q5. The emitter of Q5 is connected to the wiper of the CURRENT LIMIT control (R6), which provides a variable bias for the base-emitter junction. Transistor Q5 is normally off; however, when the output current exceeds the set limit, Q5 turns on. Conduction of A5 causes both Q4 and Q3 to conduct. Conduction of Q3 causes Q1, on the Differential Amplifier P/C Assembly, to conduct and bypass some of the sample string current. This causes the output voltage to be reduced and consequently the output current is reduced. The conduction of Q3 also turns on the regenerative pair, Q6 and Q7, which supply current to the red indicator lamp.

3-42. INTERLOCKS. The Model 332D is equipped with an interlock circuit for personnel safety (332B-1000). When either the top or bottom inner covers or printed circuit assemblies A7A2, A7, A7A1, A5A1, A5A3, A5A4, A5A5, or A5A6 are removed, the ground return for the A7K1 and A7A2K2 relays is opened. This results in removal of the input power to the high voltage transformer (T2) and opens the negative output side of the instrument.

3-43. TIME DELAY. The purpose of the time delay circuit, located on the A6 Time Delay P/C Assembly (332B-1020), is to provide a short interval for the auxiliary voltages to rise to nominal value. This ensures that the control amplifiers are operating before the high voltage is available. The time delay circuit momentarily holds open relays A7K1 and A7A2K2, which prevent the closure of A7A2K1. The time delay is approximately 3 seconds. Diodes 2001 and 2002 provide a full-wave rectified voltage from a secondary winding of the power transformer between pins 20 and 22. When the POWER switch is in the STDBY/RESET position, a small current flows through R2001, S1c, K2001, R2004, and C2001. This current, although too small to actuate K2001, charges C2001. Capacitor C2001 charges until it reaches the firing point of Q2001, approximately 2 to 3 seconds. At this point Q2001 conducts, increasing the current through K2001. The relay actuates and closes contact K2001A (which provides the current path when the POWER switch is in the OPR position) and opens contact K2001B. When K2001B opens, the grounding circuit is removed from the constant current source supplying A7K1 and A7A2K2, and these relays are allowed to actuate.

3-44. Miscellaneous Circuitry

3-45. OUTPUT CIRCUIT CURRENT SOURCE. In addition to the main high voltage bridge rectifier, CR1 through CR10 on the A7 High Voltage Mother Board P/C Assembly Schematic (332B-1056), there is another high voltage bridge (CR13 through CR20). This bridge-rectifier is in series with R27 and R28 and forms a quasi-constant current source. This current flows through the series pass transistors and acts as a minimum load to insure that their transconductance is held above a minimum value. Another purpose of the quasi-constant current source is to provide a quick discharge path for the output capacitor C1, when down ranging. This helps to reduce the setting time.

3-46. CAPACITOR SWITCH. The capacitor switch circuitry is located on the A3 Capacitor Switch P/C Assembly Schematic (332B-1092). When down ranging from 1000 volts, capacitor C4 (on the chassis) will tend to charge to a voltage level proportional to the difference between the charge on C5 and the parallel combination of the output capacitors C1 and C2. If this difference is too great, C4 will receive a charge of sufficient magnitude to cause a dielectric absorption problem, thus excessive settling time will result. (Dielectric absorption is the tendency of the dielectric material of the capacitor to absorb and retain a small charge). To prevent this occurrence, C5 is discharged through R7 (on A3) when the RANGE switch is down ranged from 1000 volts to 10 or 100 volts. In doing so the decay rate of C5 and the parallel combination of C1 and C2 will be equal, thus C4 does not receive an over charge. After C5 has discharged sufficiently (several seconds), the K1A contacts (on A3) close and parallel the low resistance of R6 with R7. This essentially shorts C5 and returns the loop gain to the required amount. The capacitor switch

circuitry is responsible for allowing a time delay before closing the K1A contacts. When down ranging from 1000 volts, C1 is charged by the +35 volt supply through R2 and R1. After several seconds, C1 accumulates a sufficient charge to cause Q1 to conduct. Conduction of Q1 energizes relay K1 which closes the K1A contacts.

3-47. CROWBAR CIRCUIT. If the output voltage were suddenly turned to zero with a load connected to the instrument, the voltage across the filter capacitors C1, C2, and C3 (located on the A7 High Voltage Mother Board P/C) would appear across the series pass transistors. This voltage could damage the series pass transistors. To protect the series pass transistors from this kind of damage, a "crowbar" circuit is utilized. (The term "crowbar" is derived from the use of such a device to discharge large capacitor banks in transmitter power supplies). The "crowbar" circuit consists of transistor Q10 and associated circuitry on the A7A1 Series Pass Element P/C. It also includes relay K2 on the A7 High Voltage Mother Board P/C. When the voltage across the series pass element reaches approximately 225 volts, transistor A10 conducts. Since relay K2 is in the collector circuit of Q10, the relay is energized and closes the contacts. With the K2A contacts closed, a discharge path through R15 is provided for the filter capacitors.

3-48. METER CIRCUIT. The front panel meter indicates the output voltage or output current, depending on the position of the METER switch. When the METER switch is in the VOLTAGE position, resistors R3 through R6, on the Series Pass Driver P/C Assembly, and the resistors selected by the RANGE switch S2f provide the meter with a current which is proportional to the output voltage. When the METER switch is in the CURRENT position, resistors R1 and R2, on the Series Pass Driver P/C Assembly, provide the meter with a current which is proportional to the output current.

Section 4
Maintenance

4-1. INTRODUCTION

4-2. Maintenance and calibration of the Model 332D is covered in this section. Paragraph 4-6, GENERAL MAINTENANCE, covers unique and miscellaneous maintenance procedures. A series of checks to determine if the instrument operates properly plus information to aid in localizing problem areas, should any of these checks fail, is covered under paragraph 4-20, PERFORMANCE TESTS. Paragraph 4-36, PERFORMANCE TESTS. Paragraph 4-36, CALIBRATION, contains procedures for alignment of circuits and final accuracy adjustments.

4-3. SERVICE INFORMATION

4-4. Each instrument manufactured by the John Fluke Manufacturing Company is warranted for a period of one year upon delivery to the original purchaser. Complete warranty information is contained in the Warranty page located at the front of this manual.

4-5. Factory authorized calibration and repair service for all Fluke instruments are available at various world wide locations. A complete list of factory authorized service centers is located in Section 7 of this manual. If requested, an estimate will be provided to the customer before any repair work is begun on instruments beyond the warranty period.

4-6. GENERAL MAINTENANCE

4-7. Maintenance Access

WARNING

The inner chassis is at +OUTPUT potential! Hazardous voltages exist between inner chassis and front panel.

4-8. The chassis may be easily removed from the outer case by unfastening the two Dzus fasteners, located at the rear of the case. To obtain access to the circuitry within the chassis, the top and/or bottom inner covers must be removed. Removal of the top and/or bottom covers opens one or both of the interlock switches. To have the instrument fully operable, with the top and/or bottom covers off, the interlocks must be "cheated".

4-9. Located on the left side of the instrument, behind bulkhead, is an extender card A8. This board is used as an extender for the plug-in circuit board assemblies to provide access to adjustments and test points.

CAUTION!

Remove all power from the instrument before removing or inserting plug-in circuit boards.

Remove the plug-in circuit board assembly to be investigated, insert the extender card in its place, and plug the circuit board assembly in the extender card.

4-10. Unique Maintenance Procedures

4-11. CLEANING OF BOARDS. Certain circuit board assemblies are ultrasonically cleaned at the factory to prevent the possibility of electrical leakage caused by contamination from handling during assembly. These circuit board assemblies include the Sample String P/C Assembly (A2), and Capacitor P/C Assembly (A1). When components are replaced on these assemblies that require soldering, the land pattern side of the board should be cleaned as described in paragraph 4-12. Should contamination be suspected on the component side of the circuit board, use Freon TF Degreaser (Miller-Stephenson Chemical Co.).

4-12. CIRCUIT BOARD SEALANT. The land pattern side of all printed circuit boards have been coated with epocast (a polyurethane resin) to inhibit fungus growth and moisture absorption. When soldering to a printed circuit land, the heat from the soldering iron decomposes the epocast resin, leaving a charred residue. Upon completion of soldering, the residue should be removed with a solvent such as toluol.

4-13. After removal of the epocast residue, the affected area should be recoated with a sealant. A spray can of Circuit Coat (Furane Plastic Inc., 4516 Brazil Street, Los California or 16 Spielman Road, Fairfield, New Jersey) may be used for recoating.

4-14. Fuse Replacement

4-15. The fuses are contained in bayonet type fuse holders located at the rear of the instrument. Listed below are the correct values for the fuses:

REF. DESIG	FUNCTION	TYPE
F1	High Voltage	¼A, slow blow
F2	Line	3A, slow blow, 115V conn. 1½A, slow blow, 230V conn.

Under no circumstances should replacement fuses with higher current ratings be installed in the instrument.

4-16. Lamp Replacement

4-17. The indicator lamps are located immediately behind the front panel. The instrument must be partially removed from the case to gain access to the lamps. The decimal lamps are easily accessible and removable from the instrument without the need of any special tools.

4-18. 115/230V Conversion

4-19. Depending upon the connection of the power transformers primary windings, the instrument may be operated from either a 115 or 230 volt ac power line. To convert the instrument from one type of power line operation to the other, use the following procedure:

a. Disconnect the line cord from the power line.

b. Remove the instrument from the case and place upside down on a suitable work space.

c. Orient the instrument and perform the appropriate electrical connections as illustrated in Figure 4-1.

d. Use the proper fuse corresponding to the selected conversion, as discussed in paragraph 4-14.

4-20. PERFORMANCE TESTS

4-21. Introduction

4-22. The following tests are intended for checking performance of the instrument. These tests may be used for incoming inspection, periodic inspections and precalibration checks. It is recommended that these tests be performance prior to calibration.

4-23. Each performance test includes an introductory paragraph which states the purpose of the test and describes the circuitry involved. An understanding of the purpose of each test and the circuitry involved should aid a technician in analyzing a malfunction.

4-24. During the following tests, it will not be necessary to remove the instrument from the case. All external equipment will be connected to the terminals provided on the instrument. Table 4-1 lists the equipment needed for testing and calibrating.

4-25. The load, line and ripple checks do not rely on any calibration adjustments; any major or minor indication should be investigated by troubleshooting. The remaining voltage standard checks do rely on proper calibration adjustments. Should minor out of tolerance indications be observed during these checks, calibration will more than likely correct these problems. However, should the calibration adjustments be ineffectual or at their extreme limits, you will have to investigate the cause of the problem.



Figure 4-1. 115/230 VAC CONVERSION

EQUIPMENT REQUIRED	SPECIFICATIONS REQUIRED
Volt/Ohmmeter - RCA VoltOhmyst or equivalent	DC Accuracy of ± 3% and input impedance of 10 M Ω
Metered Autotransformer - General Radio Variac W5MT3A or equivalent	Output of 0 to 130 vac at 3 amperes.
DC Differential Voltmeter - Fluke Model 895A or equivalent (quantity of 2 required)	DC Accuracy of ±0.0025% with 100 uv null detector
RMS Voltmeter - Fluke Model 931B or equivalent	Accuracy of ±(0.05% of input +0.005% of range) from 30 Hz to 50 kHz.
Preamplifier	Gain of 1000 and bandpass of 20 Hz to 30 kHz
Oscilloscope - Tektronix Type 541 or equivalent Preamplifier - Tektronix Type D	General purpose 1 mv / cm sensitivity
General Purpose Power Supply	Provide 5.5 volts
DC Milliammeter	0 to 100 milliamperes ±5%
Load Resistor Box - Clarostat 240-C	Resistance range of 20 to 20,000Ω at ±5%. Capable of handling up to 80 watts
Resistor, Composition	100k Ω ±5%, ½w

Table 4-1. TEST AND CALIBRATION EQUIPMENT REQUIRED (Sheet 1 of 2)

EQUIPMENT REQUIRED	SPECIFICATIONS REQUIRED
Lead Set	Low-leakage, low-thermal emf
Standard Cell Enclosure- Guildline Model 9152	Accuracy of ±0.0003%
DC Voltage Calibration System - Fluke Model 7101B consisting of the following equipment, or an equivalent system: Voltage Standard, Model 332D Null Detector, Model 845AR Voltage Divider, Model 750A Kelvin-Varley Voltage Divider, Model 720A	Capable of measuring 0.1 to 1100 vdc with 5 ppm accuracy

Table 4-1. TEST AND CALIBRATION EQUIPMENT REQUIRED (Sheet 2 of 2)

4-26. In the event that a malfunction is discovered, complete as many of the performance tests as possible. Record which tests the instrument does not successfully pass and any abnormal indications. This will help in analyzing the problem and lead to more efficient troubleshooting.

4-27. DC Output

4-28. LINE REGULATION. The line regulation test determines whether the output voltage will remain constant, within specified limits, for a low to high line input power change.

a. Connect the line cord through an autotransformer connected to an ac power line. Set the autotransformer to 115 volts ac.

b. Set the front panel controls as follows:

POWER	STDBY/RESET
METER	CURRENT
RANGE	10
READOUT	All Zero
VOLTAGE TRIP	1000
VERNIER	Clockwise
CURRENT LIMIT	Clockwise (60)

c. Connect the Model 895A to the SENSE terminals and set to plus polarity. Connect the 240-C Load Resistor Box to the OUTPUT terminals of the Model 332D.

d. Set the RANGE switch, readout dials, and load box to the values indicated in the first group of settings in Table 4-2. Set the POWER switch to the OPR position. Note the voltage indicated on the Model 895A. Set the autotransformer to low line (103V). The output voltage change, indicated on the Model 895A, should not exceed the specification listed in Table 4-2. Adjust the autotransformer setting to nominal line (115V). Note the voltage indication on the Model 895A. Set the autotransformer to high line (127V). The voltage change, indicated on the Model 895A, should not exceed the 20 microvolt specification. Repeat this procedure for each group of settings in Table 4-2.

4-29. LOAD REGULATION. The load regulation test determines if the output voltage will remain constant, within specified limits, when the output is subjected to a no-load to full-load condition.

a. Connect the line cord to an autotransformer connected to an ac power line. Set the autotransformer to 115 volts ac.

b. Set the front panel controls as follows:

POWER	STDBY/RESET
METER	CURRENT
RANGE	10
Readout	All Zero
VOLTAGE TRIP	1000
VERNIER	Clockwise
CURRENT LIMIT	Clockwise (60)

c. Connect the Model 895A to the SENSE terminals.

d. Set the RANGE switch and Readout Dials to the values indicated in the first group of settings listed in the Table 4-3. Set the POWER switch to the OPR position. Note the voltage indicated on the Model 895A. Connect the 20-ohm load to the OUTPUT terminals and note output voltage change on the Model 895A. The change should not exceed the specification listed in the table. Repeat step d. for each group of settings.

e. Repeat step d. for low line (103V) and high line (127V).

4-30. RIPPLE. The ripple test determines if an ac component superimposed on the dc output is within specified limits.

a. Connect the preamplifier to the OUTPUT terminals. Connect the Model 931 RMS Voltmeter to the output of the preamplifier.

b. Set the front panel controls as follows:

POWER	STDBY/RESET
METER	CURRENT
RANGE	10
Readout	All Zero
VOLTAGE TRIP	1000
VERNIER	Clockwise
CURRENT LIMIT	Clockwise (60)

c. With the autotransformer set to nominal line voltage (115 vac), set the POWER switch to OPR. The ripple output should not exceed 20 microvolts.

NOTE!

Ripple indication is via 1000X preamplifier.

d. Set the readout dials to 10 volts. The ripple output should not exceed 20 microvolts rms.

e. Connect the 200-ohm load resistor to the OUTPUT terminals. The ripple output should not exceed 20 microvolts rms. Disconnect the load resistor.

f. Set the readout dials to zero, and set the RANGE switch to 100. The ripple output should not exceed 30 microvolts rms.

g. Set the readout dials to 100 volts. The ripple output should not exceed 30 microvolts rms.

h. Connect the 2,000-ohm load resistor to the OUTPUT terminals. The ripple output should not exceed 30 microvolts rms. Disconnect the load resistor.

i. Set the readout dials to zero, and set the RANGE switch to 1000. The ripple output should not exceed 40 microvolts rms.

RANGE	READOUT	LOAD (50 ma)	SPEC.
10	1.000000	20Ω	10 uv
10	10.000000	200Ω	20 uv
100	10.00000	200Ω	20 uv
100	100.00000	2000Ω	200uv
1000	100.0000	2000Ω	200uv
1000	1000.0000	20,000Ω	2.0 mv

Table 4-2. CONTROL SETTINGS, LOAD REQUIREMENTS, AND LIMITS FOR LINE REGULATION

RANGE	READOUT	LOAD(50 ma)	SPEC.
10	1.000000	20Ω	10 uv
10	10.000000	200Ω	20 uv
100	10.00000	200Ω	20 uv
100	100.00000	2000Ω	200 uv
1000	100.0000	2000Ω	200 uv
1000	1000.0000	20,000Ω	2.0 mv

Table 4-3. CONTROL SETTINGS, LOAD REQUIREMENTS, AND LIMITS FOR LOAD REGULATION

j. Set the readout dials to 1000 volts. The ripple output should not exceed 40 microvolts rms.

k. Connect the 20,000-ohm load resistor to the OUTPUT terminals. The ripple output should not exceed 40 microvolts rms. Disconnect the load resistor.

4-31. VOLTAGE STANDARD ACCURACY. If the voltage standard has successfully passed the line, load, and ripple specifications, it can be assumed to be operating correctly. The output voltage can now be checked and compared to the specifications. These checks should be accomplished after the unit has warmed up for 1 hour at standard reference conditions of 23°C ±1°, up to 70% relative humidity, and constant line voltage. One method of checking the instrument accuracy is by comparing the voltages to a saturated standard cell by means of a reference divider. Use the equipment and connections shown in Figure 4-4 and the procedure of paragraph 4-53, steps l. through t.

4-32. Meter and Protection Circuits

4-33. V-I MONITOR. This procedure checks the output voltage and current monitor circuitry associated with the front panel meter.

a. With the METER switch in the VOLTAGE position, set the RANGE switch and readout dials for 100 volts output.

b. The front panel meter should indicate 100 volts ±3.0 volts.

c. Check the meter linearity at the following cardinal points, Table 4-4. All meter indications should be within ±3% of full scale.

RANGE	READOUT
10	1.000000
100	10.00000
1000	100.0000
10	10.000000
1000	1000.0000

Table 4-4. CONTROL SETTINGS FOR V-I MONITOR TEST

d. Set the RANGE switch to 10 volts, the readout dials to 5 volts, the CURRENT LIMIT control maximum clockwise, and the METER switch to CURRENT.

e. Connect a 0 to 100 dc milliammeter across the OUTPUT terminals.

f. Rotate the CURRENT LIMIT control counter-clockwise until the external meter indicates 50 milliamperes. The front panel meter of the Model 332D should indicate 50 milliamperes on the red scale.

g. Set the RANGE switch to 100 volts, then to 1000 volts. The front panel meter should indicate 50 milliamperes in each position of the RANGE switch.

4-34. CURRENT LIMIT. This check determines the range of the CURRENT LIMIT control, which should be 0.5 to 60 milliamperes.

a. Set the POWER switch to STDBY/RESET, the RANGE switch to 10 volts, the readout dials to 5 volts, and the CURRENT LIMIT control maximum clockwise.

b. Connect a 0 to 100 dc milliammeter across the output terminals.

c. Set the POWER switch to OPR. The external meter should indicate 60 milliamperes.

d. Rotate the CURRENT LIMIT control maximum counter-clockwise. The external meter should indicate 0.5 milliamperes.

4-35. VOLTAGE TRIP. This test determines if the trip circuit will actuate during an overvoltage condition on each RANGE setting.

a. Set the TRIP VERNIER maximum clockwise. Set the RANGE VOLTAGE TRIP, and readout dials to the values indicated in Table 4-5. In each case, rotate the VERNIER counter-clockwise from the maximum clockwise position until the trip circuitry just actuates. In each case the VERNIER control should be approximately 30° from the maximum clockwise position.

RANGE	VOLTAGE TRIP	READOUT DIALS
10	10	10.X00000
100	100	10X.00000
1000	1000	10XX.X00

Table 4-5. CONTROL SETTINGS FOR VOLTAGE TRIP CHECK

b. Set the output of the instrument for 4 volts on the 10 volt range. Set the VOLTAGE TRIP switch to the 10 volt position and the VERNIER control to the 12 o'clock position.

c. Set the RANGE switch to 100 volts. The trip circuit should actuate.

d. Set the VOLTAGE TRIP switch to the 100 volt position and reset the instrument.

e. Set the RANGE switch to the 1000 volt position. The trip circuit should actuate.

f. Set the VOLTAGE TRIP switch to the 1000 volt position and the VERNIER maximum clockwise. Re-set the instrument.

g. Set the RANGE switch to 100 volts then to 10 volts. The trip circuit should not actuate in either position.

4-36. CALIBRATION

4-37. Introduction

4-38. The following procedures are intended for calibration. The equipment required is listed in Table 4-1. During the first portion of the calibration procedure, the chassis will have to be removed from the case and the top inner cover removed from the chassis. However, upon removal of the top inner cover it will be necessary to "cheat" the interlock located at the top right-hand edge of the instrument chassis.

4-39. Meter Mechanical Zero

4-40. With the instrument de-energized for at least 3 minutes, adjust the mechanical zero screw (located just below the front panel meter) so that the meter pointer is over the zero position.

4-41. Auxiliary Circuits

4-42. AUXILIARY POWER SUPPLY. With the POWER switch in the OFF position, connect the instrument through an autotransformer to the power line. Adjust the autotransformer for nominal line voltage. Extend the Auxiliary Power Supply P/C Assembly (A5A5) on the extender card provided. Set the POWER switch to the STDBY/RESET position. Allow approximately 10 minutes for warm-up; then proceed as follows:

a. Using the +SENSE terminal as common, connect a Model 895A to pin 10 on the Auxiliary Power Supply P/C Assembly.

b. Referring to Figure 4-2, adjust A5A5 R9 until the Model 895A indicates 25 volts, ±10 millivolts.

c. While varying the line voltage from 100 to 130 volts ac, the Model 895A indication should not change more than 40 millivolts.

d. Set the POWER switch on OFF and disconnect the Model 895A. Replace the Auxiliary Power Supply P/C Assembly. Return the POWER switch to the STDBY/RESET position.

4-43. CURRENT LIMIT. Proceed as follows:

a. Set the front panel controls as follows:

POWER	STDBY/RESET
RANGE	10
Readout Dials	5.000000
VOLTAGE TRIP	1000
VERNIER	maximum clockwise
CURRENT LIMIT	maximum clockwise

b. Connect a 0 to 100 dc milliammeter across the OUTPUT terminals. Set the POWER switch to OPR.

c. Referring to Figure 4-2, adjust R23 for a 60 milliampere indication on the external meter.

d. Rotate the CURRENT LIMIT control maximum counter-clockwise. Adjust R24 for a 0.5 milliampere indication on the external meter.

e. If necessary, re-adjust R23 and R24 until the range of the CURRENT LIMIT control is from 0.5 to 60 milliamperes.

f. Set the POWER switch to STDBY/RESET and install the top inner cover.

4-44. OUTPUT CURRENT MONITOR. Proceed as follows:

a. Set the METER switch to CURRENT and POWER switch to OPR.

b. Adjust the CURRENT LIMIT control to obtain a 50 milliampere indication on the external meter.



Figure 4-2. LOCATION OF ADJUSTMENTS

c. Rotate the adjustment labeled OUTPUT CURRENT METER ADJUST until the front-panel meter pointer indicates 50 milliamperes on the red scale.

d. Set the RANGE switch to 100 volts; then to 1000 volts. The front-panel meter should indicate 50 milliamperes in each position of the RANGE switch.

e. Set the POWER switch to STDBY/RESET and remove the external meter connections.

4-45. OUTPUT VOLTAGE MONITOR. Proceed as follows:

a. Set the front panel controls as follows:

POWER	OPR
METER	VOLTAGE
RANGE	100
Readout Dials	100.00000

b. Rotate the adjustment labeled OUTPUT VOLTMETER ADJUST until the front-panel meter indicates 100 volts ±0.5 volts.

c. Meter linearity may be checked at the cardinal points listed in Table 4-6. All full-scale meter indications should be within ±3% of full scale.

RANGE	READOUT DIALS
10	1.000000
100	10.00000
1000	100.0000
10	10.000000
1000	1000.0000

Table 4-6. CONTROL SETTINGS FOR VOLTAGE MONITOR LINEARITY CHECK

4-46. VOLTAGE TRIP. Proceed as follows:

a. Set the front panel controls as follows:

RANGE	100
Readout Dials	10X.00000
VOLTAGE TRIPOUT ADJUST (topcover)	maximum counter-clockwise
VOLTAGE TRIP	100
VERNIER	30° from maximum

b. Rotate the VOLTAGE TRIPOUT ADJUST until the output is de-energized, as indicated by the illumination of the red indicator lamp and the audible "click" of relays.

c. Set the POWER switch to STDBY/RESET. Rotate the VERNIER control to the maximum clockwise position.

d. Set the POWER switch to OPR. Set the RANGE switch, TRIP switch, and readout dials as listed in Table 4-7. Check the trip action on each range by rotating the VERNIER control counter-clockwise. The trip point should occur in each RANGE switch position when the VERNIER control is approximately 30° from the maximum clockwise position.

TRIP	RANGE	READOUT DIALS
10	10	10.X00000
1000	1000	10XX.X000

Table 4-7. CONTROL SETTINGS FOR TRIP RANGE CHECK

4-47. MASTER REFERENCE. Proceed as follows:

a. Set the front panel controls as follows:

POWER	ON
RANGE	1000
Readout Dials	00X.0000
VOLTAGE TRIP	1000
VERNIER	Maximum clockwise
CURRENT LIMIT	Maximum clockwise

b. Connect a Model 895A to the MASTER REFERENCE test points through the top inner cover.

c. Adjust CAL 1000V, CAL 100V and CAL 10V mechanically to mid-point of travel.

d. Rotate the REF VOLTAGE ADJUST to obtain an indication of 15.00 volts (±10 uV) on the Model 895A.

e. Set the POWER switch to STDBY/RESET.

4-48. Voltage Standard Output

4-49. The voltage standard is calibrated by setting the zero output and adjusting the sample string resistors and the range resistors. Adjustment of sample string resistors determines output voltage ratio accuracy and adjustment of the range resistors determines absolute voltage accuracy. The linearization adjustment involves adjusting corresponding resistors in adjacent decades so they are in exact ten-to-one ratio with each other.

4-50. This procedure is divided into sections, initial and final. Both procedures are to be performed if any servicing has been done. The Final calibration need only be done if the instrument is operating normally and requires certification.

4-51. **INITIAL CALIBRATION.** The following adjustments should be performed whenever repairs have been made to the Model 332D. After completion, however, the adjustments given under Final Calibration must also be done.

4-52. The instrument should be warmed up for at least four hours at standard reference conditions of 23°C ±1°C, up to 70% relative humidity and constant line voltage before adjustments are made. The instrument must be operated in its case with the RANGE switch and readout dials set for 100 volts output.

a. Set the Model 332D controls as follows:

POWER	ON
RANGE	1000
Readout Dials	00X.0000
VOLTAGE TRIP	1000
VERNIER	Maximum Clockwise
CURRENT LIMIT	Maximum Clockwise

b. Connect a Model 895A to the MASTER REFERENCE test points through the top inner cover.

c. Rotate the REF VOLTAGE ADJUST to obtain an indication of 15.0 volts (±10 uV) on the Model 895A.

d. Connect a Model 845AR null detector across the OUTPUT terminals. Set the voltage standard dial readout to all zeros and the POWER switch to OPR.

e. At each RANGE switch position, vary the corresponding ZERO OUTPUT ADJUST (10V, 100V, 1000V) for a null indication (±2 microvolt) on the null detector.

f. Connect the 895A to the OUTPUT terminals of the 332D with the voltmeter common connected to the positive (+) output.

g. Set RANGE switch and decades on the 332D as listed in Table 4-8. Null the 895A reading or adjust the specified Sample String adjustment potentiometer.

h. Leave the 895A connected as in step f.

i. Set the RANGE and decades on the 332D as listed in Table 4-9. Adjust the 895A to 10.0 00 00 volts. Adjust the range calibration pots (CAL) shown in Figure 4-2 as required.

j. Set the Model 332D controls as follows:

POWER	STDBY/RESET
RANGE	10
Readout Dials	5.000000
VOLTAGE TRIP	1000
VERNIER	Maximum Clockwise
CURRENT LIMIT	Maximum Clockwise

Range	Dial Setting	Adjust 895A to:		Adjust *
1000	00 0X 00 0	Null Reading	- -	
1000	00 10 00 0	- - - - - - -	1	
1000	00 1X 00 0	Null Reading	- -	
1000	00 20 00 0	- - - - - - -	2	
1000	00 3X 00 0	Null Reading	- -	C Decade
1000	00 40 00 0	- - - - - - -	4	
1000	00 7X 00 0	Null Reading	- -	
1000	00 80 00 0	- - - - - - -	8	
1000	00 X0 00 0	Null Reading	- -	
1000	01 00 00 0	- - - - - - -	1	
100	01 X0 00 0	Null Reading	- -	
100	02 00 00 0	- - - - - - -	2	
100	03 X0 00 0	Null Reading	- -	B Decade
100	04 00 00 0	- - - - - - -	4	
100	07 X0 00 0	Null Reading	- -	
100	08 00 00 0	- - - - - - -	8	
100	0X 00 00 0	Null Reading	- -	
100	10 00 00 0	- - - - - - -	1	
10V	1X 00 00 0	Null Reading	- -	
10V	20 00 00 0	- - - - - - -	2	
10V	3X 00 00 0	Null Reading	- -	A Decade
10V	40 00 00 0	- - - - - - -	4	
10V	7X 00 00 0	Null Reading	- -	
10V	80 00 00 0	- - - - - - -	8	

* Adjust the specified Sample String potentiometers to within ±2μ volts of the previous null reading.

Table 4-8. SAMPLE STRING PRE-LINEARIZATION

332D Range	332D Dial Setting	Adjust 895A To:	Adjust
10V	100 00 00 0	10.0 00 00	10V CAL to null
100V	10 00 00 0	10.0 00 00	100V CAL to null
1000V	01 00 00 0	10.0 00 00	1000V CAL to null

Table 4-9. PRELIMINARY RANGE CALIBRATION

k. Connect a 0 to 100 dc milliammeter across the OUTPUT terminals. Set the POWER switch to OPR.

l. Referring to Figure 4-2, adjust R23 for a 60 milliampere indication on the external meter.

m. Rotate the CURRENT LIMIT control maximum counter-clockwise. Adjust R24 for approximately 0.5 milliampere indication on the external meter.

n. If necessary, re-adjust R23 and R24 until the range of the CURRENT LIMIT control is from 0.5 to 60 milliamperes.

o. Set the POWER switch to STDBY/RESET. Replace the top inner cover on the Model 332D.

p. Set the METER switch to CURRENT and POWER switch to OPR.

q. Adjust the CURRENT LIMIT control to obtain a 50 milliampere indication on the external meter.

r. Rotate the adjustment labeled OUTPUT CURRENT METER ADJUST until the front-panel meter pointer indicates 50 milliamperes on the red scale.

s. Set the RANGE switch to 100 volts; then to 1000 volts. The front-panel meter should indicate 50 milliamperes in each position of the RANGE switch.

t. Set the POWER switch to STDBY/RESET. Remove the external meter connections from Model 332D.

u. Set the Model 332D front panel controls as follows:

POWER	OPR
METER	VOLTAGE
RANGE	100
Readout Dials	100.00000

v. Rotate the adjustment labeled OUTPUT VOLTMETER ADJUST until the front-panel meter indicates 100 volts ±0.5 volts.

w. Meter linearity may be checked at the cardinal points listed in Table 4-10. All full-scale meter indications should be within ±3% of full scale.

RANGE	READOUT DIALS
10	1.000000
100	10.00000
1000	100.0000
10	10.000000
1000	1000.0000

Table 4-10. CONTROL, SETTINGS FOR VOLTAGE MONITOR LINEARITY CHECK

x. Set the Model 332D controls as follows:

RANGE	1000V
Readout Dials	125.0000
VOLTAGE TRIPOUT ADJUST (top cover)	Maximum Counter-clockwise
VOLTAGE TRIP	100
VERNIER	Fully Clockwise

y. Rotate the VOLTAGE TRIPOUT ADJUST until the output is de-energized, as indicated by the illumination of the red indicator lamp and the audible "click" of relays.

z. Set RANGE to 10 and reset the instrument.

aa. Set the POWER switch to OPR. Set the RANGE switch, TRIP switch, and readout dials as listed in Table 4-11. Check the trip action on each range by rotating the VERNIER control counter-clockwise. The trip point should occur in each RANGE switch position when the VERNIER control is approximately 30° from the maximum clockwise position.

TRIP	RANGE	READOUT DIALS
10	10	10.X00000
1000	1000	10XX.X000

Table 4-11. CONTROL SETTINGS FOR TRIP RANGE CHECK

ab. Set the output of the instrument for 4 volts on the 10 volt range. Set the VOLTAGE TRIP switch to the 10 volt position and the VERNIER control to the 12 o'clock position.

ac. Set the RANGE switch to 100 volts. The trip circuit should actuate.

ad. Set the VOLTAGE TRIP switch to the 100 volt position and reset the instrument.

ae. Set the RANGE switch to the 1000 volt position. The trip circuit should actuate.

af. Set the VOLTAGE TRIP switch to the 1000 volt position and the VERNIER maximum clockwise. Re-set the instrument.

ag. Set the RANGE switch to 100 volts then to 10 volts. The trip circuit should not actuate in either position.

4-53. FINAL CALIBRATION. The following procedure should be performed to accomplish the final linearization of the Sample String and the Range Calibration on the 332D.

a. Connect a Model 845AR null detector across the OUTPUT terminals. Set the voltage standard dial readout to all zeros and the POWER switch to OPR.

b. At each RANGE switch position, vary the corresponding ZERO OUTPUT ADJUST (10V, 100V, 1000V) for a null indication (±1 microvolt) on the voltmeter.

c. Self-calibrate the 720A using the procedure contained in its instruction manual.

d. Using the 7101B DC Voltage Calibration System make the equipment connections shown in Figure 4-3.

e. Set the readout dials of the 720A to the standard cell voltage (e.g., ".1018000").



Figure 4-3. CONNECTIONS FOR SAMPLE STRING LINEARIZATION

f. Set switch S1 to position A.

g. Adjust the output of the 332D (approximately 11V) for a null indication (±1 microvolt) on the 845AR.

h. Set OPERATE switch on 845AR to zero. Set switch S1 to position B.

i. Set the RANGE and readout dials to the values listed in Table 4-12 and adjust the RANGE CAL or SAMPLE STRING ADJUST potentiometers as indicated.

STEP	720 SETTING	332D RANGE	332D DIAL SETTING	NULL ADJUSTMENT	845AR NULL
1	0000000	1000V	000.0000	1 845AR	±1 uV
2	.1000000	1000V	000.X000	1000V CAL	±1 uV
3	.1000000	1000V	001.0000	DECK C – 1	±1 uV
4	.2000000	1000V	002.0000	DECK C – 2	±1 uV
5	.4000000	1000V	004.0000	DECK C – 4	±2 uV
6	.8000000	1000V	008.0000	DECK C – 8	±4 uV
7	1.0000000	1000V	00X.0000	2 720A	±5 uV
8	Step 7 null	1000V	010.0000	DECK B – 1	±5 uV
9	0000000	100V	00.00000	1 845AR	±1 uV
10	.1000000	100V	01.00000	100V CAL	±1 uV
11	.2000000	100V	02.00000	DECK B – 2	±1 uV
12	.4000000	100V	04.00000	DECK B – 4	±2 uV
13	.8000000	100V	08.00000	DECK B – 8	±4 uV
14	1.0000000	100V	0X.00000	2 720A	±5 uV
15	Step 14 null	100V	10.00000	DECK A – 1	±5 uV
16	0000000	10V	0.000000	1 845AR	±1 uV
17	.1000000	10V	1.000000	10V CAL	±1 uV
18	.2000000	10V	2.000000	DECK A – 2	±1 uV
19	.4000000	10V	4.000000	DECK A – 4	±2 uV
20	.8000000	10V	8.000000	DECK A – 8	±4 uV

1 Adjust the 845AR ZERO ADJ to obtain a system zero.

2 Adjust the 720A readout dials for a null on the 845AR. Retain this setting for the next step.

Table 4-12. FINAL LINEARIZATION OF DECK C, B AND A

j. Repeat steps a. through h., paragraph 4-53.

k. Set the RANGE and readout dials to the values listed in Table 4-13 and adjust the RANGE CAL potentiometers as indicated.

NOTE!

The calibration of the 332B should now be checked to ensure that it meets the accuracy specifications.

l. Using the 7101B DC Voltage Calibration System make the equipment connections shown in Figure 4-4.

m. Set the Standard cell voltage on the standard cell readout dials of the 750A.

n. Set the instruments to the settings shown in step 1 of Table 4-14.

o. Connect the 845AR across the output terminals of the 332D. The 845AR should read zero volts and be within the tolerance specified in Table 4-14.

p. Connect the 845AR to test points A shown in Figure 4-4.

q. Set the instruments to the settings shown in step 2 of Table 4-14.

r. Switch in the null indicator with the switch on the 750A and adjust the output of the 332D for a null indication (±1 microvolt) on the 845AR. The 332D should read ≈ 1100 volts.

s. Connect the 845AR to test points B shown in Figure 4-4. The null indicator should read within the tolerance specified for this step in Table 4-14.

t. Perform the remaining checks in Table 4-14 by setting the instruments as specified in each step and checking the specified tolerance against the 845AR null indicator. The steps that are marked with a flag should be performed as in instruction o. of this paragraph.

WARNING!

During this procedure high voltage is present at the terminals of all test instruments except the standard cell. When relocating the null indicator the output of the 332D should be set to zero volts.

720A SETTING	332D RANGE	332D DIAL SETTING	NULL ADJUSTMENT	845AR NULL
1.0000000	1000V	010.0000	1000V CAL	±5 uV
1.0000000	100V	10.00000	100V CAL	±5 uV
1.0000000	10V	10.000000	10V CAL	±5 uV

Table 4-13. FINAL RANGE CALIBRATION



Figure 4-4. CONNECTIONS FOR RANGE CALIBRATION CHECKS

	STEP	750A SETTING INPUT	750A SETTING OUTPUT	332D RANGE	332D DIAL SETTING	TOLERANCE
1	1	- - -	- - -	10V	0.000000	±10 uV
	2	1100	5	10V	5.000000	±60 uV
	3	1100	10	10V	10.000000	±110 uV
1	4	- - -	- - -	100V	00.00000	±20 uV
	5	1100	5	100V	05.00000	±70 uV
	6	1100	10	100V	10.00000	±120 uV
	7	1100	50	100V	50.00000	±520 uV
	8	1100	100	100V	100.00000	±1020 uV
1	9	- - -	- - -	1000V	000.0000	±200 uV
	10	1100	5	1000V	005.0000	±275 uV
	11	1100	10	1000V	010.0000	±350 uV
	12	1100	50	1000V	050.0000	±950 uV
	13	1100	100	1000V	100.0000	±1700 uV
	14	1100	500	1000V	500.0000	±7.7 mV
	15	1100	1000	1000V	1000.000	±15.2 mV
	16	1100	1100	1000V	10X0.0000	±16.7 mV
	17	1100	1100	1000V	1099.999X	±16.7 mV

1 Perform this test as described in step o., paragraph 4-53.

Table 4-14. CONTROL SETTINGS AND TOLERANCES FOR CALIBRATION CHECK

4-54. TROUBLESHOOTING

4-55. A thorough understanding of the principles of operation is necessary to efficiently troubleshoot the instrument. It is recommended that Section 3 be reviewed before attempting to troubleshoot the unit.

4-56. The following troubleshooting procedure is in such sequence that it can be applied to any unit, including one in which the trouble is totally unknown and there is doubt whether power can be applied without causing damage. If the unit is operable, the Resistance Measurement and the Standby Power Check, Paragraphs 4-57 and 4-59 may be omitted. The checkout follows the guidelines listed below, and is intended to localize the trouble to an assembly which may be tested individually.

a. Remove the Pre-Regulator P/C Assembly.

b. Check all auxiliary supplies and the reference voltage.

c. Check the Control Amplifier to ensure that it operates properly when provided with an error signal.

d. Verify that the Pre-Regulator is being turned on and off by the Unijunction Oscillator.

When it can be verified that the Pre-Regulator is controlling power to the High Voltage Rectifier, the POWER switch may be set to the OPR position and the Series Pass Element checked.

WARNING !

The inner chassis is at the same potential as the +OUTPUT terminal. Avoid contact with the inner chassis and exposed parts. The Pre-Regulator circuitry is at line voltage above ground. When changing P/C boards, use the POWER switch OFF position and wait a few seconds after removing power to allow capacitors to discharge. When changing the Pre-Regulator Assembly, set the POWER switch to OFF.

4-57. Resistance Measurements

4-58. These checks verify correct output resistance of auxiliary voltage supplies. A check of the sample string may reveal an open resistor, which is sometimes a cause of loss of regulation. An ohmmeter (RCA VoltOhmyst or equivalent) is required for this test.

a. Disconnect the instrument power plug from ac power. Disengage the chassis from the case by loosening the two Dzus fasteners on the rear of the instrument. Slide the unit out of the case and remove the top inner cover. This will open the interlock.

b. Remove the Pre-Regulator P/C Assembly. Set the instrument POWER switch to OFF and set the front panel controls as follows:

POWER	OFF
METER	V
VOLTAGE RANGE	100V
VOLTAGE TRIP	1000V
VERNIER	Fully Clockwise (CW)
CURRENT LIMIT	Fully Clockwise (CW)
Decade Dials	50.00000

c. Measure the resistance between the following test points and the +SENSE terminal. Connect the assembly to the mother board by using the extender card.

ASSEMBLY	PIN	RESISTANCE (Approx.)
Auxiliary Power Supply	9	8.4 kilohms
Auxiliary Power Supply	10	2.1 kilohms
Current Limiter	1	6.0 kilohms
Current Limiter	3	3.0 kilohms

d. Disconnect the shorting links between the SENSE and OUTPUT terminals. Remove the Differential Amplifier Assembly and connect an ohmmeter between pin 5 of the Differential Amplifier socket and the negative SENSE terminal. The ohmmeter should indicate less than 0.5 ohm. Step each dial through its range; the resistance should increase according to the following table. Return each dial to zero after checkout.

NOTE!

This check detects gross errors only, such as an open resistor. Resistors are factory selected for accuracy and temperature coefficient.

READOUT DIAL	RESISTANCE INCREASE OHMS PER STEP
Seventh	0.1
Sixth	1.0
Fifth	10
Fourth	100
Third	1000
Second	10,000
First	100,000

e. Reconnect the links between the SENSE and OUTPUT terminals and replace the Differential Amplifier Assembly.

4-59. Standby Power

4-60. This check measures power consumption in the STDBY/RESET mode. It reveals possible gross faults such as wiring errors or shorted components in the auxiliary power supply, voltage control circuitry and protection circuitry. A metered Variac and differential voltmeter are required for this test.

a. Remove the top inner cover and the Pre-Regulator Assembly if not already accomplished.

b. Connect the instrument through a Variac to a 115 volt, 60 Hz, power line with a wattmeter or ammeter in series between the Variac and the instrument. Set the Variac output to zero. Set the front panel controls as follows:

POWER	OFF
VOLTAGE RANGE	100
VOLTAGE TRIP	1000
VERNIER	maximum clockwise
CURRENT LIMIT	maximum clockwise
Readout Dials	50.00000

c. Set the POWER switch to STDBY/RESET and slowly increase the output of the Variac to 115 volts. The CURRENT LIMIT and center decimal lights should come on and the time delay relay (A6-K2001) should operate. The wattmeter should indicate 30 to 40 watts power drain.

4-61. Auxiliary Supply Voltages

4-62. This procedure checks out the bias voltages, master reference voltage and the series pass element voltage.

a. Using the Model 895A differential voltmeter, measure the voltage between the test points listed in Table 4-15 and the +SENSE terminal, which is common.

b. Where indicated, perform the adjustment to determine that it can be made. These should be re-checked during calibration of the instrument.

ASSEMBLY	PIN	VOLTS DC
Auxiliary Power Supply	10	23 to 27 [1]
Auxiliary Power Supply	9	-14 to -16
Current Limiter	1	-33 to -39
Current Limiter	3	33 to 39
Range Cal	Test Points	14.9 to 15.1 [2]
Reference Supply	Collector Q1	26 to 35 [3]
Series Pass	Collector Q8	Approx. 140
Rear bulkhead power resistor, 100 kilohms	Yellow lead	650 to 725

[1] Adjustable to 25 volts ±10 mv with R9

[2] Adjustable to 15.0 volts ±10 uV with R9 on Reference Supply pcb

[3] Approximately 1 volt at turn-on, rising to 26 to 35 volts after 10 minute warm up.

Table 4-15. REFERENCE AND AUXILIARY VOLTAGES

4-63. Unijunction Oscillator and Chopper Amplifier

4-64. UNIJUNCTION OSCILLATOR. This check verifies operation of the unijunction oscillator and the flow of error signal through the chopper amplifier, differential amplifier and series pass driver. An oscilloscope is required for this test.

a. Connect the oscilloscope with a 10X isolation probe between pins 14 (common) and 15 (input) of the Series Pass P/C Assembly. Set the oscilloscope sweep speed to 1 milliseconds/cm and vertical sensitivity to 1 volt/cm.

b. Set the POWER switch to STDBY/RESET. Positive going pulses of 1.0 to 2.0 volts peak-to-peak should be observed.

4-65. CHOPPER AMPLIFIER. This procedure checks the alignment and response of the Chopper Amplifier in the 332D. An oscilloscope and a general purpose supply are required for this test. To check alignment:

a. Install the Chopper Amplifier assembly on the extender card. Connect an oscilloscope to the base of Q3 on the Chopper Amplifier Board. The scope common should be connected to Pin 13 of the card connector. Connect a clip lead between Pin 6 and Pin 12 of the input connector.

b. Turn the POWER switch to STDBY/RESET. Turn the CHOPPER DRIVE ADJUST (R43) to maximum clockwise. Turn CHOPPER COMPENSATION ADJUST to maximum clockwise.

c. Adjust R34, CHOPPER COMPENSATION ADJUST for minimum pulse amplitude. The total adjustment range of R34 should provide a positive and negative pulse swing. If this is not satisfied, cut the jumper across R33 and again adjust R34. When correctly adjusted, R34 will reduce the positive spike at the transition point to zero.

d. Alternately adjust R43 counter-clockwise and R34 as necessary to obtain maximum squareness of the chopper waveform without a spike at the transition point. When correctly adjusted, waveform should appear as shown in Figure 4-5.



Figure 4-5. CHOPPER WAVEFORM

e. Replace the chopper board in the instrument.

4-66. To check amplifier response:

a. Connect the oscilloscope with a 10X isolation probe between Pins 14 (common) and 15 (input) of the Series Pass P/C Assembly. Set the oscilloscope sweep speed to 1 milliseconds/cm and vertical sensitivity to 1 volt/cm.

b. Set the POWER switch to STDBY/RESET. Positive going pulses of 1.0 to 2.0 volts peak-to-peak should be observed.

c. Set POWER switch to OPR position. The pulses observed in step b. should disappear.

d. Set the output of a laboratory power supply to 5.5V dc.

e. With 332D POWER switch in OPR position, connect the lab supply to the corresponding OUTPUT terminals of the 332D.

f. Set 332D controls as follows and observe unijunction pulses:

Range	Dialed Voltage	Unijunction Pulses
10V	5.000000	Should appear
10V	6.000000	Should disappear
100V	05.00000	Should appear
100V	06.00000	Should disappear
1000V	005.0000	Should appear
1000V	006.0000	Should disappear

4-67. Pre-Regulator

4-68. This check verifies operation of the Pre-Regulator circuitry Q1 through Q8. An oscilloscope and power line isolation adapter are required for this test.

a. Set the POWER switch to OFF. Install the pre-Regulator P/C Assembly.

b. Set the instrument front panel controls as follows:

POWER	OFF
RANGE	1000
VOLTAGE TRIP	1000
VERNIER	Maximum Clockwise
CURRENT LIMIT	Maximum Clockwise

c. Connect the oscilloscope power plug to the ac line via a line isolator (two-to-three wire adapter). The oscilloscope must be operated ungrounded when observing pre-regulator waveforms.

d. Connect the oscilloscope common to the emitter of Q1 and connect the input to the base (Q1 is the stud-mounted power transistor). Set the vertical input to DC, sweep speed to 1 millisecond/cm and the vertical sensitivity to 0.5 volt/cm.

e. Set the readout dials to 50.0000 and the POWER switch to STDBY/RESET. The oscilloscope waveform should appear as shown in Figure 4-6.

f. Set the POWER switch to OPR. The oscilloscope waveform should appear as shown in Figure 4-7.

g. Set POWER switch to STDBY/RESET and remove oscilloscope connections. Short out the interlocks using nylon blocks. Set POWER switch to OPR. Voltmeter of 332D should indicate 50±10 volts.

h. Set RANGE switch to 10 volt range. Voltmeter should indicate 5 ±1 volt.

i. Set RANGE switch to 1000 volt range. Voltmeter should indicate 500 ±100 volts. Set POWER switch to OFF.



Figure 4-6. PRE-REGULATOR Q1, WAVEFORM ON STDBY/RESET



Figure 4-7. PRE-REGULATOR Q1, WAVEFORM ON OPR

j. Connect the oscilloscope across the 50 watt zener diode on the pre-regulator assembly. Connect oscilloscope "positive" input to cathode; connect "negative" input to the anode; use a 10X probe. Connect output to load box.

k. Set decades for 1100 volt output and set CURRENT LIMIT to 60 mA. Set POWER switch to OPR and apply full load, 60 mA.

l. Set oscilloscope sensitivity to 50V/cm and sweep speed to 2 ms/cm.

m. Set line voltage to 115V ac, 60 Hz. The waveform observed on the oscilloscope should appear as in Figure 4-8A and should not exceed 150 volts peak.

n. Set line voltage to 100V ac, 60 Hz. The waveform observed on the oscilloscope should appear as in Figure 4-8B and should not exceed 150 volts peak.

o. Set line voltage to 130V ac, 60 Hz. The waveform observed on the oscilloscope should appear as in Figure 4-8C and should not exceed 150 volts peak.

p. Remove oscilloscope connections.

4-69. Series Pass Element

4-70. If the procedure has been completed satisfactorily thus far, the main parts of the voltage control circuitry have been checked out excluding the Series Pass P/C Assembly. A differential voltmeter and a load resistor box are required for this test.

a. Set the line voltage to 100V ac and set readout dials to all zeros on 10 volt range. Connect a voltmeter between the collector of Q1 and the emitter of Q8 on the Pass Element Assembly. This voltage should read less than 2V dc.

b. Set the line voltage and 332D controls as in Table 4-16 and measure the voltage between the collector and emitter of Q8. The voltages should be within the specified limits.

c. Connect the voltmeter across the OUTPUT terminals of the 332D. Set the 332D for the following outputs on the 1000 volt range and short the OUTPUT terminals at each setting. The output should return to normal upon removal of the short.

OUTPUTS: 100, 300, 600, 900, 1100 volts.



Figure 4-8. WAVEFORMS ACROSS ZENER DIODE

Range	Output	Load	Line Voltage	Voltage Limits Across Q8	
				Min.	Max.
10	0	0	100	45	100
10	0	0	130	45	90
1000	1100	60 mA	100	42	55
1000	1100	60 mA	130	42	55

Table 4-16. SERIES PASS ELEMENT VOLTAGE CHECKS

Section 5
Lists of Replaceable Parts

TABLE OF CONTENTS

REFERENCE DESIGNATOR	ASSEMBLY NAME/NUMBER	PART NO.	PAGE
	DC Voltage Standard Final Assembly (6160B)	6160B	5-3
A1	Capacitor P/C Assembly (332B-4055)	239343	5-10
A2	Sample String P/C Assembly (332B/AF-4051)	314849	5-11
A3	Capacitor/Switch P/C Assembly (335A-4092)	227603	5-14
A4	Range Calibration P/C Assembly (332B/AF-4052)	314856	5-15
A5	Mother Board P/C Assembly (335A-4064)	219238	5-17
A5A1	Reference Supply P/C Assembly (332B/AC-4083)	314864	5-19
A5A2	Series Pass Driver P/C Assembly (335A-4056)	219154	5-21
A5A3	Differential Amplifier P/C Assembly (335A-4057)	219162	5-23
A5A4	Chopper Amplifier Assembly (333A-4004)	251918	5-26
A5A5	Auxiliary Power Supply P/C Assembly (335A-4059)	219188	5-29
A5A6	Current Limiter P/C Assembly (335A-4060)	219196	5-33
A6	Time Delay P/C Assembly (332A-420)	192260	5-35
A7	High Voltage Mother Board P/C Assembly (332B-4056)	239350	5-37
A7A1	Series Pass Element P/C Assembly (332B-4061)	314823	5-39
A7A2	Preregulator P/C Assembly (332B-4082)	314815	5-41

5-1. INTRODUCTION

5-2. This section contains an illustrated parts breakdown of the instrument. Components are listed alpha-numerically by assembly. Electrical components are listed by reference designation and mechanical components are listed by item number. Each listed part is shown in an accompanying illustration.

5-3. Parts lists include the following information:

a. Reference Designation or Item Number.

b. Description of each part

c. Fluke Stock Number.

d. Federal Supply Code for Manufacturers. (See Appendix A for Code-to-Name list.)

e. Manufacturer's part Number or Type.

f. Total Quantity per assembly or component.

g. Recommended Quantity: This entry indicates the recommended number of spare parts necessary to support one to five instruments for a period of two years. This list presumes an availability of common electronic parts at the maintenance site. For maintenance for one year or more at an isolated site, it is recommended that at least one in each assembly in the instrument be stocked. In the case of optional subassemblies, plug-ins, etc. that are not always part of the instrument, or are deviations from the basic instrument mode, the REC QTY column lists the recommended quantity of the item in that particular assembly.

h. Use Code is provided to identify certain parts that have been added, deleted or modified during production of the instrument. Each part for which a use code has been assigned may be identified with a particular instrument serial number by consulting the Use Code Effectivity, paragraph 5-7.

5-4. HOW TO OBTAIN PARTS

5-5. Components may be ordered directly from the manufacturer by using the manufacturer's part number, or from the John Fluke Mfg. Co., Inc. factory or authorized representative by using the FLUKE STOCK NUMBER. In the event the part you order has been replaced by a new or improved part, the replacement will be accompanied by an explanatory note and installation instructions, if necessary.

5-6. To ensure prompt and efficient handling of your order, include the following information.

a. Quantity

b. FLUKE Stock Number

c. Description

d. Reference Designation or Item Number

e. Printed Circuit Board Part Number

f. Instrument model and Serial number

5-7. USE CODE EFFECTIVITY LIST

USE CODE	SERIAL NUMBER EFFECTIVITY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
	DC VOLTAGE STANDARD **Figure 5-1**	332D					
A1	Capacitor P/C Assembly (See Figure 5-2)	239343 (332B-4055)	89536	239343	1		
A2	Sample String P/C Assembly (See Figure 5-3)	314849 (332B/AF-4051)	89536	314849	1 1		
A3	Capacitor Switch P/C Assembly (See Figure 5-4)	227603 (335A-4092)	89536	227603	1		
A4	Range Calibration P/C Assembly (See Figure 5-5)	314856 (332B/AF-4052)	89536	314856	1		
A5	Main Mother Board P/C Assembly (See Figure 5-6)	219238 (335A-4064)	89536	219238	1		
A5A1	Reference Supply P/C Assembly (See Figure 5-7)	314864 (332B/AF-4083)	89536	314864	1		
A5A2	Series Pass Driver P/C Assembly (See Figure 5-8)	219154 (335A-4056)	89536	219154	1		
A5A3	Differential Amplifier P/C Assembly (See Figure 5-9)	219162 (335A-4057)	89536	219162	1		
A5A4	Chopper Amplifier P/C Assembly (See Figure 5-10)	251918 (333A-4004)	89536	251918	1		
A5A5	Auxiliary Power Supply P/C Assembly (See Figure 5-11)	219188 (335A-4059)	89536	219188	1		
A5A6	Current Limiter P/C Assembly (See Figure 5-12)	219196 (335A-4060)	89536	219196	1		
A6	Time Delay P/C Assembly (See Figure 5-13)	192260 (332A-420)	89536	192260	1		
A7	High Voltage Mother Board P/C Assembly (See Figure 5-14)	239350 (332B-4056)	89536	239350	1		
A7A1	Series Pass Element P/C Assembly (See Figure 5-15)	314823 (332B/AF-4061)	89536	314823	1		
A7A2	Preregulator P/C Assembly (See Figure 5-16)	314815 (332B/AF-4082)	89536	314815	1		
A8	Extender P/C Board	187344 (332A-415)	89536	187344	1		
C1	Cap, oil, 4 uf ±10%, 1,200V	183541	01884	CMLE405K12	1		
C2	Cap, cer, 0.01 uf, gmv, 1,600V (located on C1)	106930	71590	DD16-103	2		



Figure 5-1. DC VOLTAGE STANDARD (Sheet 1 of 3)



Figure 5-1. DC VOLTAGE STANDARD (Sheet 2 of 3)





Figure 5-1. DC VOLTAGE STANDARD (Sheet 3 of 3)

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
C3	Cap, cer, 0.005 uf ±20%, 3,000V	188003	71590	DD30-502	1		
C4,C5	Cap, plstc, 0.1 uf ±10%, 1,500V	234260	96733	C-60232A	2		
C6, C7	Cap, poly, .10 uf ±10%, 400V	289744	73445	C280CFA100K	2		
CR1	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	51	5	
CR2, CR3	Diode, silicon, 1 amp, 600 piv	112383	05277	1N4822	48	5	
CR4 thru CR8	Diode, light-emitting	309617	71318	FLV102	5		
F1	Fuse, Type MDL, slow blow, 1/4 amp, 250V	166306	71400	Type MDL	1	5	
F2	Fuse, Type MDA, slow blow, 3 amp, 250V (For 115V operation)	109280	71400	Type MDA	1	5	
F2	Fuse, Type MDX, slow blow, 1-1/2 amp, 250V (For 230V operation)	109231	71400	Type MDX	1	5	
J1	Binding post, red, OUTPUT	149856	58474	BHB10208G22	2		
J2	Binding post, black, OUTPUT	149864	58474	BHB10208G21	2		
J3	Binding post, red, SENSE	149856	58474	BHB10208G22	REF		
J4	Binding post, black, SENSE	149864	58474	BHB10208G21	REF		
J5	Binding post, GROUND	155911	58474	GP30NC	1		
J6	Binding post, blue, GUARD	233833	58474	DF31BLC	1		
K1	Relay, armature, 115 vac, dpdt	148940	73949	060713-00	1		
M1	Meter, 0-100 ua, 325Ω	225490	89536	225490	1		
R1	Res, met flm, 100k ±1%, 1/2w (mounted on S3)	151316	75042	Type CEC-TO	2		
R2	Res, met flm, 1M ±1%, 1/2w (mounted on S3)	161075	75042	Type CEC-TO	1		
R3, R4	Res, car flm, 5M ±1%, 1w	107458	75042	Type C13	2		
R5	Res, var, ww, 5k ±10%, 5w (mounted on S3)	219758	71450	Type AW	1		
R6	Res, var, ww, 300Ω ±10%, 5w	219741	71450	Type AW	1		
R7	Res, comp, 1k ±10%, 1/2w	108563	01121	EB1021	4		
R8	Res, ww, 500Ω ±5%, 25w	183533	14193	Type MC250	1		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R9, R10	Res, ww, 100k ±1%, 10w	177121	14193	Type SP1127	2		
S1	Switch, POWER, STDBY/RESET wafer	187864	76854	Type HC	1		
	Switch, POWER, OPR wafer	187872	76854	248214HC	1		
S2	Switch, VOLTAGE RANGE, rotary	237305	89536	237205	1		
S3	Switch, VOLTAGE TRIP, rotary	240739	89536	240739	1		
S4	Switch, METER, rotary	187146	89536	187146	1		
S5, S6	Switch, interlock	187708	91929	V3L-78	2		
T1	Transformer, power	222315	89536	222315	1		
T2	Transformer, high voltage	222307	89536	222307	1		
W1	Line cord	102822	89536	102822	1		
XF1, XF2	Holder, fuse	160846	75915	342004	2		
1	Coupler, dial	130252	89536	130252	7		
2	Coupler, R5 to S3	193557	89536	193557	1		
3	Coupler, Digit Switches to detents	226779	89536	226779	7		
4	Coupler, Digit Switches, S1, S4, R6	104505	89536	104505	11		
5	Coupler, S3	246058	89536	246058	1		
6	Coupler, S1 shaft to S1 wafer	200592	89536	200592	1		
7	Cover (not illustrated)	228809	89536	228809	1		
8	Detent, S1	240895	89536	240895	1		
9	Detent, Digit Switches	240887	89536	240887	7		
10	Dial, 0-10	226993	89536	226993	1		
11	Dial, 0-X	226985	89536	226985	6		
12	Foot, rubber (not illustrated)	103309	77969	9102W	4		
13	Handle, chrome plated brass	101717	05704	807	2		
14	Knob, CURRENT LIMIT	190249	89536	190249	1		
15	Knob, DIGITS 1-7	158949	89536	158949	7		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
16	Knob, METER, POWER, VOLTAGE RANGE	158956	89536	158956	3		
17	Knob, VOLTAGE TRIP						
17a	Concentric	162347	89536	162347	1		
17b	vernier	241018	89536	241018	1		
17c	trim disc	236950	89536	236950	1		
18	Lens, decimal, clear	222596	89536	222596	3		
19	Lens, decimal, red	228056	89536	228056	2		
20	Link, shorting, copper	190728	24655	938LG	2		
21	Panel, front	228775	89536	228775	1		
22	Shaft, S3 (not illustrated)	227272	89536	227272	1		
23	Shaft, S3 to front panel	240879	89536	240879	1		
24	Shaft, S1	239392	89536	239392	1		
25	Shaft, Digit Switches, S1, S4, R6	226928	89536	226928	10		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A1	**CAPACITOR P/C ASSEMBLY** **Figure 5-2**	239343 (332B-4055)	89536	239343	REF		
C1, C2	Cap, plstc, 1 uf ±20%, 250V	190330	73445	C280AE/ PIM	2		
CR1, CR2	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		

Figure 5-2. CAPACITOR PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A2	**SAMPLE STRING P/C ASSEMBLY** **Figure 5-3**	314849 (332B/AF-4051)	89536	314849	REF		
R1, R2	Res, met flm, 34Ω ±1%, 1/8w	296699	91637	TYPE MFF1/8	2		
R3, R4	Res, met flm, 20Ω ±1%, 1/8w	236844	91637	TYPE MFF1/8	2		
R5, R6	Res, var, cer met 50Ω ±20%, 1/2w	267815	71450	190PC500B	2		
R7, R8, R9, R10, R11, R12	Res, var, cer met 20Ω ±20%, 1/2w	261180	71450	190PC200B	6		
R13 thru R24	Res, met flm, 10Ω ±1%, 1/8w	268789	91637	TYPE MFF1/8	12		
R25	Res, 997.5Ω, matched set	1	89536	1	1		
R26	Res, 1996.5Ω, matched set	1		1	1		
R27, R28	Res, 3.995k, matched set	1	89536	1	2		
R29 thru R35	Res, 19.985k, matched set	1	89536	1	7		
R36 thru R46	Res, 99.925k, matched set	1	89536	1	11		
R47	Res, var, cer met, 100Ω ±20%, 1/2w	267823	71450	190PC101B	1		
R48	Res, var, cer met, 200Ω ±20%, 1/2w	284711	71450	190PC201B	1		
R49, R50	Res, var, cer met, 500Ω ±20%, 1/2w	267849	71450	190PC501B	2		
R51	Res, met flm, 100Ω ±1%, 1/8w	168195	91637	TYPE MFF1/8	1		
R52	Res, met flm, 200Ω ±1%, 1/8w	245340	91637	TYPE MFF1/8	1		
R53, R54	Res, met flm, 348Ω ±1%, 1/8w	236778	91637	TYPE MFF1/8	2		
R55	Res, ww, 2Ω ±0.2%, 1/10w	131870	89536	131870	1		
R56	Res, ww, 1Ω ±2%, 1/10w	131888	89536	131888	1		
R57, R58	Res, ww, 4Ω ±.015%, 1/4w	313809	89536	313809	2		
R59	Res, ww, 10Ω ±9%, 1/2w	155879	89536	155879	1		
R60	Res, ww, 20Ω ±5%, 1/2w	155887	89536	155887	1		
R61, R62	Res, ww, 40Ω, 1/2w	158022	89536	158022	2		
R63	Res, ww, 100Ω ±0.15%, 1/2w	155846	89536	155846	1		
R64	Res, ww, 200Ω ±0.15%, 1w	131656	89536	131656	1		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R65, R66	Res, ww, 400Ω ±0.25%, 1/2w	131698	89536	131698	2		
S1 thru S6	Switch, rotary, sample string	313023	76854	249	6		
S7	Switch, assembly, seventh decade (R67 thru R76 included)	291021	89536	291021	1		



Figure 5-3. SAMPLE STRING PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A3	**CAPACITOR SWITCH P/C ASSEMBLY** **Figure 5-4**	227603 (335A-4092)	89536	227603	REF		
C1	Cap, elect, 400 uf +50/-10%, 25V	168153	73445	C437ARF400	1	1	
CR1	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
K1	Relay, reed, 1,000V Coil, reed relay, 24V	233916 186155	12617 71707	Type DRR-5 SP-24-P	1 4		
Q1	Tstr, silicon, NPN	203489	07910	CDQ10656	17	5	
R1, R6	Res, comp, 100Ω ±10%, 1/2w	108100	01121	EB1011	2		
R2	Res, comp, 15k ±10%, 1/2w	108530	01121	EB1531	2		
R3	Res, comp, 470Ω ±10%, 1/2w	108415	01121	EB4711	2		
R4	Res, comp, 10k ±10%, 1/2w	108118	01121	EB1031	4		
R5	Res, comp, 1k ±10%, 1/2w	108563	01121	EB1021	REF		
R7	Res, comp, 39k ±5%, 1w	236729	01121	GB3935	1		



Figure 5-4. CAPACITOR SWITCH PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A4	**RANGE CALIBRATION P/C ASSEMBLY** Figure 5-5	314856 (332B/AF-4052)	89536	314856	REF		
R1	Res, var, cer met, 20Ω ±20%, 1/2w	261180	71450	190PC200B	1		
R2, R3	Res, ww, 7.492k, matched set	1	89536	1	2		
R4	Res, met flm, 20Ω ±1%, 1/2w	296350	91637	TYPE MFF1/8	1		
R5	Res, var, cer met 200Ω ±20%, 1/2w	284711	71450	190PC201B	1		
R6, R7	Res, ww, 74.925k, matched set	1	89536	1	2		
R8	Res, met flm, 200Ω ±1%, 1/2w	151480	91637	TYPE MFF1/8	1		
R9	Res, var, cer met, 2k ±20%, 1/2w	267864	71450	190PC202B	1		
R10, R11	Res, ww, 749.25k, matched set	1	89536	1	2		
R12	Res, met flm, 2k ±1%, 1/2w	151266	91637	TYPE MFF1/2	1		
T1	Test point, red	170480	74970	105-752	1		
T2	Test point, black	149112	74970	105-0753	1		

1 Factory matched for resistance accuracy and temperature coefficient. When ordering, include all information stamped on the resistor (if not legible include information on adjacent resistors) in addition to the information requested in paragraph regarding obtaining parts.



Figure 5-5. RANGE CALIBRATION PRINTED CIRCUIT ASSEMBLY



Figure 5-6. MAIN MOTHER BOARD PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5	**MAIN MOTHER BOARD P/C ASSEMBLY - Figure 5-6**	219238 (335A-4064)	89536	219238	REF		
C1	Cap, plstc, 0.1 uf ±20%, 200V	106435	56289	192P10402	3		
DS1, DS2	Lamp, neon	185017	74276	NE-7	2	5	
R1	Res, met flm, 23.7k ±1%, 1/2w	169383	75042	Type CEC-TO	2		
R2	Res, met flm, 25.5k ±1%, 1/2w	219006	75042	Type CEC-TO	1		
R3	Res, met flm, 267k ±1%, 1/2w	218990	75042	Type CEC-TO	1		
R4	Res, met flm, 274k ±1%, 1/2w	218982	75042	Type CEC-TO	1		
R5thru R7	Res, car flm, 1.82M ±1%, 1/2w	219089	75042	Type C12	3		
R8	Res, comp, 1k ±10%, 1w	109371	01121	GB1021	1		
R9	Res, comp, 470Ω ±10%, 1w	109710	01121	GB4711	1		
J1 thru J6	Connector, female, 16 contact	187732	91662	00-5009-016-153-001	8		



Figure 5-7. REFERENCE SUPPLY PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5A1	**REFERENCE SUPPLY P/C ASSEMBLY Figure 5-7**	314864 (332B/AF-4083)	89536	314864	REF		
A1	IC, Operational amplifier	313106	MOTO-ROLA	MC1723CG	1		
A2	IC, Operational amplifier	271502	12040	LM301A	1		
A3	Ref amp with oven	248914	01295	4ST1-2	1		
C1	Cap, mica, 510 pf ±5%, 500V	148411	14655	CD19F511J	1		
C2	Cap, mica, 27 pf ±5%, 500V	177998	14655	CD15F221J	1		
C3	Cap, plstc, 0.1 uf ±10%, 50V	271866	06001	75F2R5A104	1		
Q1	Tstr, Si, NPN	203489	07910	CDQ10656	1		
R2, R4, R6	Res, var, cer met, 10k ±20%, 1/2w	267880	71450	190PC103B	3		
R7A, R7B, R13	Res, ref amp, matched set (R7A is always 9k res)	314971	89536	314971	1		
R8, R10	Res, ww, 50Ω ±.06%, 1/2w	238493	89536	238493	2		
R9	Res, var, cer met 50Ω ±20%, 1/2w	267815	71450	190PC500B	1		
R11	Not used						
R12	Res, met flm, 2.94k ±1%, 1/2w	247528	91637	TYPE MFF1/2	1		
R14	Res, met flm, 6.34k ±1%, 1/2w	218636	91637	TYPE MFF1/2	1		
R15	Res, met flm, 8.66k ±1%, 1/2w	247957	91637	TYPE MFF1/2	1		
R16	Res, met flm, 16.9k ±1%, 1/2w	198275	91637	TYPE MFF1/2	1		
R17	Res, met flm, 7.15k ±1%, ½w	186072	91637	TYPE MFF 1/2	1		
R18	Res, met flm, 4.99k ±1%, 1/2w	148890	74970	105-0753	1		
R19	Res, comp, 33Ω ±5%, 2w	161497	01121	HB3305	1		
R20	Res, comp, 1.5Ω ±5%, 1/2w	246793	01121	EB15G5	1		



Figure 5-8. SERIES PASS DRIVER PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5A2	**SERIES PASS DRIVER P/C ASSEMBLY - Figure 5-8**	219154 (335A-4056)	89536	219154	REF		
C1	Cap, plstc, 0.47 uf ±20%, 250V	184366	73445	C280AE/P470	1		
C2	Cap, Ta, 2.2 uf ±10%, 20V	160226	05397	K2R2C20K	1		
C3	Cap, plstc, 0.1 uf ±20%, 200V	106435	56289	192P10402	REF		
C4	Cap, plstc, 0.22 uf ±10%, 80V	159392	56289	192P2249R8	1		
C5	Cap, Ta, 15 uf ±10%, 20V	153056	05397	K15C20K	2		
CR1, CR2, CR4, CR6 thru CR9, CR13, CR15	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
CR3, CR5	Diode, zener, 10v	113324	07910	1N961A	2	1	
CR10, CR11, CR12	Diode, silicon, 150 ma, 6 piv	113308	07910	CD13161	3		
CR14	Diode, zener, 4.3V	180455	07910	1N749A	1	1	
P1	Connector, male, 16 contact	187724	91662	02-016-013-5-200	REF		
Q1, Q4 Q6, Q8	Tstr, tested, silicon, PNP	159491	89536	159491	11	2	
Q2, Q5, Q7	Tstr, silicon, NPN	203489	07910	CDQ10656	REF		
Q3	Tstr, silicon, NPN	183004	95303	40250	1		
R1, R4	Res, met flm, 4.02k ±1%, 1/2w	167478	75042	Type CEC-TO	2		
R2	Res, var, ww, 2k ±10%, 1-1/4w	198416	71450	Type 110	1		
R3	Res, comp, 2.7k ±10%, 1w	109496	01121	GB2721	1		
R5, R13	Res, var, ww, 3k ±20%, 1-1/4w	149781	71450	Type 110	2		
R6	Res, met flm, 5.62k ±1%, 1/2w	219014	75042	Type CEC-TO	1		
R7	Res, comp, 100k ±10%, 1/2w	108126	01121	EB1041	3		
R9	Res, comp, 2.4k ±5%, 1/2w	108902	01121	EB2425	1		
R10, R11	Res, comp, 47Ω ±10%, 2w	144352	01121	HB4701	2		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R12	Res, comp, 36k ±5%, 1/2w	185991	01121	EB3635	4		
R14	Res, met flm, 1k ±1%, 1/2w	151324	75042	Type CEC-TO	1		
R15	Res, met flm, 221k ±1%, 1/2w	182527	75042	Type CEC-TO	3		
R16	Res, comp, 3.9k ±10%, 1/2w	161406	01121	EB3921	1		
R17	Res, comp, 20k ±5%, 1/2w	109041	01121	EB2035	3		
R18	Res, comp, 16k ±5%, 1/2w	159632	01121	EB1635	3		
R19	Res, comp, 10k ±10%, 1/2w	108118	01121	EB1031	REF		
R20	Res, comp, 27k ±5%, 1/2w	186023	01121	EB2735	1		
R21	Res, comp, 220Ω ±5%, 1/2w	186031	01121	EB2215	1		
R22	Res, met flm, 10Ω ±1%, 1/2w	151043	75042	Type CEC-TO	1		
R23, R25	Res, comp, 47k ±5%, 1/2w	108738	01121	EB4735	2		
R24	Res, comp, 620Ω ±5%, 1/2w	108704	01121	EB6215	2		
R26	Res, comp, 180Ω ±10%, 2w	155457	01121	HB1811	1		
R27	Res, comp, 2k ±5%, 1/2w	169854	01121	EB2025	2		
R28	Res, comp, 8.2k ±5%, 1/2w	147777	01121	EB8225	2		
	Heat sink	186759	89536	186759	1		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5A3	**DIFFERENTIAL AMPLIFIER P/C ASSEMBLY - Figure 5-9**	219162 (335A-4057)	89536	219162	REF		
C1	Cap, plstc, 0.1 uf ±10%, 50V	150318	56289	194P1049R5	1		
C2	Cap, mica, 510 pf ±5%, 500V	148411	88419	CD19F511J	2		
C3	Cap, Ta, 15 uf ±10%, 20V	153056	05397	K15C20K	REF		
C4	Cap, elect, 250 uf +50/-10%, 40V	178616	73445	C437ARG250	1	1	
C5	Cap, mica, 27 pf ±5%, 500V	177998	88419	CD15E270J	1		
CR1 thru CR 13	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
CR14	Diode, zener, 10V	113324	07910	1N961A	REF		
CR15	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
P1	Connector, male, 16 contact	187724	91662	02-016-013-5-200	REF		
Q1	Tstr, silicon, NPN	177105	07263	2N3565	5		
Q2	Tstr, FET, silicon N-channel	166223	15818	U-1249	2		
Q3	Tstr, silicon, PNP	190389	04713	SM4144	REF		
Q4	Tstr, tested, silicon, NPN	198812	89536	4805-198812	2	1	
Q5, Q7	Tstr, silicon, PNP	190389	04713	SM4144	2		
Q6	Tstr, tested, silicon, NPN	198812	89536	198812	1		
Q8	Tstr, silicon, NPN	203489	07910	CDQ10656	REF		
Q9, Q10 Q11, Q12	Tstr, silicon, PNP	183558	04713	2N3250	3	1	
R1	Res, comp, 22k ±5%, 1/2w	186064	01121	EB2235	3		
R2, R3 R5, R6	Res, comp, 100Ω ±5%, 1/2w	188508	01121	EB1015	6		
R4	Res, ww, 10k ±0.2%, 1/4w	112177	89536	112177	1		
R7, R30	Res, comp, 1k ±5%, 1/2w	108597	01121	EB1025	10		
R8	Res, comp, 3.3k ±5%, 1/2w	165761	01121	EB3325	4		
R9	Res, comp, 3k ±5%, 1/2w	109090	01121	EB3025	2		



Figure 5-9. DIFFERENTIAL AMPLIFIER PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R10	Res, comp, 510Ω ±5%, 1/2w	108951	01121	EB5115	1		
R11	Res, comp, 22M ±10%, 1/2w	108233	01121	EB2261	1		
R12	Res, comp, 6.2k ±5%, 1/2w	108621	01121	EB6225	3		
R13	Res, comp, 2.2k ±5%, 1/2w	108506	01121	EB2225	2		
R14	Res, comp, 1.2k ±10%, 1/2w	108803	01121	EB1221	1		
R15	Res, met flm, 100k ±1%, 1/2w	151316	75042	Type CEC-TO	REF		
R16, R20	Res, met flm, 221k ±1%, 1/2w	182527	75042	Type CEC-TO	REF		
R17, R21	Res, met flm, 40.2k ±1%, 1/2w	161059	75042	Type CEC-TO	2		
R18, R19	Res, met flm, 75Ω ±1%, 1/2w	150870	75042	Type CEC-TO	2		
R22	Res, met flm, 6.04k ±1%, 1/2w	162586	75042	Type CEC-TO	REF		
R23	Res, met flm, 42.2k ±1%, 1/2w	182501	75042	Type CEC-TO	1		
R24	Res, met flm, 9.09k ±1%, 1/2w	151258	75042	Type CEC-TO	1		
R25	Res, met flm, 15k ±1%, 1/2w	151498	75042	Type CEC-TO	1		
R26 R27	Res, met flm, 1.58k ±1%, 1/2w	182543	75042	Type CEC-TO	2		
R28	Res, met flm, 9.76k ±1%, 1/2w	182485	75042	Type CEC-TO	3		
R29	Res, comp, 10k ±5%, 1/2w	109165	01121	EB1035	2		
R31	Res, comp, 2k ±5%, 1/2w	169854	01121	EB2025	REF		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5A4	**CHOPPER AMPLIFIER ASSEMBLY** **Figure 5-10**	251918 (333A-4004)	89536	251918			
C1	Cap, plstc, 0.1 uf ±10%, 250V	161992	73445	C280AE/A100K	1		
C2, C3	Cap, plstc, 0.0068 uf ±20%, 200V	106070	56289	192P68202	2		
C4	Cap, plstc, 0.047 uf ±10%, 250V	162008	73445	C280AE/A47K	1		
C5	Cap, mica, 4 pf ±5%, 500V	190397	14655	CD15C040K	1		
C6	Cap, mica, 640 pf ±5%, 500V	215251	14655	CD19F6405	1		
C7, C13	Cap, elect, 5 uf +75/−10%, 25V	152009	56289	30D505G025 BA4	2		
C8, C21	Cap, elect, 50 uf +50/−10%, 25V	168823	73445	C426ARF50	2		
C9, C23	Cap, elect, 100 uf +75/−10%, 3V	106534	56289	30D107G003 CB4	2		
C10	Cap, mica, 220 pf ±5%, 500V	170423	14655	CD15F221J	1		
C11	Cap, cer, 100 pf ±10%, 1 kV	105593	71590	DD-101	1		
C12	Cap, mica, 5 pf ±10%, 500V	148577	14655	CD15C050K	1		
C14, C16	Cap, Ta, 33 uf ±10%, 10V	182832	56289	150D336X90 10B2	2		
C15, C17	Cap, elect, 15 uf +75/−10%, 6V	105700	56289	30D156G006 BA4	2		
C18	Cap, Ta, 100 uf ±10%, 10V	170456	05397	K100C10K	1		
C19, C20	Cap, plstc, 0.015 uf ±2%, 100V	233577	02799	1PC-153-G	2		
C22	Cap, Ta, 0.47 uf ±20%, 35V	161349	56289	196D474X00 35	1		
CR1	Diode, zener, silicon	266601	07910	1N965B	1		
CR2 thru CR9	Diode, silicon, 150 mA	203323	03508	DHD1105	8		
IC1	IC, operational amplifier	246603	07263	U5B770939X	1		
Q1	Tstr, MOS FET, P-channel	226043	07263	FT704	1		
Q2	Tstr, FET, N-channel	271924	07910	CFE13041	1		
Q3	Tstr, silicon, PNP	195974	04713	2N3906	1		
Q4	Tstr, silicon, PNP	288761	49956	RS2048	1		
Q5 thru Q7	Tstr, silicon, NPN	218396	04713	2N3904	3		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R1	Res, comp, 51k ±5%, 1/4w	193334	01121	CB5135	1		
R2, R21, R22	Res, comp, 100k ±5%, 1/4w	148189	01121	CB1045	3		
R3	Res, met flm, 604k ±1%, 1/2w	182493	91637	TYPE MFF1/2	1		
R4	Res, comp, 10Ω ±5%, 1/4w	147868	01121	CB1005	1		
R5	Res, met flm, 604k ±1%, 1/2w	182493	91637	TYPE MFF1/2	1		
R6	Res, comp, 3.3M ±5%, 1/4w	208389	01121	CB3355	1		
R7	Res, comp, 13k ±5%, 1/4w	221598	01121	CB1335	1		
R8, R41, R42	Res, comp, 200Ω ±5%, 1/4w	193482	01121	CB2015	3		
R9, R32, R37, R39 R40	Res, comp, 22k ±5%, 1/4w	148130	01121	CB2235	5		
R10, R12	Res, met flm, 34k ±1%, 1/2w	151241	91637	TYPE MFF1/2	2		
R11	Res, comp, 10M ±5%, 1/4w	194944	01121	CB1065	1		
R13	Res, comp, 1.5k ±5%, 1/4w	148031	01121	CB1525	1		
R14	Res, met flm, 301 ±1%, 1/2w	167494	91637	TYPE MFF1/2	1		
R15	Res, met flm, 8.06k ±1%, 1/2w	159467	91637	TYPE MFF1/2	1		
R16	Res, met flm, 68.1k ±1%, 1/2w	161083	91637	TYPE MFF1/2	1		
R17	Res, comp, 68k ±5%, 1/4w	148171	01121	CB6835	1		
R18	Res, comp, 24k ±5%, 1/4w	193425	01121	CB2435	1		
R19, R20	Res, met flm, 10k ±1%, 1/2w	151274	91637	TYPE MFF1/2	2		
R23	Res, comp, 33k ±5%, 1/4w	148155	01121	CB3335	1		
R24	Res, comp, 10k ±5%, 1/4w	148106	01121	CB1035	1		
R25	Res, comp, 36k ±5%, 1/4w	221929	01121	CB3635	1		
R26	Res, comp, 18k ±5%, 1/4w	148122	01121	CB1835	1		
R27	Res, comp, 560Ω ±5%, 1/4w	147991	01121	CB5615	1		
R28	Res, comp, 47k ±5%, 1/4w	148163	01121	CB4735	1		
R29	Res, comp, 180k ±5%, 1/4w	193441	01121	CB1845	1		
R30	Res, comp, 8.2k ±5%, 1/4w	160796	01121	CB8225	1		
R31	Res, comp, 15k ±5%, 1/4w	148114	01121	CB1535	1		
R33	Res, met flm, 4.22k ±1%, 1/2w	223396	91637	TYPE MFF1/2	1		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R34	Res, var cer met, 5k ±20%, 3/4w	159905	73138	78PR5K	1		
R35	Res, met flm, 24.3k ±1%, 1/2w	217430	91637	TYPE MFF1/2	1		
R36, R38	Res, met flm, 187k ±1%, 1/8w	289462	91637	TYPE MFF1/2	2		
R43	Res, var, comp, 10k ±30%, 1/4w	223131	37942	TYPE MTC	1		
	Connector, male, 16 contact	187724	91662	02-106-013-5-200	1		
	Cover, chopper	251751	89536	251751	1		



Figure 5-10. CHOPPER AMPLIFIER PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5A5	**AUXILIARY POWER SUPPLY P/C ASSEMBLY - Figure 5-11**	219188 (335A-4059)	89536	219188	REF		
C1	Cap, Ta, 68 uf ±10%, 15V	182824	05397	K68C15K	1		
C2	Cap, elect, 250 uf +50/-10%, 64V	185850	73445	C437ARH250	4	1	
C3, C8	Cap, elect, 50 uf +75/-10%, 50V	105122	80183	TE1307	3	1	
C4	Cap, cer, 220 pf ±10%, 500V	105528	72982	315-024X5UD 221K	1		
C5, C10	Cap, plstc, 2 uf ±20%, 100V	106963	84411	Type X663FR	2		
C6	Cap, plstc, 0.1 uf ±20%, 200V	106435	56289	192P10402	REF		
C7, C11	Cap, elect, 20 uf +75/-10%, 50V	106229	80183	TE1305	REF		
C9	Cap, plstc, 0.0012 uf ±10%, 200V	106088	56289	192P12292	1		
CR1, CR2, CR3, CR4, CR7 thru CR10	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
CR5	Diode, zener, 3.9V	113316	07910	1N748	2	1	
CR6	Diode, zener, 6.3V	172148	03877	1N3496	1	1	
P1	Connector, male, 16 contact	187724	91662	02-016-013-5-200	REF		
Q1	Silicon controlled rectifier, 1.6 amp, 50V	192567	03508	C-6F	2	1	
Q2	Tstr, selected, silicon, PNP	159491	89536	159491	REF		
Q3, Q5, Q6, Q8, Q9	Tstr, silicon, NPN	203489	07910	CDQ10656	REF		
Q4, Q7	Tstr, silicon, NPN	183004	95303	40250	REF		
R1	Res, comp, 10k ±5%, 1/2w	109165	01121	EB1035	REF		
R2	Res, comp, 390Ω ±5%, 1/2w	109082	01121	EB3915	1		
R3	Res, comp, 5.6k ±5%, 1/2q	187880	01121	EB5625	1		
R4	Res, comp, 15Ω ±10%, 2w	155549	01121	HB1505	1		
R5	Res, comp, 15k ±10%, 1/2w	108530	01121	EB1531	REF		



Figure 5-11. AUXILIARY POWER SUPPLY PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R6	Res, comp, 3k ±5%, 1/2w	109090	01121	EB3025	REF		
R7	Res, comp, 33k ±10%, 1/2w	178541	01121	EB3331	REF		
R8	Res, met flm, 7.15k ±1%, 1/2w	186072	75042	Type CEC-TO	1		
R9	Res, var, ww, 1k ±20%, 1-1/4w	113266	71450	Type 110	1		
R10	Res, met flm, 2.55k ±1%, 1/2w	176362	75042	Type CEC-TO	1		
R11	Res, comp, 6.2k ±5%, 1/2w	108621	01121	EB6225	REF		
R12	Res, met flm, 2.37k ±1%, 1/2w	182519	75042	Type CEC-TO	1		
R13	Res, comp, 12k ±10%, 1/2w	108977	01121	EB1231	1		
R14	Res, comp, 82Ω ±10%, 2w	110239	01121	HB8201	1		
R15	Res, comp, 8.2k ±5%, 1/2w	147777	01121	EB8225	REF		
R16	Res, comp, 3.3k ±10%, 1/2w	108373	01121	EB3321	1		
R17	Res, comp, 4.7k ±10%, 1/2w	108381	01121	EB4721	2		
R18	Res, met flm, 8.45k ±1%, 1/2w	159475	75042	Type CEC-TO	1		
R19	Res, met flm, 4.99k ±1%, 1/2w	148890	75042	Type CEC-TO	1		
R20	Res, comp, 2.0k ±5%, 1/2w	169854	01121	EB2025	REF		



Figure 5-12. CURRENT LIMITER PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A5A6	**CURRENT LIMITER P/C ASSEMBLY - Figure 5-12**	219196 (335A-4060)	89536	219196	REF		
C1	Cap, elect, 350 uF +75/–10%, 75V	292862	73445	C437ARH250	3		
C2	Cap, elect, 20 uf +75/-10%, 50V	106229	80183	TE1305	REF		
C3	Cap, elect, 20 uf +75/-10%, 50V	106229	80183	TE1305	REF		
C4	Cap, elect, 350 uF +75/–10%, 75V	292862	73445	C437ARH250	REF		
C5	Cap, elect, 20 uf +75/-10%, 50V	106229	80183	TE1305	REF		
C6	Cap, elect, 350 uF +75/–10%, 75V	292862	73445	C437ARH250	REF		
C7	Cap, plstc, 0.047 uf ±20%, 100V	106096	72928	335B473M	1		
C9	Cap, elect, 2 uf +75/-10%, 50V	105197	80183	TE1301	1	1	
C10	Cap, elect, 160 uf +50/-10%, 64V	170274	73445	C437ARH160	1	1	
CR1, CR2, CR3, CR4, CR8	Diode, silicon, 1 amp, 600 piv	112382	05277	1N4822	REF		
CR5	Diode, zener, 36V	186163	07910	1N974B	2	1	
CR6	Diode, zener, 3.9V	113316	07910	1N748	REF		
CR7	Diode, zener, 36V	237354	04713	1N3033A	1	1	
CR9	Diode, zener, 12V	159780	07910	1N759	1	1	
CR10, CR11	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
CR12	Diode, silicon, 150 ma, 6 piv	113308	07910	CD13161	REF		
P1	Connector, male, 16 contact	187724	91662	02-016-013-5-200	REF		
Q1	Tstr, silicon, NPN	183004	95303	40250	REF		
Q2	Tstr, germanium, PNP	152868	95303	2N2869	1	1	
Q3	Tstr, selected, silicon, PNP	159491	89536	159491	REF		
Q4, Q7	Tstr, silicon, NPN	203489	07910	CDQ10656	REF		
Q5, Q6	Tstr, selected, silicon, PNP	159491	89536	159491	REF		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R1, R4	Res, comp, 10Ω ±10%, 2w	110163	01121	HB1001	4		
R2, R5	Res, comp, 3.3k ±5%, 1/2w	165761	01121	EB3325	REF		
R3, R26	Res, comp, 2.4k ±5%, 2w	218834	01121	HB2425	2		
R6, R19 R20	Res, comp, 7.5k ±5%, 1/2w	108910	01121	EB7525	3		
R7, R16	Res, comp, 100k ±10%, 1/2w	108126	01121	EB1041	REF		
R8, R9 R25	Res, comp, 120Ω ±10%, 2w	155531	01121	HB1211	3		
R10	Res, comp, 4.7k ±10%, 1/2w	108381	01121	EB4721	REF		
R11, R12	Res, comp, 10k ±10%, 1/2w	108118	01121	EB1031	REF		
R13	Res, comp, 16k ±5%, 1/2w	159632	01121	EB1635	REF		
R14, R21	Res, comp, 1k ±10%, 1/2w	108563	01121	EB1021	REF		
R15	Res, comp, 2.2k ±10%, 1/2w	108605	01121	EB2221	1		
R17	Res, comp, 36k ±5%, 1/2w	185991	01121	EB3635	REF		
R18	Res, comp, 330k ±5%, 1/2w	150201	01121	EB3345	1		
R22	Res, met flm, 12.1k ±1%, 1/2w	182535	75042	Type CEC-TO	1		
R23	Res, var, ww, 10k ±10%, 1-1/4w	162115	71450	Type 110	1		
R24	Res, var, ww, 150Ω ±10%, 1-1/4w	113092	71450	Type 110	1		
	Heat sink	186759	89536	186759	REF		
	Heat sink	186742	89536	186742	1		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A6	**TIME DELAY P/C ASSEMBLY** **Figure 5-13**	192260 (332A-420)	89536	192269	REF		
C2001	Cap, elect, 400 uf +50/-10%, 40V	185868	73445	C437ARG400	1		
CR2001 CR2002 CR2003	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
K2001	Relay, armature, 12 vdc, dpdt	176347	80089	62-760	1		
Q2001	Silicon controlled rectifier, 1.6 amp, 50V	192567	03508	C-6F	REF		
R2001	Res, comp, 2.2k ±10%, 2w	109967	01121	HB2221	2		
R2002	Res, comp, 5.6k ±10%, 1/2w	108324	01121	EB5621	1		
R2003	Res, comp, 390Ω ±10%, 1/2w	108365	01121	EB3911	1		
R2004	Res, comp, 10k ±10%, 1/2w	108118	01121	EB1031	REF		



Figure 5-13. TIME DELAY PRINTED CIRCUIT ASSEMBLY



Figure 5-14. HIGH VOLTAGE MOTHER BOARD PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A7	**HIGH VOLTAGE MOTHER BOARD P/C ASSEMBLY - Figure 5-14**	239350 (332B-4056)	89536	239250	REF		
A7A1	Series Pass Element P/C Assembly (See Figure 5-15)	314823 (332B-4064)	89536	314823	REF		
A7A2	Preregulator P/C Assembly (See Figure 5-16)	314815 (332B-4082)	89536	314815	REF		
C1, C2, C3	Cap, elect, 125 uf +50/-10%, 450V	106336	56289	Type 66D	3	1	
C4, C5	Cap, elect, 8 uf +50/-10%, 450V	194068	56289	39D805F-450HE4	2		
C6, C10	Cap, plstc, 1 uf ±20%, 200V	106450	84411	Type X663F	2		
C7	Cap, elect, 50 uf +75/-10%, 50V	105122	80183	TE1307	1		
C8	Cap, cer, 0.001 uf ±20%, 3 kv	105635	80183	29C300	1		
C9	Cap, cer, 0.01 uf, gmv, 1600V	106930	71590	DD16-103	REF		
CR1 thru CR19	Diode, silicon, 1 amp, 600 piv	112383	05277	1N4822	REF		
CR21, CR22	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
K1	Relay, reed, 5,000V	184440	12617	DRVT-1	2		
	Coil, reed relay, 24V	186155	71707	SP-24-P	REF		
K2	Relay, reed, 5,000V	184440	12617	DRVT-1	REF		
	Coil, reed relay, 24V	186155	71707	SP-24-P	REF		
R1, R2 R12, thru R14	Res, comp, 220k ±10%, 2w	110197	01121	HB2241	6		
R4, R5	Res, comp, 470k ±5%, 1w	809819	01121	GB4745	2		
R6, R9	Res, comp, 10Ω ±10%, 2w	110163	01121	HB1001	REF		
R7	Res, comp, 470Ω ±10%, 1/2w	108415	01121	EB4711	REF		
R8	Res, comp, 5.1Ω ±5%, 1w	219071	01121	GB51G5	1		
R10	Res, comp, 270Ω ±10%, 2w	110189	01121	HB2711	1		
R11	Res, comp, 2.2k ±10%, 2w	109967	01121	HB2221	REF		
R15	Res, ww, 2k ±5%, 10w	155416	06136	Type 10F	1		
T1	Transformer, pulse	185827	89536	185827	1		
J1, J2	Connector, female, 16 contact	285015	91662	00-5009-016 153-001	REF		



Figure 5-15. SERIES PASS ELEMENT PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A7A1	**SERIES PASS ELEMENT P/C ASSEMBLY - Figure 5-15**	314823 (332B-4061)	89536	14823	REF		
C1	Cap, cer, 0.05 uf +80/-10%, 500V	105676	56289	33C58B	4		
C2	Cap, elect, 8 uf +50/-10%, 450V	194068	56289	39D805F450-HE4	REF		
C3	Cap, mylar, .0022 uf ±10%, 50V	313239	06001	75F1R5A224	1		
C4	Cap, cer, 0.005 uf ±20%, 100V	175232	56289	C023B101E-802M	1		
C5	Cap, elect, 20 uf +50/-10%, 16V	241356	73445	C426ARE20	1		
CR1 thru CR5, CR7 thru CR17, CR31	Diode, silicon, 1 amp, 600 piv	112383	05277	1N4822	17		
CR6	Diode, zener, ±5%, 16V	313221	12969	UZ8716	1	1	
CR18	Diode, zener, 20V	113340	07910	1N968A	1	1	
CR19	Diode, zener, 36V	186163	07910	1N974B	REF		
CR20, CR21, CR32	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
CR22	Diode, zener, 6.2V	180497	07910	1N753	1	1	
CR23 thru CR30	Diode, zener, 200V	217422	04713	1N3051A	8	1	
P1	Connector, male, 16 contact	187724	91662	02-016-013 5-200	REF		
Q1 thru Q8	Tstr, silicon, NPN	190710	04713	2N3739	8	8	
Q9	Tstr, silicon, unijunction	117176	03508	2N1671A	1	1	
Q10	Tstr, silicon, NPN	203489	07910	CDQ10656	REF		
R1 thru R3	Res, comp, 1.8k ±10%, 2w	185983	01121	HB1821	3		
R4, R8	Res, comp, 62k ±5%, 1/2w	108522	01121	EB6235	2		

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R5	Res, comp, 100k ±10%, 2w	158659	01121	HB1041	1		
R6	Res, comp, 56k ±5%, 1/2w	219048	01121	EB5635	1		
R7, R9 R11	Res, comp, 1k ±5%, 1/2w	108597	01121	EB1025	REF		
R10	Res, comp, 68k ±5%, 1/2w	159624	01121	EB6835	1		
R12, R35	Res, comp, 75k ±5%, 1/2w	108928	01121	EB7535	REF		
R13, R15, R17, R19, R42	Res, comp, 1k ±5%, 1/2w	108597	01121	EB1025	REF		
R14	Res, comp, 82k ±5%, 1/2w	195966	01121	EB8235	1		
R16	Res, comp, 91k ±5%, 1/2w	219030	01121	EB9135	1		
R18, R21 thru R27, R40	Res, comp, 100k ±5%, 1/2	168054	01121	EB1045	9		
R20	Res, comp, 1.1Ω ±5%, 1/2w	163717	01121	EB11G5	1		
R28, R29 thru R34	Res, comp, 22k ±10%, 2w	109975	01121	HB2231	7		
R36, R43	Res, comp, 5.1k ±5%, 1/4w	193342	01121	CB5125	REF		
R37	Res, comp, 36k ±5%, 1/2w	185991	01121	EB3635	REF		
R38	Res, comp, 180Ω ±5%, 1/2w	108944	01121	EB1815	1		
R39	Res, comp, 1.1k ±5%, 1/4w	267336	01121	CB1125	1		
R41	Res, comp, 5.1k ±5%, 1/4w	193342	01121	CB5125	2		
	Heat sink	192245	89536	192245	1		
L1, L2	Inductance, 2.2 MH	147801	72259	WEE-2,200	2		
L3	Inductance, 220 uh	147835	72259	WEE-220	1		
Q11	Tstr, silicon NPN	218396	04713	2N3904			
Q12	Tstr, silicon NPN	177105	07263	2N3565			

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
A7A2	**PREREGULATOR P/C ASSEMBLY** Figure 5-16	314815 (332B-4082)	89536	314815	REF		
C1, C2 C6, C8	Cap, cer, 0.05 uf +80/-10%, 500V	105676	56289	33C58B	REF		
C3, C4	Cap, elect, 250 uf +50/-10%, 16V	187765	73445	C437ARE250			
C5	Cap, mylar, 1.0 uf ±20%, 200V	106450	72928	364	1		
C7	Cap, mylar, .001 uf ±10%, 200V	159582	56289	192P10292	1		
CR1 thru CR5, CR15 thru CR17	Diode, silicon, 1 amp, 100 piv	116111	05277	1N4817	REF		
CR6 thru CR9	Diode, silicon, 1 amp, 600 piv	112383	05277	1N4822	REF		
CR10 thru CR13	Diode, silicon, 3 amp, 200 piv	187716	04713	MR1032B	4		
CR14	Diode, zener, 200V	187617	04713	1N3350RA	1	1	
K1	Relay, armature, 115 vac, dpdt	106864	16332	100-5ADPDT	1		
K2	Relay, reed, 500V	136630	12617	Type DRG-1	1		
	Coil, reed relay, 24V	186155	71707	SP-24-P	REF		
P1	Connector, male, 16 contact	187724	91662	02-016-013-5-200	REF		
Q1	Tstr, silicon, NPN	193953	05277	320C034H31	1	1	
Q2	Tstr, silicon, NPN	261347	16758	Type DTS410	1		
Q3	Tstr, tested, silicon, NPN	203489	07910	CDQ10656	REF		
Q4, Q6	Tstr, tested, silicon, PNP	159491	89536	4805-159491	REF		
Q5, Q7	Tstr, silicon, NPN	203489	07910	CDQ10656	REF		
Q8, Q9	Tstr, silicon, PNP	159491	89536	159491	REF		
R1	Res, comp, 68Ω ±10%, 2w	110205	01121	HB6801	1		
R2	Res, ww, 0.192Ω ±1%, 3w	238741	89536	238741	1	1	
R4	Res, ww, 1k ±5%, 5w	113282	63743	Type 5F1000	1		



Figure 5-16. PREREGULATOR PRINTED CIRCUIT ASSEMBLY

REF DESIG	DESCRIPTION	STOCK NO	MFR	MFR PART NO	TOT QTY	REC QTY	USE CODE
R5	Res, comp, 22k ±5%, 1/2w	186064	01121	EB2235	REF		
R6	Res, ww, 1Ω ±10%, 5w	112425	44655	1K48F	1		
R7	Res, comp, 220Ω ±10%, 1/2w	108191	01121	EB2211	1		
R8	Res, comp, 430Ω ±5%, 1/2w	109058	01121	EB4315	1		
R9	Res, comp, 100Ω ±5%, 1/2w	188508	01121	EB1015	REF		
R10	Res, comp, 2.2k ±5%, 1/2w	108506	01121	EB2035	REF		
R11	Res, comp, 100Ω ±5%, 1/2w	188508	01121	EB1015	REF		
R12	Res, comp, 1k ±5%, 1/2w	108597	01121	EB1025	REF		
R13, R14, R17	Res, comp, 1k ±5%, 1/2w	108597	01121	EB1025	3		
R15	Res, comp, 4.7k ±5%, 1/2w	108886	01121	EB4725	1		
R16	Res, comp, 3.3k ±5%, 1/2w	165761	01121	EB3325	REF		
R18	Res, comp, 560Ω ±5%, 1/2w	109124	01121	EB5615	1		
R19	Res, comp, 68Ω ±5%, 1/2w	178384	01121	EB6805	1		
	Heat sink	314807	89536	314807	1		

Section 6

Option & Accessory Information

There are no options or accessories available for use with the Model 332D DC Voltage Standard, other than the rack mounting kits described earlier in section 2 of this manual.

Section 7

General Information

7-1. This section of the manual contains generalized user information as well as supplemental information to the List of Replaceable Parts contained in Section 5.

List of Abbreviations and Symbols

A or amp	ampere
ac	alternating current
af	audio frequency
a/d	analog-to-digital
assy	assembly
AWG	american wire gauge
B	bel
bcd	binary coded decimal
°C	Celsius
cap	capacitor
ccw	counterclockwise
cer	ceramic
cermet	ceramic to metal(seal)
ckt	circuit
cm	centimeter
cmrr	common mode rejection ratio
comp	composition
cont	continue
crt	cathode-ray tube
cw	clockwise
d/a	digital-to-analog
dac	digital-to-analog converter
dB	decibel
dc	direct current
dmm	digital multimeter
dvm	digital voltmeter
elect	electrolytic
ext	external
F	farad
°F	Fahrenheit
FET	Field-effect transistor
ff	flip-flop
freq	frequency
FSN	federal stock number
g	gram
G	giga (10^9)
gd	guard
Ge	germanium
GHz	gigahertz
gmv	guaranteed minimum value
gnd	ground
H	henry
hd	heavy duty
hf	high frequency
Hz	hertz
IC	integrated circuit
if	intermediate frequency
in	inch(es)
intl	internal
I/O	input/output
k	kilo (10^3)
kHz	kilohertz
kΩ	kilohm(s)
kV	kilovolt(s)
lf	low frequency
LED	light-emitting diode
LSB	least significant bit
LSD	least significant digit
M	mega (10^6)
m	milli (10^{-3})
mA	milliampere(s)
max	maximum
mf	metal film
MHz	megahertz
min	minimum
mm	millimeter
ms	millisecond
MSB	most significant bit
MSD	most significant digit
MTBF	mean time between failures
MTTR	mean time to repair
mV	millivolt(s)
mv	multivibrator
MΩ	megohm(s)
n	nano (10^{-9})
na	not applicable
NC	normally closed
(–) or neg	negative
NO	normally open
ns	nanosecond
opnl ampl	operational amplifier
p	pico (10^{-12})
para	paragraph
pcb	printed circuit board
pF	picofarad
pn	part number
(+) or pos	positive
pot	potentiometer
p-p	peak-to-peak
ppm	parts per million
PROM	programmablle read-only memory
psi	pound-force per square inch
RAM	random-access memory
rf	radio frequency
rms	root mean square
ROM	read-only memory
s or sec	second (time)
scope	oscilloscope
SH	shield
Si	silicon
serno	serial number
sr	shift register
Ta	tantalum
tb	terminal board
tc	temperature coefficient or temperature compensating
tcxo	temperature compensated crystal oscillator
tp	test point
u or μ	micro (10^{-6})
uhf	ultra high frequency
us or μs	microsecond(s) (10^{-6})
uut	unit under test
V	volt
v	voltage
var	variable
vco	voltage controlled oscillator
vhf	very high frequency
vlf	very low frequency
W	watt(s)
ww	wire wound
xfmr	transformer
xstr	transistor
xtal	crystal
xtlo	crystal oscillator
Ω	ohm(s)
μ	micro (10^{-6})

Federal Supply Codes for Manufacturers

D9816
Westermann Wilhelm Augusta-Anlage
Mannheim-Nackarau Germany

00199
Marcon Electronics Corp
Kearny, New Jersey

00213
Nytronics Comp. Group Inc.
Darrlington, South Carolina

00327
Welwyn International Inc.
Westlake, Ohio

00656
Aerovox Corp.
New Bedford, Massachusetts

00686
Film Capacitors Inc.
Passaic, New Jersey

00779
AMP, Inc.
Harrisburg, Pennsylvania

01121
Allen Bradley Co.
Milwaukee, Wisconsin

01281
TRW Electronics & Defense Sector
Lawndale, California

01295
Texas Instruments Inc.
Semiconductor Group
Dallas,Texas

01537
Motorola Communications &
Electronics Inc.
Franklin Park, Illinois

01686
RCL Electronics/Shallcross Inc.
Electro Components Div.
Manchester, New Hampshire

01884
Sprague Electric Co.
(Now 56289)

01961
Varian Associates Inc.
Pulse Engineering Div.
Convoy, Connecticut

02111
Spectrol Electronics Corp.
City of Industry, California

02114
Amperex Electronic Corp.
Ferrox Cube Div.
Saugerties, New York

02131
General Instrument Corp.Government
Systems Div.
Westwood, Massachusetts

02395
Sonar Radio Corp.
Hollywood, Florida

02533
Leigh Instruments Ltd.
Frequency Control Div.
Don Mills, Ontario, Canada

02606
Fenwal Labs
Division of Travenal Labs
Morton Grove, Illinois

0266
Bunker Ramo-Eltra Corp.
Amphenol NA Div.
Broadview, Illinois

02735
RCA-Solid State Div.
Somerville, New Jersey

02799
Arco Electronics Inc.
Chatsworth, California

03508
General Electric Co.
Semiconductor Products& Batteries
Auburn, New York

03797
Genisco Technology Corp.
Eltronics Div.
Rancho Dominquez, Calif.

03877
Gilbert Engineering Co.Inc
Incon Sub of Transitron
Electronic Corp.
Glendale, Arizona

03888
KDI Electronics Inc.
Pyrofilm Div.
Whippany, New Jersey

03911
Clairex Corp.
Clairex Electronics Div.
Mount Vernon, New York

03980
Muirhead Inc.
Mountainside, New Jersey

04009
Cooper Industries, Inc.
Arrow Hart Div.
Hartford, Connecticut

04217
Essex International Inc.
Wire & Cable Div.
Anaheim, California

04221
Midland-Ross Corp.
Midtex Div.
N. Mankato, Minnesota

04222
AVX Corp.
AVX Ceramics Div.
Myrtle Beach, S. Carolina

04423
Telonic Berkley Inc.
Laguna Beach, California

04713
Motorola Inc.
Semiconductor Group
Phoenix, Arizona

05236
Jonathan Mfg. Co.
Fullerton, California

05245
Corcom Inc.
Libertyville, Illinois

05276
ITT Pomona
Electronics Div.
Pomona, California

05277
Westinghouse Elec. Corp.
Semiconductor Div.
Youngwood, Pennsylvania

05397
Union Carbide Corp.
Materials Systems Div.
Cleveland. Ohio

05571
Sprague Electric Co.
(Now 56289)

05574
Viking Connectors Inc
Sub of Criton Corp.
Chatsworth, Calif.

05820
EG & G Wakefield Engineering
Wakefield, Massachusetts

05972
Loctite Corp.
Newington, Connecticut

06001
General Electric Co.
Electric Capacitor Product Section
Columbia, S. Carolina

06141
Fairchild Weston Systems Inc.
Data Systems Div.
Sarasota, Florida

06192
La Deau Mfg. Co.
Glendale, California

06229
Electrovert Inc.
Elmsford, New York

06383
Panduit Corp.
Tinley Park, Illinois

06473
Bunker Ramo Corp.
Amphenol NA Div.
SAMS Operation
Chatsworth, California

06555
Beede Electrical Instrument
Penacook, New Hampshire

06665
Precision Monolithics
Sub of Bourns Inc.
Santa Clara, California

06666
General Devices Co. Inc.
Indianapolis, Indiana

06739
Electron Corp.
Littleton, Colorado

06743
Gould Inc.
Foil Div.
Eastlake, Ohio

06751
Components Inc.
Semcor Div.
Phoenix, Arizona

06776
Robinson Nugent Inc.
New Albany, Indiana

06915
Richco Plastic Co.
Chicago, Illinois

06961
Vernitron Corp.
Piezo Electric Div.
Bedford, Ohio

06980
Varian Associates Inc.
Eimac Div.
San Carlos, California

07047
Ross Milton Co., The
Southampton, Penna.

07138
Westinghouse Electric Corp.
Industrial & Government
Tube Div.
Horseheads, New York

07233
Benchmark Technology Inc.
City of Industry, Calif.

07239
Biddle Instruments
Blue Bell, Penna.

07256
Silicon Transistor Corp.
Sub of BBF Inc.
Chelmsford, Massachusetts

07261
Avnet Corp.
Culver City, California

07263
Fairchild Camera & Instrument
Semiconductor Div.
Mountain View, California

07344
Bircher Co. Inc., The
Rochester, New York

Federal Supply Codes for Manufacturers (cont)

07557
Campion Co. Inc.
Philadelphia, Penna.

07597
Burndy Corp.
Tape/Cable Div.
Rochester, New York

07716
TRW Inc. (Can use 11502)
IRC Fixed Resistors/
Burlington
Burlington, Iowa

07792
Lerma Engineering Corp.
Northampton, Massachusetts

07810
Bock Corp.
Madison, Wisconsin

07933
Raytheon Co.
Semiconductor Div.
Mountain View, Calif.

08235
Industro Transistor Corp.
Long Island City, New York

08261
Spectra-Strip
An Eltra Co.
Garden Grove, Calif.

08530
Reliance Mica Corp.
Brooklyn, New York

08718
ITT Cannon Electric
Phoenix Div.
Phoenix, Arizona

08806
General Electric Co.
Minature Lamp Products
Cleveland, Ohio

08863
Nylomatic
Fallsington, Penna.

08988
Skottie Electronics Inc.
Archbald, Pennsylvania

09021
Airco Inc.
Airco Electronics
Bradford, Penna.

09023
Cornell-Dublier Electronics
Fuquay-Varina, N. Carolina

09214
General Electric Co.
Semiconductor Products Dept.
Auburn, New York

09353
C and K Components Inc.
Newton, Massachusetts

09423
Scientific Components Inc.
Santa Barbara, California

09579
CTS of Canada, Ltd
Streetsville, Ontario

09922
Burndy Corp.
Norwalk, Connecticut

09969
Dale Electronics Inc.
Yankton, South Dakota

09975
Burroughs Corp.
Electronics Components
Detroit, Michigan

10059
Barker Engineering Corp.
Kenilworth, New Jersey

10389
Illinois Tool Works Inc.
Licon Div.
Chicago, Illinois

10582
CTS of Asheville
Skyland, N. Carolina

11236
CTS Corp.
Berne Div.
Berne, Indiana

11237
CTS Corp of California
Paso Robles Div.
Paso Robles, California

11295
ECM Motor Co.
Schaumburg, Illinois

11358
Columbia Broadcasting System
CBS Electronic Div.
Newburyport, Massachusetts

11403
Vacuum Can Co.Best Coffee Maker Div.
Chicago, Illinois

11502
TRW Inc.
TRW Resistive Products Div.
Boone, North Carolina

11503
Keystone Columbia Inc.
Freemont, Indiana

11532
Teledyne Relays Teledyne
Industries Inc.
Hawthorne, California

11711
General Instrument Corp.
Rectifier Div.
Hicksville, New York

11726
Qualidyne Corp.
Santa Clara, California

12014
Chicago Rivet & Machine Co.
Naperville, Illinois

12040
National Semiconductor Corp.
Danbury, Connecticut

12060
Diodes Inc.
Northridge, California

12136
PHC Industries Inc.
Formerly Philadelphia Handle Co.
Camden, New Jersey

12300
AMF Canada Ltd.
Potter-Brumfield
Guelph, Ontario, Canada

12323
Practical Automation Inc.
Shelton, Connecticut

12327
Freeway Corp.
Cleveland, Ohio

12443
Budd Co.,The
Plastics Products Div.
Phoenixville, Pennsylvania

12581
Hitachi Metals International Ltd.
Hitachi Magna-Lock Div.
Big Rapids, Missouri

12615
US Terminals Inc.
Cincinnati, Ohio

12617
Hamlin Inc.
Lake Mills, Wisconsin

12697
Clarostat Mfg. Co. Inc.
Dover, New Hampshire

12749
James Electronic Inc.
Chicago, Illinois

12856
MicroMetals Inc.
Anaheim, California

12881
Metex Corp.
Edison, New Jersey

12895
Cleveland Electric Motor Co.
Cleveland, Ohio

12954
Microsemi Corp.
Components Group
Scottsdale, Arizona

12969
Unitrode Corp.
Lexington, Massachusetts

13050
Potter Co.
Wesson, Mississippi

13103
Thermalloy Co., Inc.
Dallas, Texas

13327
Solitron Devices Inc.
Tappan, New York

13511
Bunker-Ramo Corp.
Amphenol Cadre Div.
Los Gatos, California

13606
Sprague Electric Co.
(Use 56289)

13689
SPS Technologies Inc.
Hatfield, Pennsylvania

13919
Burr-Brown Research Corp.
Tucson, Arizona

14099
Semtech Corp.
Newbury Park, California

14140
McGray-Edison Co.
Commercial Development Div.
Manchester, New Hampshire

14193
Cal-R-Inc.
Santa Monica, California

14298
American Components Inc.
an Insilco Co. RPC Div.
Conshohocken, Pennsylvania

14298
ACIC Inc.
Sub of Insilco Corp.
Research Triangle Park, NC

14329
Wells Electronics Inc.
South Bend, Indiana

14482
Watkins-Johnson Co.
Palo Alto, California

14552
Microsemi Corp.
Santa Ana, California

14655
Cornell-Dublier Electronics
Div. of Federal Pacific
Electric Co. Govt Cont Dept.
Newark, New Jersey

Federal Supply Codes for Manufacturers (cont)

14704
Crydom Controls
(Division of Int Rectifier)
El Segundo, California

14752
Electro Cube Inc.
San Gabriel, California

14936
General Instrument Corp.
Discrete Semi Conductor Div.
Hicksville, New York

14949
Trompeter Electronics
Chatsworth, California

15412
Amtron
Midlothian, Illinois

15542
Scientific Components Corp.
Mini-Circuits Laboratory Div.
Brooklyn, New York

15636
Elec-Trol Inc.
Saugus, California

15782
Bausch & Lomb Inc.
Graphics & Control Div.
Austin, Texas

15801
Fenwal Eletronics Inc.
Div. of Kidde Inc.
Framingham, Massachusetts

15818
Teledyne Inc. Co.
Teledyne Semiconductor Div.
Mountain View, California

15849
Useco Inc.
(Now 88245)

15898
International Business
Machines Corp.
Essex Junction, Vermont

16245
Conap Inc.
Olean, New York

16258
Space-Lok Inc.
Burbank, California

16352
Codi Corp.
Linden, New Jersey

16469
MCL Inc.
LaGrange, Illinois

16473
Cambridge Scientific Industries
Div. of Chemed Corp.
Cambridge, Maryland

16733
Cablewave Systems Inc.
North Haven, Connecticut

16742
Paramount Plastics
Fabricators Inc.
Downey, California

16758
General Motors Corp.
Delco Electronics Div.
Kokomo, Indiana

17069
Circuit Structures Lab
Burbank, California

17117
Electronic Molding Corp.
Woonsocket, Rhode Island

17338
High Pressure Eng. Co. Inc.
Oklahoma City, Oklahoma

17545
Atlantic Semiconductors Inc.
Asbury Park, New Jersey

17745
Angstrohm Precision, Inc.
Hagerstown, Maryland

17856
Siliconix Inc.
Santa Clara, California

18178
E G & Gvactee Inc.
St. Louis, Missouri

18324
Signetics Corp.
Sacramento, California

18520
Sharp Electronics Corp.
Paramus, New Jersey

18542
Wabash Inc.
Wabash Relay & Electronics Div.
Wabash, Indiana

18565
Chomerics Inc.
Woburn, Massachusetts

18612
Vishay Intertechnology Inc.
Vishay Resistor Products Group
Malvern, Pennsylvania

18632
Norton-Chemplast
Santa Monica, California

18677
Scanbe Mfg. Co.
Div. of Zero Corp.
El Monte, California

18736
Voltronics Corp.
East Hanover, New Jersey

18927
GTE Products Corp.
Precision Material Products
Business Parts Div.
Titusville, Pennsylvania

19315
Bendix Corp., The
Navigation & Control Group
Terboro, New Jersey

19451
Perine Machinery & Supply Co..
Kent, Washington

19613
Minnesota Mining & Mfg. Co.
Textool Products Dept.
Electronic Product Div.
Irving, Texas

19647
Caddock Electronics Inc.
Riverside, California

19701
Mepco/Centralab Inc.
A N. American Philips Co.
Mineral Wells, Texas

20584
Enochs Mfg. Inc.
Indianapolis, Indiana

20891
Cosar Corp.
Dallas, Texas

21317
Electronics Applications Co.
El Monte, California

21604
Buckeye Stamping Co.
Columbus, Ohio

21845
Solitron Devices Inc.
Semiconductor Group
Rivera Beach, Florida

22526
DuPont, EI DeNemours & Co. Inc.
DuPont Connector Systems
Advanced Products Div.
New Cumberland, Pennsylvania

22767
ITT Semiconductors
Palo Alto, California

22784
Palmer Inc.
Cleveland, Ohio

23050
Product Comp. Corp.
Mount Vernon, New York

23732
Tracor Applied Sciences Inc.
Rockville, Maryland

23880
Stanford Applied Engineering
Santa Clara, California

23936
William J. Purdy Co.
Pamotor Div.
Burlingame, California

24347
Penn Engineering Co.
S. El Monte, California

24355
Analog Devices Inc.
Norwood, Massachusetts

24444
General Semiconductor
Industries, Inc.
Tempe, Arizona

24655
Genrad Inc.
Concord, Massachusetts

24759Lenox-Fugle Electronics Inc.
South Plainfield, New Jersey

24796
AMF Inc.
Potter & Brumfield Div.
San Juan Capistrano, Calif.

24931
Specialty Connector Co.
Greenwood, Indiana

25088
Siemen Corp.
Isilen, New Jersey

25099
Cascade Gasket
Kent, Washington

25403
Amperex Electronic Corp.
Semiconductor & Micro-Circuit Div.
Slatersville, Rhode Island

25706
Daburn Electronic & Cable Corp.
Norwood, New Jersey

26629
Frequency Sources Inc.
Sources Div.
Chelmsford, Massachusetts

26806
American Zettler Inc.
Irvine, California

27014
National Semiconductor Corp.
Santa Clara, California

27167
Corning Glass Works Corning
Electronics
Wilmington, North Carolina

27264
Molex Inc.
Lisle, Illinois

27440
Industrial Screw Products
Los Angeles, California

Federal Supply Codes for Manufacturers (cont)

27745
Associated Spring Barnes Group Inc.
Syracuse, New York

27956
Relcom (Now 14482)

28198
Positronic Industries
Springfield, Missouri

28213
Minnesota Mining & Mfg. Co.
Consumer Products Div.
3M Center
Saint Paul, Minnesota

28425
Serv-O-Link
Euless, Texas

28478
Deltrol Corporation
Deltrol Controls Div.
Milwaukee, Wisconsin

28480
Hewlett Packard Co.
Corporate HQ
Palo Alto, California

28484
Emerson Electric Co.
Gearmaster Div.
McHenry, Illinois

28520
Heyco Molded Products
Kenilworth, New Jersey

29083
Monsanto Co.
Santa Clara, California

29604
Stackpole Components Co.
Raleigh, North Carolina

29907
Omega Engineering Inc.
Stamford, Connnecticut

30035
Jolo Industries Inc.
Garden Grove, California

30146
Symbex Corp.
Painesville, Ohio

30148
AB Enterprise Inc.
Ahoskie, North Carolina

30161
Aavid Engineering Inc.
Laconia, New Hampshire

30315
Itron Corp.
San Diego, California

30323
Illinois Tool Works Inc.
Chicago, Illinois

30800
General Instrument Corp.
Capacitor Div.
Hicksville, New York

31019
Solid State Scientific Inc.
Willow Grove, Pennsylvania

31091
Alpha Industries Inc.
Microelectronics Div.
Hatfield, Pennsylvania

31323
Metro Supply Company
Sacramento, California

31448
Army Safeguard Logistics Command
Huntsville, Alabama

31746
Cannon Electric
Woodbury, Tennessee

31827
Budwig
Ramona, California

31918
ITT-Schadow
Eden Prairie, Minnesota

32293
Intersil
Cupertino, California

32539
Mura Corp.
Westbury, Long Island, N.Y.

32559
Bivar
Santa Ana, California

32767
Griffith Plastics Corp.
Burlingame, California

32879
Advanced Mechanical Components
Northridge, California

32897
Murata Erie North America Inc.
Carlisle Operations
Carlisle, Pennsylvania

32997
Bourns Inc.
Trimpot Div.
Riverside, California

33096
Colorado Crystal Corp.
Loveland, Colorado

33173
General Electric Co.
Owensboro, Kentucky

33246
Epoxy Technology Inc.
Billerica, Massachusetts

33297
NEC Electronics USA Inc.
Electronic Arrays Inc. Div.
Mountain View, California

33919
Nortek Inc.
Cranston, Rhode Island

34333
Silicon General Inc.
Garden Grove, California

34225
Advanced Micro Devices
Sunnyvale, California

34359
Minnesota Mining & Mfg. Co.
Commercial Office Supply Div.
Saint Paul, Minnesota

34371
Harris Corp.
Harris Semiconductor
Products Group
Melbourne, Florida

34649
Intel Corp.
Santa Clara, California

34802
Electromotive Inc.
Kenilworth, New Jersey

34848
Hartwell Special Products
Placentia, California

35009
Renfrew Electric Co. Ltd.
IRC Div.
Toronto, Ontario, Canada

36665
Mitel Corp.
Kanata, Ontario, Canada

37942
Mallory Capacitor Corp.
Sub of Emhart Industries
Indianapolis, Indiana

39003
Maxim Industries
Middleboro, Massachusetts

40402
Roderstein Electronics Inc.
Statesville, North Carolina

42498
National Radio
Melrose, Massachusetts

43543
Nytronics Inc.(Now 53342)

44655
Ohmite Mfg. Co.
Skokie, Illinois

49671
RCA Corp.
New York, New York

49956
Raytheon Company
Executive Offices
Lexington, Massachusetts

50088
Thomson Components-Mostek Corp.
Carrollton, Texas

50120
Eagle-Picher Industries Inc.
Electronics Div.
Colorado Springs, Colorado

50157
Midwest Components Inc.
Muskegon, Mississippi

50541
Hypertronics Corp.
Hudson, Massachusetts

50579
Litronix Inc.
Cupertino, California

51167
Aries Electronics Inc.
Frenchtown, New Jersey

51372
Verbatim Corp.
Sunnyvale, California

51406
Murata Erie, No. America Inc.
(Also see 72982)
Marietta, Georgia

51499
Amtron Corp.
Boston, Massachusetts

51605
CODI Semiconductor Inc.
Kenilworth, New Jersey

51642
Centre Engineering Inc.
State College, Pennsylvania

51791
Statek Corp.
Orange, California

51984
NEC America Inc.
Falls Church, Virginia

52063
Exar Integrated Systems
Sunnyvale, California

52072
Circuit Assembly Corp.
Irvine, California

52152
Minnesota Mining & Mfg.
Saint Paul, Minnesota

52333
API Electronics
Haugpauge,Long Island,New York

Federal Supply Codes for Manufacturers (cont)

52361
Communication Systems
Piscataway, New Jersey

52525
Space-Lok Inc.
Lerco Div.
Burbank, California

52531
Hitachi Magnetics
Edmore, Missouri

52745
Timco
Los Angeles, California

52763
Stettner-Electronics Inc.
Chattanooga, Tennessee

52769
Sprague-Goodman Electronics Inc.
Garden City Park, New York

52771
Moniterm Corp.
Amatrom Div.
Santa Clara, California

52840
Western Digital Corp.
Costa Mesa, California

53021
Sangamo Weston Inc.
(See 06141)

53217
Technical Wire Products Inc.
Santa Barbara, California

53342
Opt Industries Inc.
Phillipsburg, New Jersey

53944
Glow-Lite
Pauls Valley, Oklahoma

54294
Shallcross Inc.
Smithfield, North Carolina

54453
Sullins Electronic Corp.
San Marcos, California

54473
Matsushita Electric Corp.
(Panasonic)
Secaucus, New Jersey

54583
TDK
Garden City, New York

54869
Piher International Corp.
Arlington Heights, Illinois

54937
DeYoung Mfg.
Bellevue, Washington

54590
RCA Corp.
Electronic Components Div.
Cherry Hill, New Jersey

55026
American Gage & Machine Co.
Simpson Electric Co. Div.
Elgin, Illinois

55112
Plessey Capacitors Inc.
(Now 60935)

55261
LSI Computer Systems Inc.
Melville, New York

55285
Bercquist Co.
Minneapolis, Minnesota

55576
Synertek
Santa Clara, California

55680
Michicon/America/Corp.
Schaumburg, Illinois

56282
Utek Systems Inc.
Olathe, Kansas

56289
Sprague Electric Co.
North Adams, Massachusetts

56365
Square D Co.
Corporate Offices
Palatine, Illinois

56375
DAL Industries Inc.
Wescorp Div.
Mountain View, California

56481
Shugart Associates
Sub of Xerox Corp.
Sunnyvale, California

56708
Zilog Inc.
Campbell, California

56856
Vamistor Corp. of Tennessee
Sevierville, Tennessee

56880
Magnetics Inc.
Baltimore, Maryland

57026
Endicott Coil Co. Inc.
Binghamton, New York

57053
Gates Energy Products
Denver, Ohio

58014
Hitachi Magnalock Corp.
(Now 12581)

58104
Simco
Atlanta, Georgia

58474
Superior Electric Co.
Bristol, Connecticut

59124
KOA-Speer Electronics Inc.
Bradford, Pennsylvania

59640
Supertex Inc.
Sunnyvale, California

59660
Tusonix Inc.
Tucson, Arizona

59730
Thomas and Betts Corp.
Iowa City, Iowa

59831
Semtronics Corp.
Watchung, New Jersey

60395
Xicor Inc.
Milpitas, California

60399
Torin Engineered Blowers
Div. of Clevepak Corp.
Torrington, Connecticut

60705
Cera-Mite Corp.
(formerly Sprague)
Grafton, Wisconsin

60935
Westlake Capacitor Inc.
Tantalum Div.
Greencastle, Indiana

61804
M/A Com Inc.
Burlington, Massachusetts

61857
SAN-O Industrial Corp.
Bohemia, Long Island, NY

61935
Schurter Inc.
Petaluma, California

62351
Apple Rubber
Lancaster, New York

62793
Lear Siegler Inc.
Energy Products Div.
Santa Ana, California

63743
Ward Leonard Electric Co.Inc.
Mount Vernon, New York

64154
Lamb Industries
Portland, Oregon

64155
Linear Technology
Milpitas, California

64834
West M G Co.
San Francisco, Calif.

65092
Sangamo Weston Inc.
Weston Instruments Div.
Newark, New Jersey

65940
Rohm Corp & Whatney
Irvine, California

65964
Evox Inc.
Bannockburn, Illinois

66150
Entron Inc.
Winslow Teltronics Div.
Glendale, New York

66608
Bering Industries
Fremont, California

70290
Almetal Universal Joint Co.
Cleveland, Ohio

70485
Atlantic India Rubber Works Inc.
Chicago, Illinois

70563
Amperite Company
Union City, New Jersey

70903
Belden Corp.
Geneva, Illinois

71002
Bimbach Co. Inc.
Farmingdale, New York

71034
Bliley Electric Co.
Erie, Pennsylvania

71183
Westinghouse Electric Corp.
Bryant Div.
Bridgeport, Connecticut

71400
Bussman Manufacturing
Div. McGraw-Edison Co.
St. Louis, Missouri

71450
CTS Corp.
Elkhart, Indiana

71468
ITT Cannon Div. of ITT
Fountain Valley, California

71482
General Instrument Corp.
Clare Div.
Chicago, Illinois

Federal Supply Codes for Manufacturers (cont)

71590
Mepco/Centralab
A North American Philips Co.
Fort Dodge, Iowa

71707
Coto Corp.
Providence, Rhode Island

71744
General Instrument Corp.
Lamp Div/Worldwide
Chicago, Illinois

71785
TRW Inc.
Cinch Connector Div.
Elk Grove Village, Illinois

71984
Dow Corning Corp.
Midland, Michigan

72005
AMAX Specialty Metals Corp.
Newark, New Jersey

72136
Electro Motive Mfg. Corp.
Florence, South Carolina

72228
AMCA International Corp.
Continental Screw Div.
New Bedford, Massachusetts

72259
Nytronics Inc.
New York, New York

72619
Amperex Electronic Corp.
Dialight Div.
Brooklyn, New York

72653
G C Electronics Co.
Div. of Hydrometals Inc.
Rockford, Illinois

72794
Dzus Fastner Co. Inc.
West Islip, New York

72928
Gulton Industries Inc.
Gudeman Div.
Chicago, Illinois

72982
Murata Erie N. America Inc.
Erie, Pennsylvania

73138
Beckman Industrial corp.
Helipot Div.
Fullerton, California

73168
Fenwal Inc.
Ashland, Massachusetts

73293
Hughes Aircraft Co.
Electron Dynamics Div.
Torrance, California

73445
Amperex Electronic Corp.
Hicksville, New York

73559
Carlingswitch Inc.
Hartford, Connecticut

73586
Circle F Industries
Trenton, New Jersey

73734
Federal Screw Products Inc.
Chicago, Illinois

73743
Fischer Special Mfg. Co.
Cold Spring, Kentucky

73893
Microdot
Mt. Clemens, Mississippi

73899
JFD Electronic Components
Div. of Murata Erie
Oceanside, New York

73905
FL Industries Inc.
San Jose, California

73949
Guardian Electric Mfg. Co.
Chicago, Illinois

74199
Quam Nichols Co.
Chicago, Illinois

74217
Radio Switch Co.
Marlboro, New Jersey

74306
Piezo Crystal Co.
Div. of PPA Industries Inc.
Carlisle, Pennsylvania

74542
Hoyt Elect.Instr. Works Inc.
Penacook, New Hampshire

74840
Illinois Capacitor Inc.
Lincolnwood, Illinois

74970
Johnson EF Co.
Waseca, Minnesota

75042
TRW Inc.
IRC Fixed Resistors
Philadelphia, Pennsylvania

75297
Litton Systems
Kester Solder Div.
Chicago, Illinois

75376
Kurz-Kasch Inc.
Dayton, Ohio

75378
CTS Knights Inc.
Sandwich, Illinois

75382
Kulka Electric Corp.
(Now 83330)
Mount Vernon, New York

75915
Tracor Littlefuse
Des Plaines, Illinois

76854
Oak Switch Systems Inc.
Crystal Lake, Illinois

77122
TRW Assemblies & Fasteners Group
Fastener Div.
Moutainside, New Jersey

77342
AMF Inc.
Potter & Brumfield Div.
Princeton, Indiana

77542
Ray-O-Vac Corp
Madison, Wisconsin

77638
General Instrument Corp.
Rectifier Div.
Brooklyn, New York

77900
Shakeproof Lock Washer Co.
(Now 78189)

77969
Rubbercraft Corp. of CA Ltd.
Torrance, California

78189
Illinois Tool Works Inc.
Shakeproof Div.
Elgin, Illinois

78277
Sigma Instruments Inc.
South Braintree, Mass.

78290
Struthers Dunn Inc.
Pitman, New Jersey

78553
Eaton Corp.
Engineered Fastener Div.
Cleveland, Ohio

78592
Stoeger Industries
South Hackensack, New Jersey

79136
Waldes Kohinoor Inc.
Long Island City, New York

79497
Western Rubber Co.
Goshen, Indiana

79727
C - W Industries
Southampton, Pennsylvania

79963
Zierick Mfg. Corp.
Mount Kisco, New York

80009
Tektronix
Beaverton, Oregon

80031
Mepco/Electra Inc.
Morristown, New Jersey

80032
Ford Aerospace & Communications Corp.
Western Development
Laboratories Div.
Palo Alto, California

80145
LFE Corp.
Process Control Div.
Clinton, Ohio

80183
Sprague Products
(Now 56289)

80294
Bourns Instruments Inc.
Riverside, California

80583
Hammerlund Mfg. Co. Inc.
Paramus, New Jersey

80640
Computer Products Inc.
Stevens-Arnold Div.
South Boston, Mass.

81073
Grayhill Inc.
La Grange, Illinois

81312
Litton Systems Inc.
Winchester Electronics Div.
Watertown, Connecticut

81439
Therm-O-Disc Inc.
Mansfield, Ohio

81483
International Rectifier Corp.
Los Angeles, California

81590
Korry Electronics Inc.
Seattle, Washington

81741
Chicago Lock Co.
Chicago, Illinois

82227
Airpax Corp.
Cheshire Div.
Cheshire, Connecticut

82240
Simmons Fastner Corp.
Albany, New York

Federal Supply Codes for Manufacturers (cont)

82305
Palmer Electronics Corp.
South Gate, California

82389
Switchcraft Inc.
Sub of Raytheon Co.
Chicago, Illinois

82415
Airpax Corp
Frederick Div.
Frederick, Maryland

82872
Roanwell Corp.
New York, New York

82877
Rotron Inc.
Custom Div.
Woodstock, New York

82879
ITT
Royal Electric Div.
Pawtucket, Rhode Island

83003
Varo Inc.
Garland, Texas

83014
Hartwell Corp.
Placentia, California

83055
Signalite Fuse Co.
(Now 71744)

83058
TRW Assemblies & Fasteners Group
Fasteners Div.
Cambridge, Massachusetts

83259
Parker-Hannifin Corp.
O-Seal Div.
Culver City, California

83298
Bendix Corp.
Electric & Fluid Power Div.
Eatonville, New Jersey

83315
Hubbell Corp.
Mundelein, Illinois

83330
Kulka Smith Inc.
A North American Philips Co.
Manasquan, New Jersey

83478
Rubbercraft Corp. of America
West Haven, Connecticut

83553
Associated Spring Barnes Group
Gardena, California

83740
Union Carbide Corp.
Battery Products Div.
Danbury, Connecticut

84171
Arco Electronics
Commack, New York

84411
American Shizuki
TRW Capacitors Div.
Ogallala, Nebraska

84613
FIC Corp.
Rockville, Maryland

84682
Essex Group Inc.
Peabody, Massachusetts

85367
Bearing Distributing Co.
San Fransisco, California

85372
Bearing Sales Co.
Los Angeles, California

85480
W. H. Brady Co.
Industrial Product
Milwaukee, Wisconsin

85932
Electro Film Inc.
Valencia, California

86577
Precision Metal Products Co.
Peabody, Massachusetts

86684
Radio Corp. of America
(Now 54590)

86928
Seastrom Mfg. Co. Inc.
Glendale, California

87034
Illuminated Products Inc.
(Now 76854)

88219
GNB Inc.
Industrial Battery Div.
Langhorne, Pennsylvania

88245
Winchester Electronics
Litton Systems-Useco Div.
Van Nuys, California

88486
Triangle PWC Inc.
Jewitt City, Connecticut

88690
Essex Group Inc.
Wire Assembly Div.
Dearborn, Michigan

89020
Amerace Corp.
Buchanan Crimptool Products Div.
Union, New Jersey

89265
Potter-Brumfield
(See 77342)

89536
John Fluke Mfg. Co., Inc.
Everett, Washington

89597
Fredericks Co.
Huntingdon Valley, Penna.

89709
Bunker Ramo-Eltra Corp.
Amphenol Div.
Broadview, Illinois

89730
General Electric
Lamp Div.
Newark, New Jersey

90201
Mallory Capacitor Co.
Sub of Emhart Industries Inc.
Indianapolis, Indiana

90215
Best Stamp & Mfg. Co.
Kansas City, Missouri

90303
Duracell Inc.
Technical Sales & Marketing
Bethel, Connecticut

91094
Essex Group Inc.
Suflex/IWP Div.
Newmarket, New Hampshire

91247
Illinois Transformer Co.
Chicago, Illinois

91293
Johanson Mfg. Co.
Boonton, New Jersey

91462
Alpha Industries Inc.
Logansport, Indiana

91502
Associated Machine
Santa Clara, California

91506
Augat Inc.
Attleboro, Massachusetts

91507
Froeliger Machine Tool Co.
Stockton, California

91637
Dale Electronics Inc.
Columbus, Nebraska

91662
Elco Corp.
A Gulf Western Mfg. Co.
Connector Div.
Huntingdon, Pennsylvania

91737
ITT Cannon/Gremar
(Now 08718)

91802
Industrial Devices Inc.
Edgewater, New Jersey

91833
Keystone Electronics Corp.
New York, New York

91836
King's Electronics Co. Inc.
Tuckahoe, New York

91929
Honeywell Inc.
Micro Switch Div.
Freeport, Illinois

91934
Miller Electric Co.
Woonsocket, Rhode Island

91984
Maida Development Co.
Hampton, Virginia

91985
Norwalk Valve Co.
S. Norwalk, Connecticut

92914
Alpha Wire Corp.
Elizabeth, New Jersey

93332
Sylvania Electric Products
Semiconductor Products Div.
Woburn, Massachusetts

94144
Raytheon Co.
Microwave & Power Tube Div.
Quincy, Massachusetts

94222
Southco Inc.
Concordville, Pennsylvania

94988
Wagner Electric Corp.
Sub of Mcgraw-Edison Co.
Whippany, New Jersey

95146
Alco Electronic Products Inc.
Switch Div.
North Andover, Massachusetts

95263
Leecraft Mfg. Co.
Long Island City, New York

95275
Vitramon Inc.
Bridgeport, Connecticut

95303
RCA Corp.
Receiving Tube Div.
Cincinnati, Ohio

95348
Gordo's Corp.
Bloomfield, New Jersey

95354
Methode Mfg. Corp.
Rolling Meadows, Illinois

Federal Supply Codes for Manufacturers (cont)

95573
Campion Laboratories Inc.
Detroit, Michigan

95712
Bendix Corp.
Electrical Comp. Div.
Franklin, Indiana

95987
Weckesser Co. Inc.
(Now 85480)

96733
SFE Technologies
San Fernando, California

96853
Gulton Industries Inc.
Measurement & Controls Div.
Manchester, New Hampshire

96881
Thomson Industries Inc.
Port Washington, New York

97525
EECO Inc.
Santa Ana, California

97540
Whitehall Electronics Corp.
Master Mobile Mounts Div.
Fort Meyers, Florida

97913
Industrial Electronic
Hardware Corp.
New York, New York

97945
Pennwalt Corp.
SS White Industrial Products
Piscataway, New Jersey

97966
CBS
Electronic Div.
Danvers, Massachusetts

98094
Machlett Laboratories Inc.
Santa Barbara. California

98159
Rubber-Teck Inc.
Gardena, California

98278
Malco A Microdot Co.
South Pasadena, California

98291
Sealectro Corp.
BICC Electronics
Trumbill, Connecticut

98372
Royal Industries Inc.(Now 62793)

98388
Lear Siegler Inc.
Accurate Products Div.
San Deigo, California

99120
Plastic Capacitors Inc.
Chicago, Illinois

99217
Bell Industries Inc.
Elect. Distributor Div.
Sunnyvale, California

99378
ATLEE of Delaware Inc.
N. Andover, Massachusetts

99392
Mepco/Electra Inc.
Roxboro Div.
Roxboro, North Carolina

99515
Electron Products Inc.
Div. of American Capacitors
Duarte, California

99779
Bunker Ramo- Eltra Corp.
Barnes Div.
Lansdown, Pennsylvania

99800
American Precision Industries
Delevan Div.
East Aurora, New York

99942
Mepco/Centralab
A North American Philips Co.
Milwaukee, Wisconsin

U.S. SALES OFFICE AREAS

AL, Huntsville
John Fluke Mfg. Co., Inc.
4920J Corporate Drive
Huntsville, AL 35805-6202
(205) 837-0581

AZ, Phoenix
John Fluke Mfg. Co., Inc.
2211 S. 48th Street
Suite B
Tempe, AZ 85282
(602) 438-8314

Tucson
(602) 790-9881

CA, Southern
John Fluke Mfg. Co., Inc.
P.O. Box 19676
Irvine, CA 92713-9676
16969 Von Karman
Suite 100
Irvine, CA 92714
(714) 863-9031

Burbank
John Fluke Mfg. Co., Inc.
2020 N. Lincoln Street
Burbank, CA 91504
(213) 849-7181

Northern
John Fluke Mfg. Co., Inc.
2300 Walsh Ave., Bldg. K
Santa Clara, CA 95051
(408) 727-0513

San Diego
(619) 292-7656

CO, Denver
John Fluke Mfg. Co., Inc.
14180 East Evans Ave.
Aurora, CO 80014
(303) 695-1000

CT, Hartford
John Fluke Mfg. Co., Inc.
Glen Locken East
41-C New London Turnpike
Glastonbury, CT 06033
(203) 659-3541

DC, Washington
(301) 770-1570

FL, Clearwater
(813) 799-0087

Miami
(305) 462-1380

Orlando
John Fluke Mfg. Co.,Inc.
940 N. Fern Creek Ave.
Orlando, FL 32803
(305) 896-4881

Tampa
(813) 251-9211

GA, Atlanta
John Fluke Mfg. Co., Inc.
2700 Delk Rd., Suite 150
Marietta, GA 30067
(404) 953-4747

IL, Chicago
John Fluke Mfg. Co., Inc.
1150 West Euclid Ave.
Palatine, IL 60067
(312) 705-0500

IN, Indianapolis
John Fluke Mfg. Co., Inc.
8777 Purdue Rd.
Suite 101
Indianapolis, IN 46268
(317) 875-7870

LA, Baton Rouge
(504) 924-1203

New Orleans
(504) 455-0814

MA, Boston
John Fluke Mfg. Co., Inc.
Middlesex Tech Center
900 Middlesex Turnpike
Building 8
Billerica, MA 01821
(617) 663-2400

MD, Baltimore
(301) 792-7060

Rockville
John Fluke Mfg. Co., Inc.
5640 Fishers Lane
Rockville, MD 20852
(301) 770-1570

MI, Detroit
John Fluke Mfg. Co., Inc.
33031 Schoolcraft
Livonia, MI 48150
(313) 522-9140

MN, Bloomington
John Fluke Mfg. Co., Inc.
1801 E. 79th St., Suite 9
Bloomington, MN 55420
(612) 854-5526

MO, St. Louis
John Fluke Mfg. Co., Inc.
11756 Borman Drive
Suite 160
St. Louis, MO 63146
(314) 993-3805

NC, Greensboro
John Fluke Mfg. Co., Inc.
1310 Beaman Place
Greensboro, NC 27408
(919) 273-1918

NJ, Paramus
John Fluke Mfg. Co., Inc.
P.O. Box 930
Paramus, NJ 07653-0930
West 75 Century Road
Paramus, NJ 07652
(201) 262-9550

NM, Albuquerque
(505) 881-3550

NY, Rochester
John Fluke Mfg. Co., Inc.
4515 Culver Road
Rochester, NY 14622
(716) 323-1400

OH, Cleveland
John Fluke Mfg. Co., Inc.
7830 Freeway Circle
Middleburg Heights, OH 44130
(216) 234-4540

Dayton
John Fluke Mfg. Co., Inc.
5450 Far Hills Avenue
Suite 111
Kettering, OH 45429
(513) 436-2224

OK, Northeast
(918) 749-0190

OR, Portland
(503) 227-2042

PA, Philadelphia
John Fluke Mfg. Co., Inc.
200 Lindenwood Drive
Malvern, PA 19355
(215) 647-9550

Pittsburgh
(412) 261-5171

TX, Austin
(512) 459-3344

Dallas
John Fluke Mfg. Co., Inc.
1801 Royal Lane
Suite 307
Dallas, TX 75229
(214) 869-0311

El Paso
(915) 533-3508

Houston
(713) 240-5995

San Antonio
John Fluke Mfg. Co., Inc.
10417 Gulfdale
San Antonio, TX 78216
(512) 340-0498

UT, Salt Lake City
(801) 268-9331

WA, Seattle
John Fluke Mfg. Co., Inc.
5020 148th Ave. N.E.
Suite #110
Redmond, WA 98052
(206) 881-6966

U.S. Government Specialists

Army	(301) 770-1570, MD (203) 837-0581, AL
Navy	(714) 863-9031, CA (301) 770-1570, MD
USAF	(513) 436-2224, OH (512) 340-2621, TX
Security	(301) 770-1570, MD

Service Center Areas

CA, Burbank (213) 849-4641
CA, Santa Clara (408) 727-0513
CO, Denver (303) 695-1000
FL, Orlando (305) 896-4881
IL, Chicago (312) 705-0500
MD, Rockville (301) 770-1576
NJ, Paramus (201) 262-9550
TX, Dallas (214) 869-2848
WA, Everett (206) 356-5560

For more information on Fluke products or Sales Offices you may dial (800) 426-0361 toll-free in most of the U.S.A. From Alaska, Hawaii, or Washington phone (206) 356-5400. From Canada and other countries phone (206) 356-5500.

FLUKE®
John Fluke Mfg. Co., Inc., P.O. Box C9090, Everett, WA 98206
Fluke (Holland) B.V., P.O. Box 2269, 5600 CG, Eindhoven, The Netherlands. Phone (040) 458045
Litho in U.S.A. 11/87

INTERNATIONAL SALES OFFICES

Argentina ●
Coasin S.A.
Virrey del Pino 4071 DPTO E-65
1430 CAP FED
Buenos Aires, Argentina
Tel: 54-1-552-5248
TLX: (390) 22284 COASN AR

Asia
Fluke Asia Ltd.
Shun Tak Centre, Room 1501
200 Connaught Road
Central, Hong Kong
Tel: 852 5 482116
TLX: (780) 87058 FLUKE
FAX: (852) 5-479863

Australia ●
Elmeasco Instruments Pty, Ltd.
P.O. Box 30
Concord, N.S.W. 2137
Australia
Tel: 61-2-736-2888
TLX: (790) 25887 A/B: ELSCOAA 25887
FAX: 61-2-733663

Elmeasco Instruments Pty, Ltd.
P.O. Box 623
12 Maroondah Highway
Ringwood, Victoria 3134
Australia
Tel: 61-3-879-2322
TLX: (790) 30418 A/B: ELTENTAA 30418
FAX: (61) (3) 879-4310

Elmeasco Instruments Pty, Ltd.
P.O. Box 274
Salisbury, Queensland 4107
Australia
Tel: 61-7-875-1444
TLX: (790) 44062 A/B: ELMQLDAA44062

Elmeasco Instruments Pty, Ltd.
P.O. Box 154
Prospect, South Australia 5082
Tel: 61-8-344-9000 TLX: (790) A/B:87519

Elmeasco Instruments Pty, Ltd.
P.O. Box 413
Scott House
46-48 Kings Park Road
West Perth, Western Australia 6005
Australia
Tel: 61-9-481-1500
TLX: (790) 94765 A/B: ASECSAA 94765
FAX: (61) (9) 322-2075

Austria ■
Walter Rekirsch Elektronische
Gerate GmbH & Co.
Vertrieb KG
Obachgasse 28
1220 Vienna, Austria
Tel: 43-222-25-36-26
TLX: (847) 134759
FAX: 43-222-25-72-75

Bahrain ●
Basma W.L.L.
P.O. Box 5701
Manama, Bahrain
Tel: 973-251364; TLX: (955) 9003
FAX: (965) 245218

Bangladesh ●
Motherland Corporation
24 Hatkhola Road, Tikatuli
Dacca-3, Bangladesh
Tel: 257249
TLX: (950) 642022 PCO BJ
Cable: "MOTHERLAND" DACCA

Belgium ■
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

Bolivia ●
Coasin Bolivia S.R.L.
Casilla 7295
La Paz, Bolivia
Tel: 591-2-40962
TLX: (336) 3233 COALAP BV
Cable: COALAP

Brazil ●
ATP/Hi-Tek Eletronica Ltda.
Al. Amazonas 422,
Alphaville, 06400, Barueri
Sao Paulo, Brazil
Tel: 55-11-421-5477;
TLX: (391) 1171413 HITK BR

Brunei ●
Rank O'Connor's SDN BHD
No. 8 Blk D
Sufri Shophouse Complex
Mile 1 Jalan Tutong
Bandar Seri Begawan
Negara Brunei Darussalam
Tel: 673-2-23109 or 23557
TLX: (799) BU 2265 RANKOC

Canada ●
Fluke Electronics Canada Inc.
101, 1144 - 29th Avenue N.E.
Calgary, Alberta T2E 7P1
Canada
Tel: (403) 291-5215
Fax: (403) 291-5219

Fluke Electronics Canada Inc.
400 Britannia Road East
Unit #1
Mississauga, Ontario L4Z 1X9
Tel: (416) 890-7600
Fax: (416) 890-6866

Fluke Electronics Canada Inc.
1255 Trans Canada Hwy.
Suite 130
Dorval, Quebec
H9P 2V4 Canada
Tel: (514) 685-0022
TLX: (514) 685-0039

Fluke Electronics Canada Inc.
1690 Woodward Drive
Suite 216
Ottawa, Ontario
K2C 3R8 Canada
Tel: (613) 723-9453
Fax: (613) 723-9458

Chile ●
Intronica Chile, Ltda.
Casilla 16228 (Mail)
Santiago 9, Chile
Tel: 56-2-2321886
TLX: (332) 346351 INTRON CK

China, Peoples Republic of ●
Fluke International Corporation
P.O. Box 9085
Beijing
People's Republic of China
Tel: 86-01-65-7281
TLX: (716) 222237 FBSC CN

Instrimpex - Fluke Service Center
57, Xisi Dong Da Jie
Xicheng-qu
Beijing
Peoples Republic of China
Tel: 86-01-65-7281

Colombia ●
Sistemas E Instrumentacion, Ltda.
Carrera 13, No. 37-43, Of. 401
Ap. Aereo 29583
Bogota DE, Colombia
Tel: 57-232-4532
TLX: (396) 45787 COASN CO

Cyprus ■
Chris Radiovision, Ltd.
P.O. Box 1989
Nicosia, Cyprus
Tel: 357-21-66121; TLX: (826) 2395

Cyprus, Northern ■
Ucok Buroteknik
2C & 2D Muftu Ziyai Street
Lefkosa, Northern Cyprus
Mersin 10, Turkey
Tel: 90-741-357-20-71777
TLX: (821) 57267

Czechoslovakia ■
Amtest Associates, Ltd.
Amtest House
75-79 Guildford Street
Chertsey, Surrey KT16 9AS
England
Tel: 44-9328-68355
TLX: (851) 928855 AMTEST G
Fax: 44-9328-61919

Denmark ■
Tage Olsen A/S
Ballerup Byvej 222
2750 Ballerup
Denmark
Tel: 45-2-658111
TLX: (855) 35293 TOAS DK

Eastern European Countries ■
Amtest Associates, Ltd.
Amtest House
75-79 Guildford Street
Chertsey, Surrey KT16 9AS
England
Tel: 44-9328-68355
TLX: (851) 928855 AMTEST G
Fax: 44-9328-61919

German Branch Office
Amtest Associates, Ltd.
Zugspitzstrasse 2A
P.O. Box 1107
8011 Vaterstetten
West Germany
Tel: 49-81-067117, TLX: (841) 528332

Ecuador ●
Proteco Coasin Cia., Ltda.
P.O. Box 228-A
Ave. 12 de Octubre 2285
y Orellana
Quito, Ecuador
Tel: 593-2-529684
TLX: (393) 22085 ESIND

Egypt
Electronic Engineering Liaison Office
P.O. Box 2891 Horreya
11361 Heliopolis, Cairo
Egypt
Tel: 20-2-695705, TLX: (927) 22782

England
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

Fiji ●
Awa New Zealand Limited
37 Freeston Road
Walu Bay, P.O. Box 858
Suva, Fiji
Tel: 679-312079, TLX: (792) FJ2347
FAX: 679-314379

Finland ■
Instrumentarium Elektroniika
P.O. Box 64
02631 Espoo 63
Finland
Tel: 358-0-5281
TLX: (857) 124426 HAVUL SF
FAX: (358) 0-5021073
Teletex: (857) 8-100155 INSTRUE

France ■
M.B. Electronique S.A.
606, Rue Fourney
P.O. Box 31
78530 BUC, France
Tel: 33-1-39-56-81-31
TLX: (842) 695414
Fax: (33) (1) 3956-53-44

German Branch Office
Amtest Associates, Ltd.
Zugspitzstrasse 2A
P.O. Box 1107
8011 Vaterstetten
West Germany
Tel: 49-81-067117
TLX: (841) 528332

Germany, West
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

Greece
Hellenic Scientific Representations Ltd.
11, Vrassida Street
Athens 612, Greece
Tel: 30-1-7211140, TLX: (863) 219330

Hong Kong ●
Schmidt & Co (H.K.), Ltd
18th Floor, Great Eagle Centre
23 Harbour Road
Wanchai, Hong Kong
Tel: 852-5-8330-222
TLX: (780) 74766 SCHMC HX
FAX: 852-5-8918754

India ●
Hinditron Services Pvt., Ltd.
69/A.L. Jagmohandas Marg
Bombay 400 006, India
Tel: 91-22-8121316, 8125344
TLX: (953) 1175326 HSPL IN

Bangalore Office
Hinditron Services Pvt., Ltd.
8th Main Road
33/44A Raj Mahal Vilas Extension
Bangalore 560 080, India
Tel: 91-812-363139
TLX: (953) 08452741
Cable: TEKHIND BANGALORE

Calcutta Office
Hinditron Services Pvt. Ltd.
5th Floor, Castle House
5/1A, Hungerford St.
Calcutta 700 017, India
Tel: 91-33-432628
TLX: (953) 214153

New Delhi Sales
Hinditron Services Pvt. Ltd.
204-206 Hemkunt Tower
98 Nehru Place
New Delhi, 110019, India
Tel: 91 (11) 6410380 or 6414493
TLX: (953) 3161458 HSPL IN

New Delhi Service
Hinditron Services Pvt., Ltd.
Field Service Center
15, Community Centre
Panchshila Park
New Delhi 110 017, India
Tel: 91 011 6433675

Cable: Tekcentre Delhi
Hyderabad Office
Hinditron Services Pvt. Ltd.
Field Service Center
Emerald Complex, 5th Floor
1-7-264
114 Sarojini Devi Road
Secunderabad 500 003, India
Tel: 91 842 821117
TLX: (953) 04256973 HSPL IN

Indonesia ●
P.T. Lamda Triguna
P.O. Box 6/JATJG
Jakarta, 13001
Indonesia
Tel: 62 21 8195365
TLX: (796) 46171 LAYARIA

Iran ■
Arma Baynelmeleli Co., Ltd.
P.O. Box 951570
Pasdaran-Tehran
Tel: 98-21-248717, TLX: (951) 213648

Ireland
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

Israel ■
R.D.T. Electronics Engineering Ltd.
P.O. Box 43137
Tel Aviv 61430
Israel
Tel: (3) 972-3-483211
TLX: (922) 371452 RDT IL
Fax: 972-3-492190

Italy ■
Sistrel S.p.A.
Via le Erminio Spalla 41
00142 Rome, Italy
Tel: 39-6-504-1367, TLX: (843) 625857
Fax: (39) 6-504137

FLUKE®

John Fluke Mfg. Co., Inc. / PO Box C9090 / Everett, WA 98206 / (206) 356 5400

Litho in U.S.A. 11/87

Milan Office
Sistrel S.p.A.
Via Pelizza da Volpedo 59
20092 Cinisello Balsamo
Milan, Italy
Tel: 39-2-6181893, TLX: (843) 334643
Fax: (39) 2-6182440

Naples Office
Sistrel S.p.A.
Via Cintia
Parco S. Paolo 35
80126 Naples, Italy
Tel: 39-81-7678700
Fax: (39) 81-7661361

Japan ●
John Fluke Mfg. Co., Inc.
Japan Branch
Sumitomo Higashi Shinbashi Bldg.
1-1-11 Hamamatsucho
Minato-ku, Tokyo 105, Japan
Tel: 81-3-434-0181
TLX: (781) 2424331 FLUK JPJ
FAX: 81-3-434-0170

Osaka Sales Office
John Fluke Mfg. Co., Inc.
Japan Branch
Katsushige Building
2-45 Kohraibashi
Higashi-ku, Osaka 541
Japan
Tel: 81-6-229-0871 FAX: 81-6-229-1098

Korea, Republic of ●
Myoung Corporation
Yeo Eui Do P.O. Box 14
Seoul, Korea
Tel: 82-2-784-9942 MYOUNG
TLX: (787) K24283
FAX: (82) 2-784-2387

Kuwait ■
Al Bahar International Group
P.O. Box 26672 Safat
13127 Safat, Kuwait
Kuwait, Arabian Gulf
Tel: 965-848601, 847598
TLX: (959) 44822

Lebanon and Jordan ■
Mabek (Electronics Division)
P.O. Box 13-5657
Beirut, Lebanon
Tel: 812523
TLX: (923) 22889 LIBANK LE

Malaysia ●
Mecomb Malaysia Sdn Bhd
P.O. Box 24
46700 Petaling Jaya, Selangor, Malaysia
Tel: 60-3-774-3422
TLX: (784) MA37764 MECOMB
Fax: (6) 03-774-3414

Malta ■
Fabian Enterprises
20, Msida Road
Gzira, Malta
Tel: 513283/40216, TLX: (838) 1837

Mexico ●
Mexicana de Electronica
Industrial, S.A. (Mexel)
Diagonal No. 27
Entre Calle de Eugenia Y Ave
Colonia del Valle
C.P. 03100, Mexico
Tel: (905) 660-4323
TLX: (383) 1771038 FAIRME

Executone De Monterrey, S.A.
Ave. Gonzalitos NTE 545
Monterrey N.L., Mexico
Tel: 90-5-480400, 472625
TLX: (383) 382659

Morocco ■
Oussama S.A.
Angle Boulevard Emile Zola et
Rue Rethel
P.O. Box 2007 Casa
Casablanca
Morocco
Tel: 212-24-13-38, TLX: (933) 28879 M

Nepal ●
Associated Enterprises
GPO Box 790, Pyaphal Tole
Kathmandu, Nepal
Tel: 13868, TLX: (947) 2568 (ASOENT NP)

Netherlands
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

New Zealand ●
Auckland Office
Northrop Instruments & Systems, Ltd.
459 Khyber Pass Road
Private Bag, Newmarket
Auckland 1, New Zealand
Tel: 64-9-501-801, 501-219
TLX: (791) 21570
FAX: 64-9-543430

Wellington Office
Northrop Instruments & Systems Ltd.
Information Technology Group
First Floor, Northrop Bldg.
189-191 Willis Street
P.O. Box 2406
Wellington, New Zealand
Tel: 64-4-856-658
TLX: (791) 3380

Christchurch Office
Northrop Instruments & Systems Ltd.
Information Technology Group
110 Mandeville Street
P.O. Box 8388
Christchurch, New Zealand
Tel: 64-3-488-874
TLX: (791) 4801

Norway ■
Morgenstierne & Co A/S
Konghellegate 3
P.O. Box 6688, Rodelokka
Oslo 5, Norway
Tel: (2) 356110, TLX: (856) 71719

Oman ■
OHI Telecommunications LLC
P.O. Box 889
Muscat, Oman
Tel: 968-603606
TLX: (926) 5052 TELECOM ON

Pakistan ●
International Operations (PAK), Ltd.
505 Muhammadi House
I.I. Chundrigar Road
P.O. Box 5323, Karachi, Pakistan
Tel: 92-21-221127, TLX: (952) 24494 PIO PK

Peru ●
Importaciones y Representaciones
Electronicas S.A.
Avda. Franklin D. Roosevelt 105
Lima 1, Peru
Tel: 51-14-28-8650
TLX: (394) 25663 PE IREING

Philippines, Republic of ●
Spark Radio & Electronics, Inc.
Greenhills P.O. Box 610
San Juan, Metro Manila, Zip 3113
Philippines
Tel: 63-2-775192, 704096
TLX: (722 or 732) 27901 RLA PH

Portugal ■
Decada Espectral
Equipamentos de Electronica
Av. Bombeiros Voluntarios
Lote 102B, Miraflores/Alges
1495 Lisbon, Portugal
Tel: 351-1-4103420, TLX: (832) 15515

Romania ■
Amtest Associates Ltd.
Amtest House
75-79 Guildford Street
Chertsey, Surrey KT16 9AS
England
Tel: 44-9328-68355, TLX: (851) 928855
FAX: 44-9328-61919

Saudi Arabia ■
Electronic Equipment Marketing Co.
P.O. Box 3750
Riyadh, Saudi Arabia
Tel: 966-1-477-1650
TLX: (928) 401120 ZUHAIR SJ

Scotland
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

Singapore, Republic of ●
Rank O'Connor's (PTE) Ltd.
O'Connor House
98 Pasir Panjang Road
Singapore 0511
Republic of Singapore
Tel: 65-4737944, TLX: (786) RS21023 OCONSIN
FAX: 4724508 CABLE CINECOM SINGAPORE

South Africa ●
Protea PNI
P.O. Box 39127
Bramley 2018
Republic of South Africa
Tel: 27-11-786-3647
TLX: (960) 4-24409 SA
FAX 27-11-786-1807

Spain ■
ESSA
Equipos y Sistemas S.A.
C/Apolonio Morales, 13-B
Madrid 16, Spain
Tel: 34-1-458-0150
TLX: (831) 42856 EYS E

Sri Lanka ●
Computerlink Data Systems, Ltd.
331 Union Place
Colombo 2, Sri Lanka
Tel: 94-1-28641
TLX: (954) 22455 COLINK CE

Sweden
N.V. Philips
Industrial & Electro-Acoustic Systems
5600 MD Eindhoven
The Netherlands
Tel: 040-785539
Tlx: 35000 phtc nl
Fax: 040-785651

Switzerland ■
Traco Electronic AG
Jenatschstrasse 1
8002 Zurich
Switzerland
Tel: 41-1-201-0711
TLX: (845) 815570 TRCOCH

Syria ■
Mabek (Electronics Division)
P.O. Box 4238
Damascus, Syria

Taiwan ●
Schmidt Electronics Corp.
5th Fl, Cathay Min Sheng
Commercial Building,
344 Min Sheng East Road
Taipei Taiwan R.O.C.
Tel: 886-2-501-3468
TLX: (785) 11111 SCHMIDT
Fax: (886) 2-502-9692

Thailand ●
Measuretronix Ltd.
2102/63 Ramkamhaeng Rd.
Huamark Bangkok 10240
Thailand
Tel: 66 (2) 3742516, 3741632
TLX: (788) 82796 HUAMARK TH

Tunisia ■
Selep S.A.R.L.
6, Rue de Sparte
Tunis - 1000 RP
Tunisia
Tel: 216-1-248093, TLX: (934) 13030

Turkey ■
Erkman Elektronik Aletler
Ticaret Anonim Sirketi
Necatibey Cad 92/3
Karakoy, Istanbul, Turkey
Tel. 90 (11) 441546, TLX: (821) 24399

United Arab Emirates ■
Haris Al-Afag, Ltd.
P.O. Box 8141
Kamal Hamza Bldg.
Traffic Police Road
Dubai, U.A.E.
Tel: 971-4-283625
TLX: (958) 48168 AFAQEM

Al-Sanani Cen. Trad. Est.
P.O. Box 7187
Abu-Dhabi, U.A.E.
Tel: 971-2-821370, TLX: (958) 23966

Uruguay ●
Coasin Uruguaya S.A.
Casilla de Correo 1400
Libertad 2529
Montevideo, Uruguay
Tel: 598-2-789204, 789015
TLX: (398) UY23010 COAUR

USSR
Amtest Associates Ltd.
Amtest House
75-79 Guildford Street
Chertsey, Surrey KT16 9AS
England
Tel: 44-9328-68355, TLX: (851) 928855
FAX: 44-9328-61919

Venezuela ●
Coasin C.A.
Calle 9 Con Calle 4, Edif Edinurbi
Apartado de Correos NR-70.136
Los Ruices
Caracas 1070-A, Venezuela
Tel: 58 (2) 241-03-09
TLX: (395) 21027 EMVEN VC

Yugoslavia ■
Amtest Associates Ltd.
Amtest House
75-79 Guildford Street
Chertsey, Surrey KT16 9AS
England
Tel: 44-9328-68355, TLX: (851) 928855
FAX: 44-9328-61919

■ Supplied and Supported by —
Fluke (Holland) B.V.
P.O. Box 2269
5600 CG Eindhoven
The Netherlands
Tel: (040) 45805, TLX: (844) 51846
FAX: 31-40-457515

● Supplied and Supported by —
Fluke International Corporation
P.O. Box C9090
Everett, WA 98206 U.S.A.
Tel: (206) 356-5500
TLX: 185103 FLUKE UT
FAX: 206-356-5116

The following countries are represented by:
Fluke (Holland) B.V.
P.O. Box 2269
5600 CG Eindhoven
The Netherlands
Tel: (040) 45805, TLX: 51846
FAX: 31-40-457515

Abu Dhabi
Afghanistan
Albania
Algeria
Angola
Benin
Bornholm
Botswana
Chad
Corsica
Czechoslavakia
Dubai
Ethiopia
Guinea
Ibiza
Iceland
Iraq
Kuwait
Liberia
Libya
Luxembourg
Maderia
Mallorca
Mauritania
Menorca
Mongolia
Niger
Nigeria
Qatar
Rodhos
Russia
Sardinia
Saudia Arabia
Scotland
Senegal
Sierra Leone
Somalia
Togo
Upper Volta
Wales
Wstn Sahara
Yemen
Zaire
Zambia
Zimbabwe

FLUKE®

TECHNICAL SERVICE CENTERS

U.S.A.

CA, Burbank
John Fluke Mfg. Co., Inc.
(213) 849-4641

CA, Santa Clara
John Fluke Mfg. Co., Inc.
(408) 727-8121

CO, Denver
John Fluke Mfg. Co., Inc.
(303) 695-1000

FL, Orlando
John Fluke Mfg. Co.,Inc.
(305) 896-4881

IL, Palatine
John Fluke Mfg. Co., Inc.
(312) 705-0500

MD, Rockville
John Fluke Mfg. Co.,Inc.
(301) 770-1576

NJ, Paramus
John Fluke Mfg. Co., Inc.
(201) 262-9550

TX, Dallas
John Fluke Mfg. Co., Inc.
(214) 869-0311

WA, Seattle
John Fluke Mfg. Co., Inc.
(206) 356-5560

Other Countries

Argentina, Buenos Aires
Coasin S.A.
Tel: 552-5248
TLX: (390) 22284

Australia, Brisbane
Elmeasco Instruments Pty. Ltd.
Tel: 552-5248

Australia, Concord
Elmeasco Instruments Pty Ltd.
Tel: 736-2888
TLX: (790) AA25887

Australia, Ringwood
Elmeasco Instruments Pty. Ltd.
Tel: 879-2322
TLX: (790) AA36206

Austria, Vienna
Walter Rekirsch
Elektronische Gerate GmbH & Co.
Tel: 253626
TLX: (847) 134759

Belgium, Brussels
Fluke (Belgium) NV/SA
Tel: 2164090
TLX: (846) 26312

Brazil, Sao Paulo
Hi-Tek Eletronica Ltda.
Tel: 421-5477
TLX: (1391) 1171413

Canada, Calgary
Fluke Electronics Canada Inc.
Tel: (403) 291-5215
Fax: (403) 291-5219

Canada, Mississauga
Fluke Electronics Canada Inc.
Tel: (416) 890-7600
Fax: (416) 890-6866

Canada, Montreal
Fluke Electronics Canada Inc.
Tel: (514) 685-0022
Fax: (514) 685-0039

Canada, Ottawa
Fluke Electronics Canada Inc.
Tel: (613) 723-9453
Fax: (613) 723-9458

Chile, Santiago
Intronica Chile Ltda.
Tel: 232 1886
TLX: (332) 346351

China, Peoples Republic of
Instrimpex - Fluke Service Center
Tel: 65-7281

Colombia, Bogota
Sistemas E Instrumentacion, Ltda.
Tel: 232-4532
TLX: (396) 45787

Denmark, Ballerup
Tage Olson A/S
Tel: 658111
TLX: (855) 35293

Ecuador, Quito
Proteco Coasin Cia., Ltda.
Tel: 526759
TLX: (393) 2865

Egypt and Sudan
Electronic Engineering Liaison Ofc
Tel: 2455705
TLX: (927) 22782

England, Chertsey, Surrey
Amtest Associates, Ltd
Tel: 68355

England, Watford, Herts
Fluke (Great Britain) Ltd
Tel: 40511
TLX: (851) 934583

Finland
Instrumentarium Elektronikka
Tel: 358-0-5281
TLX: (857) 124426

France
M.B. Electronique S.A.
Tel: 1-39-56-81-31
TLX: (842) 695414

Greece, Athens
Hellenic Scientific Representations
Tel: 7211140
TLX: (863) 219330

Hong Kong, Wanchai
Schmidt & Co (H.K.) Ltd.
Tel: 8330-222
TLX: (780) 74766

India, Bangalore
Hinditron Services Pvt. Ltd.
Tel: 363139
TLX: (953) 845741

India, Bombay
Hinditron Services Pvt. Ltd.
Tel: 6300043
TLX: (953) 11-72247

India, New Delhi
Hinditron Services Pvt. Ltd.
Tel: 6433675
TLX: (953) 316458

India, Secunderbad
Hinditron Services Pvt. Ltd.
Tel: 821117
TLX: (953) 1556973

Indonesia, Jakarta Pusat
P.T. Lamda Triguna
Tel: 8195365
TLX: 46171 LAYARIA

Israel, Tel Aviv
R.D.T. Electronics Engineering Ltd.
Tel: 483211
TLX: (922) 371452

Italy, Milan
Sistrel S.p.A.
Tel: 6181893
TLX: (843) 334643

Japan, Tokyo
John Fluke Mfg. Co., Inc.
Japan Branch
Tel: 434-0181
TLX: (781) 242-4331

Korea, Republic of
Myoung Corp.
Tel: 784-9942
TLX: MYOUNG K24283

Malaysia, Selangor
Mecomb Malaysia Sdn. Bhd.
Tel: 3-743422
TLX: (784) MA37764

Mexico
Mexicana de Electronica
Industrial, S.A. (Mexel)
Tel: 5-660-4323
TLX: (383) 1771038

Netherlands, Tilburg
Fluke (Nederland) B.V.
Tel: 352455
TLX: (844) 52683

New Zealand, Auckland
Northrop Instruments
& Systems Ltd.
Tel: 501-801
TLX: (791) NZ21570

New Zealand, Wellington
Northrop Instruments
& Systems Ltd.
Tel: 856-658
TLX: (791) NZ3380

Norway, Oslo
Morgenstierne & Co. A/S
Tel: 356110
TLX: (856) 71719

Pakistan, Karachi
International Operations (PAK), Ltd.
Tel: 221127, 239052
TLX: (952) 24494

Peru, Lima
Importaciones Y Representaciones
Electronicas S.A.
Tel: 288650
TLX: (394) 25663

Philippines
Spark Radio & Electronics Corp.
Tel: 2-775192
TLX: (722) 27901

Portugal, Lisboa
Equipamentos de Electronica e
Cientificos, SARL.
Tel: 2103420
TLX: (832) 15515

Republic of Singapore
Rank O'Connor's (PTE) Limited
Tel: 4737944
TLX: (786) RS21023

Republic of South Africa, Bramley
Protea PNI
Tel: 11-786-3647
TLX: (960) 4-24409

Spain, Madrid
Equipos y Sistemas S.A.
Tel: 458-0150
TLX: (831) 42856

Sweden, Vallingby
Kaliber AB
Tel: 380350
TLX: (854) 14077

Switzerland, Zurich
Traco Electronic AG
Tel: 2010711
TLX: (845) 815570

Taiwan, Taipei
Schmidt Electronics Corp.
Tel: 5013468
TLX: (785) 11111

Thailand, Bangkok
Measuretronix Ltd.
Tel: 374-2516
TLX: (788) 82796

Turkey, Istanbul
Erkman Elektronik Aletler
Tel: 441546
TLX: (821) 24399

Uruguay, Montevideo
Coasin Uruguaya S.A.
Tel: 789015
TLX: (398) UY23010

Venezuela, Caracas
Coasin C.A.
Tel: 241-0309
TLX: (395) 21027

West Germany, Ismaning/Munich
Fluke (Deutschland) GmbH
Tel: 9605240
TLX: (841) 0522472

FLUKE®

John Fluke Mfg. Co., Inc., P.O. Box C9090, Everett, WA 98206
Fluke (Holland) B.V., P.O. Box 2269, 5600 CG, Eindhoven, The Netherlands. Phone (040) 458045
Litho in U.S.A. 11/87

Section 8
Schematic Diagrams

FIGURE NO.	NAME	DRAWING NO.	PAGE
8-1	DC Voltage Standard (3 sheets)	332B-1001	8-3
8-2	Support Module Assemblies (2 sheets)	332B-1002	8-6
8-3	A2 Sample String	332B-1003	8-8
8-4	Power Distribution Assemblies	332B-1004	8-9



NOTES:
1. RESISTANCE IN OHMS, AND CAPACITANCE IN MICROFARADS UNLESS OTHERWISE SPECIFIED
2. ▼ FACTORY SELECTED COMPONENT
3. ⊘ INTERNAL ADJUSTMENT
4. ▷ FLAG NOTES WITH SAME NUMBERS ARE CONNECTED. FLAGS WITHOUT TO OR FROM INFORMATION ARE LOCATED ON SAME SHEET

CHANGES:
1. ADDED AT S/N 178 AND ON
2. CR15 ADDED AT S/N 179 AND ON
3. R4 WAS 360Ω, R5 WAS 270K; S/N 123 THRU 187.
4. A5A2R21 WAS 220Ω; A7A2R8 WAS 430Ω FOR S/N 123 THRU 355.
5. A7A1C4 DELETED, A7A1R4 DELETED, A7A1R42 REPLACED WITH BUSS WIRE, S/N 356, 758, 368, 369, 376 AND UP.
6. MODIFIED ASSEMBLY ON 332B/AF
7. A7C10 CHANGED TO 1μF ON 332B/AF

FIGURE 8-1. (1 of 3) DC VOLTAGE STANDARD (332B-1001)



FIGURE 8-1. (2 of 3) DC VOLTAGE STANDARD (332B-1001)



FIGURE 8-1. (3 of 3) DC VOLTAGE STANDARD (332B-1001)



NOTES:

1. RESISTANCE IN OHMS AND CAPACITANCE IN MICROFARADS UNLESS OTHERWISE SPECIFIED.
2. ▷ FLAGS WITH SAME NUMBER ARE CONNECTED.
3. * FACTORY SELECTED COMPONENT.
4. ⊘ INTERNAL ADJUSTMENT

CHANGES:

1. A5A3 C5 INCLUDED IN S/N 188 THRU 307, 309, 311, 314, 316, 317, 319, 320, 322, 324, 330, 331, & 335.
2. A5A1C1 ADDED TO S/N 270, 273, 283, 284, 287-296, 298, 300-302, 305, 306 & ON.
3. A5A3R30 CHANGED FROM 1K TO 1.5K AT S/N 366 & ON.
4. MODIFIED ASSEMBLY ON 332B/AF.

FIGURE 8-2. (1 of 2) SUPPORT MODULE ASSEMBLIES (332B-1002)


A5A4, 4058, CHOPPER AMPLIFIER
AMPLIFIER
A5A3, 4057 DIFF. AMPL.
SEE DWG 332B-1002, SHT 1
A5A3, 4057 DIFFERENTIAL AMPLIFIER
SEE DWG 332B-1002 SHT 1
SYNCHRONOUS DEMODULATOR
270Hz OUTPUT FILTER
270Hz MULTIVIBRATOR
MOSFET CHOPPER
CHOPPER DRIVE ADJ
A5A5, 4059 AUXILIARY POWER SUPPLY
SEE DWG 332B-1004
NOT USED
0 REF
1ms/cm
NOTE: TEST VOLTAGES READ ONLY AFTER ADJUSTING TO OBTAIN WAVEFORMS WITH PINS 6 & 12 SHORTED, INSTRUMENT IN STBY, AND USING A 10:1 PROBE, AC COUPLED. READ TEST VOLTAGES WITH PINS 6 & 12 UNSHORTED, USING +SENSE AS COMMON, CURRENT LIMIT CONTROL CW, RANGE SET TO 10 (10 000 000 DIALED) AND BOTTOM INTERLOCK ON.
▽ NUMBERS IN COMMON SYMBOL INDICATE DIFFERENT COMMON POINTS.
A5A1, 4083, MASTER VOLTAGE REFERENCE
REFERENCE SUPPLY
NOTE: TEST VOLTAGES READ USING +SENSE AS COMMON AND 332B IN STANDBY OR OPERATE. REFERENCE VOLTAGE SHOULD APPROXIMATE VALUE WRITTEN ON BOARD WHITE TAG.
OVEN TEMPERATURE REGULATOR
OVEN HEATER (PART OF A3)
TO A4, RANGE CAL. ASSEMBLY, JUNCTION OF R1, R5, & R29 DWG 332B-1001, SHT 3
A5A5, 4059 AUXILIARY POWER SUPPLY
SEE DWG 332B-1004
A5A5 COMMON

NOTES:

SEE SHEET 1 FOR NOTES AND CHANGES.

FIGURE 8-2. (2 of 2) SUPPORT MODULE ASSEMBLIES (332B-1002)



NOTES:

1. RESISTANCE IN OHMS UNLESS OTHERWISE SPECIFIED.
2. ⊘ INTERNAL ADJUSTMENT.

FIGURE 8-3. A2 SAMPLE STRING (332B-1003)


A5A5, 4059, AUXILIARY POWER SUPPLY
A7A2 PREREGULATOR AC INPUT
SEE DWG 3328-1001, SHT 1
4060, A5A6 CURRENT LIMITER
4082, A7A2 PREREGULATOR
4061, A7A1, SERIES PASS ELEMENT
CHANGES:
NOTES:
1. RESISTANCE IN OHMS AND CAPACITANCE IN MICROFARADS UNLESS OTHERWISE SPECIFIED.
2. FLAGS WITH SAME NUMBERS ARE CONNECTED. FLAGS WITHOUT TO OR FROM INFORMATION ARE LOCATED ON SAME SHEET.
3. INTERNAL ADJUSTMENT.

FIGURE 8-4. POWER DISTRIBUTION ASSEMBLIES (332B-1004)

www.manualsplus.com
1028704

SE Laboratories
LOC. GG1
MAN – 06387